



NYISO Wind Integration Study Status Report

John Adams
New York Independent System Operator

MIWG, TPAS & SOAS October Monthly Meetings
Second Draft 10/8/08
For Discussion Purposes Only

Agenda

- I. Status of NYISO Wind Study Tasks**
- II. Summer 2008 Wind Plant Performance Statistics**
- III. Review of the European Experience and Other Studies**
- IV. Current Task Activity**
- V. Other Wind Study Activities**
 - *NERC IVGTF*
 - *Eastern Interconnection Wind integration Study*

NYISO Study Tasks

- 1. Develop study assumptions**
 - 1. Select study years,***
 - 2. Develop wind generator penetration forecast,***
 - 3. MW output profile, and***
 - 4. MW load profile.***
- 2. Develop and implement performance monitoring for operating wind generators.**
- 3. Review other regions' experience with wind generators.**

NYISO Study Tasks (cont.)

- 4. Study the impacts on system operations of wind generators at various future levels of installed MW for the selected study years.**
- 5. Evaluate the impact of the higher penetration of wind generation on system planning and the need for transmission infrastructure from a thermal, voltage and stability perspective.**
- 6. Evaluate the impact of the higher penetration of wind generation on energy production by fuel types, LBMP/Congestion, reserve, regulation, load following costs and including the impact of selected facility outages on system operations as well as transmission expansion for future years.**

Summary of Task Status


Task	Begins	Analysis Completed
1	In progress	Complete
2	In progress	Complete
3	In progress	Complete
4	May	Nov./Dec.
5	June	Nov./Dec.
6	June	Nov./Dec.

Wind Plant Performance Report

- ♦ Tracks the performance of wind plants by months on a daily basis for key metrics such as maximum coincident wind plant output, total output at the time of the system peak, Mwh generated, capacity factor, etc.


Existing Wind Farms

*As of
April 2008*




Performance Report (cont.)

Average Day - June



Performance Report (cont.)

Average Day - July



Simulated In 2004 – 05 Wind Study





Figure 2.3 Average hourly output for all 101 wind sites and NYCA average load for July


Performance Report (cont.)

Average Day - August




Performance Report (cont.)

Average Day - September



Performance Report (cont.)


Peak Day - June



Performance Report (cont.)


Peak Day - July

Hourly Load vs Hourly Wind Output for the Peak Day of the Month




Performance Report (cont.)

Peak Day - August




Performance Report (cont.)

Peak Day - September




Performance Report (cont.)

Hourly Output Duration Curve - July



Performance Report (cont.)

Distribution of June Through September Daily Capacity Factors



Performance Report (cont.)

Other Statistics

Month	Nameplate Total MW	Average ¹ Capacity Factor	Peak Hour Coincidence Factor (CF) ^{2,3}	Max 1 HR Output MW	Number Of Days with Hrs < 0
<i>June</i>	706	20.1%	39.3%	453.8	1
<i>July</i>	706	16.5%	38.2%	508.8	8
<i>August</i>	706	11.6%	35.8%	433.8	7 ⁴
<i>September</i>	706	13.5%	0.0%	528.6	10

- 1) The overall average capacity factor for the four summer months was 15.4%
- 2) CF is the ratio of wind plant output at the system peak hour to nameplate
- 3) Capacity value for wind plant is defined as the capacity factor between the hours of 1400 and 1800 for the summer months of June, July and August. Summer 2008 value was 16.7%.
- 4) Had one day where the aggregate output for the entire day was less than zero

Simulated In 2004 – 05 Wind Study





Figure 2.2 Average monthly capacity factor for all 101 wind sites and NYCA monthly peak load


Performance Report (cont.)

- High Speed Cutout Event approx. 12 noon on 6/10/08 – Ramp up preceding the cutouts: 26% of nameplate to 61% of nameplate over 30 minutes. Ramp down from cutouts: To 5% of nameplate over 10 minutes. Ramp up after cutout event cleared: To 82% of nameplate over 45 minutes.




Performance Report (cont.)

System View for Full Day 6/10/08




Performance Report (cont.)

- Another High Speed Cutout Event occurred on 7/24/08 – Ramp up preceding the cutouts: 10% of nameplate to 65% of nameplate over approx. 30 minutes. Ramp down from cutouts: To 10% of nameplate over approx. 45 minutes. Ramp up after cutout event cleared: To 37% of nameplate over 10 minutes.



Performance Report (cont.)

System View for Full Day 7/24/08



Wind Plant Integration Issues

- ◆ **Transmission**
- ◆ **System Flexibility**
- ◆ **Operator Awareness and Practices**
 - *Forecasting*
- ◆ **Wind Generation Plant Performance & Standards**
 - *System Models*

Experience with Wind Plants Europe, U.S. & Canada

- ◆ **NYISO contracted with European Consultant to update the European Experience with Wind Generation – complete**
- ◆ **NYISO reviewed most recent studies conducted in California, Texas and the Province of Ontario**


Experience with Wind Plants Europe, U.S. & Canada (cont.)

- ◆ Overall conclusions from the above reviews include:
 - *The primary insights that can be drawn from the review of the European and other studies is first that higher levels of installed wind generation above the 3,300 MW from a system operation perspective are feasible.*
 - *To achieve the higher penetration will require implementation of enhancements to and extension of existing operating protocols, procedures and reliability standards.*
 - *The major areas of ongoing concern that are common across all regions tend to focus on:*
 - Will there be sufficient transmission infrastructure to integrate the higher penetrations of wind?
 - Will sufficient resources be available when the higher penetration of wind generation are achieved to provide the operational flexibility that will be needed with higher penetration of variable generation?
 - Validation of wind turbine models needed for system studies.

Impact of Wind Plants on System Operations

- ◆ The NYISO is conducting a study to evaluate the impacts on system operations of penetration of installed wind plants above 3,300 MWs.
 - *One of the key questions that this study will address is: “What is the impact of wind variation on the intrinsic load variability already experienced by the New York Control Area?” Power systems are dynamic, existing in a continuously changing environment, and are impacted by factors that change from second-to-second, minute-to-minute, hourly, seasonally and year-to-year.*
- ◆ The analysis of system variability for various time scales from minutes to hours is being undertaken to assess the impact on such operating parameters as regulation, load following, operating reserves, ramping, and scheduling.
- ◆ AWS Truewind is developing the wind plant output based on 2004 through 2006 weather. Load models with one minute integrated demands have been developed.

System Parameters & Their Time Scales



Example of System Variance Report

Variance Report 1: July 2008 Week Days System 5 Minute Data

Month	TypeName	Time_Period	_FREQ_	Mean_Value	Delta_Mean_Value	Delta_Sigma	Max_Positive_Delta	Max_Negative_Delta	Three_Sigma_Value
July	Load	HB 00 – 05	1380	18095.2	-47.5	50.6	79.5	-227.7	151.7
July	Load	HB 06 – 11	1656	21749.2	113.3	56.6	319.6	-99.2	169.9
July	Load	HB 12 – 17	1656	26841.5	23.2	32.9	177.1	-95.1	98.7
July	Load	HB 18 – 23	1932	24681.4	-81.5	69.0	121.1	-358.3	207.1
July	Load	HB 06 – 09	1104	21847.2	136.2	50.1	319.6	-93.9	150.3
July	Load	HB 15 – 19	1380	26647.4	-36.4	48.7	79.7	-236.9	146.1
July	Wind	HB 00 – 05	1380	148.0	0.2	7.0	39.4	-47.0	20.9
July	Wind	HB 06 – 11	1656	102.8	-0.8	5.9	37.2	-66.8	17.8
July	Wind	HB 12 – 17	1656	120.5	0.4	8.3	60.7	-46.8	24.8
July	Wind	HB 18 – 23	1932	105.3	0.1	6.7	73.9	-43.9	20.2
July	Wind	HB 06 – 09	1104	96.4	-1.0	5.4	37.2	-29.7	16.3
July	Wind	HB 15 – 19	1380	109.6	-1.0	7.8	73.9	-42.5	23.4
July	Net_	HB 00 – 05	1380	17947.2	-47.7	50.9	85.1	-230.2	152.6
July	Net_	HB 06 – 11	1656	21646.4	114.2	57.7	328.2	-103.4	173.0
July	Net_	HB 12 – 17	1656	26721.0	22.8	33.4	175.0	-90.8	100.3
July	Net_	HB 18 – 23	1932	24576.1	-81.6	69.3	115.5	-357.2	207.9
July	Net_	HB 06 – 09	1104	21750.8	137.2	51.2	328.2	-94.9	153.7
July	Net_	HB 15 – 19	1380	26537.7	-35.4	48.7	82.8	-241.1	146.2

Pct_Sigma_Increase_With_Wind
0.60%
1.78%
1.64%
0.37%
2.26%
0.06%

Transmission Infrastructure Needs

- ◆ The NYISO will evaluate the impact of the higher penetration of wind generation on system planning from a thermal, voltage and stability perspective as well as the need for additional transmission infrastructure to support higher penetrations of wind.
 - *The study will use the RNA 2009-2013 case as the study base case.*
 - *The analysis will be conducted with 4,250 MW of nameplate installed wind.*
 - *Assumed wind plant output is 20% of nameplate for peak load case and 80% for min load case*
 - *The location of the wind plants will be determined by the NYISO interconnection queue in queue order.*
 - *A summer and winter peak case will be evaluated as well as a maximum wind output case under light load conditions.*
 - *The analysis will be repeated as determined from the results of the 4,250 MW case for 6,000 MW.*
- ◆ Because of the potential impact of wind plants on the New York and New England power systems coming on line by the end of 2008 in the Moses-Willis-Plattsburgh transmission corridor (a.k.a., the North Country Wind Farms), the NYISO is involved in a near term operational planning transmission study. This study is jointly being undertaken with New York and New England transmission owners and ISO-NE. This study is evaluating the integration of 408 MW of wind generation into the grid in that part of the system.

Production & Transmission Impacts of Wind Generation

- ♦ The study will evaluate the impact of the higher penetration of wind generation on electricity production by fuel types, LBMP, reserve, regulation, load following costs, etc. Also, the study will evaluate the impact of selected facility outages on system operations for future years. The overall objective is to evaluate the cost impact on system operations that result from the higher penetration of wind plants.
- ♦ This analysis will evaluate the impacts of transmission limitations and upgrades on congestion and electricity production by fuel type for much higher penetrations of wind plants above that studied in the 2004 Study (3,300 MW).

Other Studies

NERC IVGTF

- ♦ The NYISO is participating in the **North America Electric Reliability Council's Integration of Variable Generation Task Force**. In December 2007 in anticipation of the growth of wind and other variable generation, NERC's Planning and Operating Committees created the Integration of Variable Generation Task Force.
- ♦ Task Force charged with preparing a report to include:
 - 1) *philosophical and technical considerations for integrating variable resources into the Interconnection, and*
 - 2) *specific recommendations for practices and requirements, including reliability standards that cover the planning, operations planning, and real-time operating timeframes.*
- ♦ Draft to NERC' Planning and Operating Committees due in September.

Other Studies

Eastern Interconnection Study

- ◆ The objective of the **Eastern Wind Integration and Transmission Study (EWITS)** being lead by **DOE/NREL (National Renewable Energy Lab)** is to help stakeholders, including regional utilities and transmission operators, to understand the costs and operating impacts of significant amounts of wind power on their grids and to help them in future transmission planning.
- ◆ NYISO is a member of the Technical Review Committee (TRC) organized by NREL
- ◆ Study years are 2018 and 2024.
- ◆ Preliminary work completed by MISO and Contractors as part of the Joint Coordinated System Plan (JCSP) which consist of MISO, PJM, SPP and TVA.
- ◆ Preliminary results for the 20% scenarios indicates that west to east transfer capability in the eastern interconnection will have to be increased two to three fold to accommodate 20% wind.
- ◆ Secondary goal is to test the theory that it makes more sense to build wind in areas with high capacity factors and deliver it to load areas than to build wind plants with low capacity factors closer to load centers.
- ◆ Issue – Who pays for the transmission?
- ◆ Final report expected to be available in approximately one year from now.

Other Studies

Eastern Interconnection Study

- ◆ The work will consist of seven tasks:
 1. Examine high levels of wind penetration and answer specific stakeholder and TRC issues.
 2. Model a baseline assessment for the wind integration study area footprint without new wind (5% reference case).
 3. Conduct detailed transmission planning analysis for the entire Eastern Interconnect for the 20% and 30% wind energy penetration scenarios
 4. Model two high renewable scenarios based on a 20% and 30% wind energy penetration in the study footprint analyzing wind integration within the wind integration study area footprint.
 5. Model two variations based on the 20% wind and/or the 30% wind energy penetration scenario analyzing wind integration within the wind integration study area footprint to answer specific TRC issues
 6. Conduct effective load carrying capacity (ELCC) and loss of load probability (LOLP) analysis on four high penetration wind scenarios within the wind integration study area footprint.
 7. Prepare Draft and Final Reports.



The New York Independent System Operator (NYISO) is a not-for-profit corporation that began operations in 1999. The NYISO operates New York's bulk electricity grid, administers the state's wholesale electricity markets, and provides comprehensive reliability planning for the state's bulk electricity system.

www.nyiso.com