

NEXtera Energy- TO36 Core 1		
REVISION: 1		
NEXtera Energy- TO36 Core 1 -DIRECT COST		
Substation Direct Costs		Total Each Segment
Direct Labor, Material & Equipment Costs	1. Station 29 New Ruland Road 345kv Substation	\$ 54,287,315
Direct Labor, Material & Equipment Costs	2.Station 252 New East Garden City 345 Substation	\$ 169,585,051
Direct Labor, Material & Equipment Costs	3.Station 48 Valley Stream 345/138 kV Substation Upgrades	\$ 78,638,755
Direct Labor, Material & Equipment Costs	4.Barrett 138 kV Substation Upgrades	\$ 41,509,967
Direct Labor, Material & Equipment Costs	5.Dunwoodie 345 kV GIS Substation	\$ 38,003,264
Direct Labor, Material & Equipment Costs	6.Elwood 138 kV Substation Upgrades	\$ 4,224,612
Direct Labor, Material & Equipment Costs	7.Jamaica 138 kV Substation Upgrades	\$ 1,095,138
Direct Labor, Material & Equipment Costs	8.Newbridge 345/138 kV GIS Substation Upgrades	\$ 53,527,289
Direct Labor, Material & Equipment Costs	9.Rainey 345kV GIS Substation Upgrades	\$ 25,813,520
Direct Labor, Material & Equipment Costs	10.Shore Road 138kV Substation Upgrades	\$ 7,453,423
Direct Labor, Material & Equipment Costs	11.Sprain Brook 345kV Substation Expansion	\$ 322,019,268
Direct Labor, Material & Equipment Costs	12. Existing Ruland Road 138 kV Substation Upgrade	\$ 1,077,395
Direct Labor, Material & Equipment Costs	13.Exisitng East Garden City 138 kV Substation Upgrades	\$ 15,046,417
SUBTOTAL (Costs):		\$ 812,281,414
CONTRACTOR MARK-UP (OH&P)		\$ 130,676,655
SUBTOTAL (AFTER MU):		\$ 942,958,069
CONTINGENCY ON ENTIRE PROJECT		\$ 188,591,614
Substation TOTAL:		\$ 1,131,549,683
Transmission Line Direct Costs		Total Each Segment
Direct Labor, Material & Equipment Costs	Comp 4 - Dunwoodie To New Rochelle Landing 345kV Onshore UG Cables -single circuit(EGC To Dunwoodie 345 kV)	\$ 106,106,649
Direct Labor, Material & Equipment Costs	Comp 4C - Sprain Brook To New Rochelle Landing Onshore 345kV UG Cables -Dobule circuits(EGC To Sprain Brook 345 kV / Ruland To Sprain Brook 345 kV)	\$ 195,310,866
Direct Labor, Material & Equipment Costs	Comp 17. New Rochelle Landing to Hempstead Harbor Landing (Shore Road) 345kV Offshore Submarine Cables - Three circuits (three lines, single circuit each) EGC-Dunwoodie 345KV / EGC-SprainBrook 345KV/ Ruland-SprainBrook 345KV	\$ 424,887,357
Direct Labor, Material & Equipment Costs	Comp 3A - East Garden City To Hempstead Harbor Landing 345kV Onshore UG Cables -Double circuits(EGC To Sprain Brook 345 kV / EGC To Ruland 345 kV)	\$ 217,033,473
Direct Labor, Material & Equipment Costs	Comp 5 - Ruland To Hempstead Harbor Landing (Shore Road) 345kV Onshore UG Cables -Single circuit(Ruland To Sprain Brook 345 kV)	\$ 196,661,987
Direct Labor, Material & Equipment Costs	Comp 10A - East Graden City To Valley Stream 345kV Onshore UG Cables -Triple circuits	\$ 222,396,395
Direct Labor, Material & Equipment Costs	Comp 8C - Rebuild: East Garden City - Newbridge 345kV Onshore UG Cables -Double circuits	\$ 75,390,181
Direct Labor, Material & Equipment Costs	Comp 13A - Syosset - Oakwood 138 kV Onshore UG Cables -Single circuit	\$ 14,061,400
Direct Labor, Material & Equipment Costs	Comp 13B - Syosset - Greenlawn 138 kV Onshore UG Cables -Single circuit	\$ 14,061,400
Direct Labor, Material & Equipment Costs	Comp 113 - Jamaica to East Garden City 138kV Onshore UG Cables -Single circuit	\$ 130,556,641
Direct Labor, Material & Equipment Costs	Comp XX - Ruland Road - Newbridge138 kV #3 (567 Line) Onshore UG Cables -Single circuit	\$ 2,624,365
Direct Labor, Material & Equipment Costs	Other Comp. 138kV Upgrades	\$ 8,268,700
SUBTOTAL (Costs):		\$ 1,607,359,414
CONTRACTOR MARK-UP (OH&P)		\$ 289,324,695
SUBTOTAL (AFTER MU):		\$ 1,896,684,109
CONTINGENCY ON ENTIRE PROJECT		\$ 379,336,822
Transmission Line TOTAL:		\$ 2,276,020,931
NEXtera Energy- TO36 Core 1Total Direct Cost		\$ 3,407,570,613

NEXtera Energy- TO36 Core 1 -INDIRECT COST		
Substation Indirect Costs		Total Each Segment
Indirect Costs	1. Station 29 New Ruland Road 345kv Substation	\$ 15,736,579
Indirect Costs	2.Station 252 New East Garden City 345 Substation	\$ 79,716,796
Indirect Costs	3.Station 48 Valley Stream 345/138 kV Substation Upgrades	\$ 24,786,200
Indirect Costs	4.Barrett 138 kV Substation Upgrades	\$ 14,212,557
Indirect Costs	5.Dunwoodie 345 kV GIS Substation	\$ 9,740,565
Indirect Costs	6.Elwood 138 kV Substation Upgrades	\$ 1,387,563
Indirect Costs	7.Jamaica 138 kV Substation Upgrades	\$ 334,752
Indirect Costs	8.Newbridge 345/138 kV GIS Substation Upgrades	\$ 11,999,373
Indirect Costs	9.Rainey 345kV GIS Substation Upgrades	\$ 7,677,720
Indirect Costs	10.Shore Road 138kV Substation Upgrades	\$ 2,393,936
Indirect Costs	11.Sprain Brook 345kV Substation Expansion	\$ 99,114,306
Indirect Costs	12. Existing Ruland Road 138 kV Substation Upgrade	\$ 356,246
Indirect Costs	13.Exisitng East Garden City 138 kV Substation Upgrades	\$ 4,938,374
SUBTOTAL (Costs):		\$ 272,394,968
CONTRACTOR MARK-UP (OH&P)		\$ 49,031,094
SUBTOTAL (AFTER MU):		\$ 321,426,063
CONTINGENCY ON ENTIRE PROJECT		\$ 64,285,213
Substation TOTAL:		\$ 385,711,275
Transmission Line Indirect Costs		Total Each Segment
Indirect Costs	Comp 4 - Dunwoodie To New Rochelle Landing 345kV Onshore UG Cables -single circuit(EGC To Dunwoodie 345 kV)	\$ 27,103,560
Indirect Costs	Comp 4C - Sprain Brook To New Rochelle Landing Onshore 345kV UG Cables -Dobule circuits(EGC To Sprain Brook 345 kV / Ruland To Sprain Brook 345 kV)	\$ 49,373,632
Indirect Costs	Comp 17. New Rochelle Landing to Hempstead Harbor Landing (Shore Road) 345kV Offshore Submarine Cables - Three circuits (three lines, single circuit each)	\$ 101,825,530
Indirect Costs	Comp 3A - East Garden City To Hempstead Harbor Landing 345kV Onshore UG Cables -Double circuits(EGC To Sprain Brook 345 kV / EGC To Ruland 345 kV)	\$ 55,307,165
Indirect Costs	Comp 5 - Ruland To Hempstead Harbor Landing (Shore Road) 345kV Onshore UG Cables -Single circuit(Ruland To Sprain Brook 345 kV)	\$ 50,420,274
Indirect Costs	Comp 10A - East Graden City To Valley Stream 345kV Onshore UG Cables -Triple circuits	\$ 56,015,535
Indirect Costs	Comp 8C - Rebuild: East Garden City - Newbridge 345kV Onshore UG Cables -Double circuits	\$ 18,760,576
Indirect Costs	Comp 13A - Syosset - Oakwood 138 kV Onshore UG Cables -Single circuit	\$ 3,945,883
Indirect Costs	Comp 13B - Syosset - Greenlawn 138 kV Onshore UG Cables -Single circuit	\$ 3,945,883
Indirect Costs	Comp 113 - Jamaica to East Garden City 138kV Onshore UG Cables -Single circuit	\$ 33,606,126
Indirect Costs	Comp XX - Ruland Road - Newbridge138 kV #3 (567 Line) Onshore UG Cables -Single circuit	\$ 1,157,351
Indirect Costs	Other Comp. 138kV Upgrades	\$ 3,645,378
SUBTOTAL (Costs):		\$ 405,106,891
CONTRACTOR MARK-UP (OH&P)		\$ 72,919,240
SUBTOTAL (AFTER MU):		\$ 478,026,132
CONTINGENCY ON ENTIRE PROJECT		\$ 95,605,226
Transmission Line TOTAL:		\$ 573,631,358
NEXtera Energy- TO36 Core 1 Total Indirect Cost		\$ 959,342,633
NEXtera Energy- TO36 Core 1 Total		\$ 4,366,913,246

NEXTera Energy- TO36 Core 1

1. Station 29 New Ruland Road 345kv Substation

Total: \$ 97,499,274

NEXTera Energy- TO36 Core 1				
	Material Supply	Labor Supply	Equip Supply	Total
1. Station 29 New Ruland Road 345kv Substation				
1. SITE PREP/ GRADING/ FENCING / CIVIL	\$ 1,237,904	\$ 967,768	\$ 556,064	\$ 2,761,736
2. SUBSTATION FOUNDATIONS	\$ 1,784,377	\$ 2,039,288	\$ 1,274,555	\$ 5,098,219
3. SUBSTATION STRUCTURES	\$ 725,707	\$ 520,606	\$ 307,182	\$ 1,553,495
4. MAJOR EQUIPMENT	\$ 20,829,008	\$ 5,933,406	\$ 3,767,864	\$ 30,530,278
5. LOW VOLTAGE & CONTROL CABLE	\$ 198,656	\$ 53,719	\$ 10,744	\$ 263,119
6. CONDUIT & CABLE TRENCH	\$ 3,855,740	\$ 2,142,022	\$ 1,153,533	\$ 7,151,296
7. GROUND GRID	\$ 126,601	\$ 90,776	\$ 20,936	\$ 238,314
8. CONTROL ENCLOSURE	\$ 3,148,429	\$ 2,577,294	\$ 965,135	\$ 6,690,858
9. MOB/DEMOB, ENGINEERING, PERMITTING, T&C, PM & INDIRECTS	\$ 3,235,738	\$ 9,109,210	\$ 3,391,631	\$ 15,736,579
Turnkey cost (HVDC, GIS)	\$ 5,745,000	\$ 3,447,000	\$ 2,298,000	\$ 11,490,000
Non-Turnkey cost	\$ 29,397,161	\$ 19,987,089	\$ 9,149,644	\$ 58,533,894
SUBTOTAL (Costs):	\$ 35,142,161	\$ 23,434,089	\$ 11,447,644	\$ 70,023,894
CONTRACTOR MARK-UP (OH&P)	\$ 5,636,189	\$ 3,804,496	\$ 1,784,816	\$ 11,225,501
SUBTOTAL:	\$ 40,778,350	\$ 27,238,585	\$ 13,232,460	\$ 81,249,395
CONTINGENCY ON ENTIRE PROJECT	\$ 8,155,670	\$ 5,447,717	\$ 2,646,492	\$ 16,249,879
TOTAL:	\$ 48,934,020	\$ 32,686,303	\$ 15,878,952	\$ 97,499,274

Description of Work: New greenfield 345 kV/138 kV Ruland Road Substation, and modification at exisitng 138kv Ruland station ( replace with two hybrid circuit breaker)

Item	Item Description	Estimated Quantity	Unit of Measure	Material Supply Rate	Labor Supply Rate	Const. Equipment Rate	Material Supply Cost	Labor Supply Cost	Const. Equipment Cost	TOTAL COST
1. Station 29 New Ruland Road 345kv Substation										
1. SITE PREP/ GRADING/ FENCING / CIVIL										
1.1	Site Clearing	3.5	ACRE	-	10,800.00	7,200.00	\$ -	\$ 37,800	\$ 25,200	\$ 63,000
1.2	Demolition	0	ACRE	-	-	-	\$ -	\$ -	\$ -	\$ -
1.3	New Access Road - 20'	3,149	SY	4.85	7.20	4.80	\$ 15,272	\$ 22,672	\$ 15,115	\$ 53,059
1.4	Strip and Dispose Top Soil	5,647	CY		24.50	10.50	\$ -	\$ 138,343	\$ 59,290	\$ 197,633
1.5	Site Grading- Excavation for Substation Pad	16,940	CY		9.00	6.00	\$ -	\$ 152,460	\$ 101,640	\$ 254,100
1.6	Site Grading- Excavation for Substation Pad-Rock excavation-Hauling and disposal	9,148	CY		21.00	9.00	\$ -	\$ 192,099.60	\$ 82,328.40	\$ 274,428.00
1.7	Site Grading- Fill for Substation Pad (site borrow, compacted in place)	13,721	CY		2.40	1.60	\$ -	\$ 32,931	\$ 21,954	\$ 54,886
1.8	Site Grading -Fill for Substation Pad (import, compacted in place)	9,148	CY	25.00	2.40	1.60	\$ 228,690	\$ 21,954	\$ 14,636	\$ 265,280
1.9	Blasting		EA				\$ -	\$ -	\$ -	\$ -
1.10	Install substation 8" pad base	16,940	SY	11.00	6.00	4.00	\$ 186,340	\$ 101,640	\$ 67,760	\$ 355,740
1.11	Site Surfacing - Aggregate 6" Thick	16,940	SY	16.50	4.50	3.00	\$ 279,510	\$ 76,230	\$ 50,820	\$ 406,560
1.12	7' Station Fence w/ Barbed Wire & Grounding	1,439	LF	13.85	13.85	6.92	\$ 19,927	\$ 19,927	\$ 9,964	\$ 49,818
1.13	20' Slide Gate & Grounding	1	EA	8,100.00	3,245.00	1,305.00	\$ 8,100	\$ 3,245	\$ 1,305	\$ 12,650
1.14	4' Pedestrian gate	1	EA	2,500.00	1,000.00	350.00	\$ 2,500	\$ 1,000	\$ 350	\$ 3,850
1.15	Storm drain-15" HDPE, INFILTRATION TRENCH, INLET and Hydrodynamic Separator	1	LS	446,976.00	115,200.00	76,104.00	\$ 446,976	\$ 115,200	\$ 76,104	\$ 638,280
1.16	Seeding	11,952	SF	1.50	1.50	1.00	\$ 17,928	\$ 17,928	\$ 11,952	\$ 47,808
1.17	Erosion Control-Silt fence install & remove	2,700	LF	2.41	3.16	0.72	\$ 6,507	\$ 8,532	\$ 1,944	\$ 16,983
1.18	Temporary fencing	1,800	LF	7.50	5.25	2.25	\$ 13,500	\$ 9,450	\$ 4,050	\$ 27,000
1.19	Substation entrance with asphalt	556	SY	19.50	26.00	19.50	\$ 10,833	\$ 14,444	\$ 10,833	\$ 36,111
1.20	Concrete curb	70	LF	26.00	27.30	11.70	\$ 1,820	\$ 1,911	\$ 819	\$ 4,550

Item	Item Description	Estimated Quantity	Unit of Measure	Material Supply Rate	Labor Supply Rate	Const. Equipment Rate	Material Supply Cost	Labor Supply Cost	Const. Equipment Cost	TOTAL COST
1.21	Retaining Wall	0	LF	156.00	117.00	117.00	\$ -	\$ -	\$ -	\$ -
TOTAL - SITE PREP/ GRADING/ FENCING / CIVIL							\$ 1,237,904	\$ 967,768	\$ 556,064	\$ 2,761,736
2. SUBSTATION FOUNDATIONS										
2.1	345kV, Lightning mast	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.2	345kV, A Frame 70'	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.3	345kV, Bus support-3 Ph	48	CY	703.89	804.44	502.78	\$ 33,449	\$ 38,227	\$ 23,892	\$ 95,567
2.4	345kV, Bus support-3 Ph, low	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.5	345kV, Bus support-1 Ph	119	CY	703.89	804.44	502.78	\$ 83,622	\$ 95,567	\$ 59,730	\$ 238,919
2.6	345kV, GIS air terminal	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.7	345kV, GIS support-1 Ph	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.8	345kV, GIS support-3 Ph	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.9	345kV, GIS Cable sealing end	109	CY	703.89	804.44	502.78	\$ 76,780	\$ 87,748	\$ 54,843	\$ 219,371
2.10	345kV, Cable sealing end	11	CY	703.89	804.44	502.78	\$ 7,532	\$ 8,608	\$ 5,380	\$ 21,519
2.11	345kV, CCVT	16	CY	703.89	804.44	502.78	\$ 11,297	\$ 12,911	\$ 8,070	\$ 32,278
2.12	345kV, Disconnect Switch	158	CY	703.89	804.44	502.78	\$ 111,495	\$ 127,423	\$ 79,640	\$ 318,558
2.13	345/138KV, Power Transformer with oil containment	656	CY	703.89	804.44	502.78	\$ 461,749	\$ 527,713	\$ 329,820	\$ 1,319,282
2.14	345kV, Shunt Reactor with oil containment-275MVAR	305	CY	703.89	804.44	502.78	\$ 214,685	\$ 245,354	\$ 153,346	\$ 613,386
2.15	345kV, Shunt Reactor with oil containment-100MVAR	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.16	345kV, Phase Angle Regulator with oil containment	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.17	345kV, Circuit Breaker	120	CY	703.89	804.44	502.78	\$ 84,466	\$ 96,533	\$ 60,333	\$ 241,332
2.18	345kV, Circuit Breaker (GIS), outdoor rated	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.19	345Kv, Control Enclosure-BLDG with generator pad	259	CY	703.89	804.44	502.78	\$ 182,306	\$ 208,350	\$ 130,219	\$ 520,875
2.20	345kV, Surge arrester	48	CY	703.89	804.44	502.78	\$ 33,892	\$ 38,734	\$ 24,209	\$ 96,834
2.21	138kV, Phase Angle Regulator with oil containment	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.22	138kV, Circuit Breaker, Hybrid circuit breaker	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.23	138kV, Bus support-3 Ph, low	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.24	138kV, Bus support-1 Ph, low	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.25	138kV, Disconnect Switch	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.26	138kV, Cable sealing end	24	CY	703.89	804.44	502.78	\$ 17,062	\$ 19,500	\$ 12,187	\$ 48,749
2.27	138kV, Surge arrester	32	CY	703.89	804.44	502.78	\$ 22,595	\$ 25,823	\$ 16,139	\$ 64,556
2.28	138kV, CCVT	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.29	138kV, A Frame 50'	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.30	Firewall Foundation	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.31	Precast Firewall for transformer, PARs, reactors	-	SF	25.00	15.00	10.00	\$ -	\$ -	\$ -	\$ -
2.32	Precast Concrete Piles-12"X80'	-	EA	18,000.00	3,200.00	2,800.00	\$ -	\$ -	\$ -	\$ -
2.33	Local Control Cabinet foundation	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.34	138kV, GIS Enclosure-BLDG & control room	630	CY	703.89	804.44	502.78	\$ 443,448	\$ 506,797	\$ 316,748	\$ 1,266,993
TOTAL - 345KV FOUNDATION							\$ 1,784,377	\$ 2,039,288	\$ 1,274,555	\$ 5,098,219
3. SUBSTATION STRUCTURES										
3.1	345kV, Lightning mast	0	EA				\$ -	\$ -	\$ -	\$ -
3.2	345kV, A Frame 70'	0	EA	48,100.00	28,860.00	19,240.00	\$ -	\$ -	\$ -	\$ -
3.3	345kV, Bus support-3 Ph	3	EA	8,346.00	5,758.74	3,839.16	\$ 25,038	\$ 17,276	\$ 11,517	\$ 53,832
3.4	345kV, Bus support-3 Ph, low	0	EA	8,346.00	5,758.74	3,839.16	\$ -	\$ -	\$ -	\$ -
3.5	345kV, Bus support-1 Ph	15	EA	4,810.00	2,886.00	1,924.00	\$ 72,150	\$ 43,290	\$ 28,860	\$ 144,300
3.6	345kV, GIS air terminal	0	EA	8,346.00	5,758.74	3,839.16	\$ -	\$ -	\$ -	\$ -
3.7	345kV, GIS support-1 Ph	0	EA	8,346.00	5,758.74	3,839.16	\$ -	\$ -	\$ -	\$ -
3.8	345kV, GIS support-3 Ph	0	EA	4,810.00	2,886.00	1,924.00	\$ -	\$ -	\$ -	\$ -
3.9	345kV, GIS Cable sealing end	9	EA	8,346.00	5,758.74	3,839.16	\$ 75,114	\$ 51,829	\$ 34,552	\$ 161,495
3.10	345kV, Cable sealing end	1	EA	8,346.00	5,758.74	3,839.16	\$ 8,346	\$ 5,759	\$ 3,839	\$ 17,944
3.11	345kV, CCVT	3	EA	4,810.00	2,886.00	1,924.00	\$ 14,430	\$ 8,658	\$ 5,772	\$ 28,860
3.12	345kV, Disconnect Switch	5	EA	19,240.00	11,544.00	7,696.00	\$ 96,200	\$ 57,720	\$ 38,480	\$ 192,400
3.13	138kV, Bus support-3 Ph, low	0	EA	4,173.00	2,879.76	1,919.84	\$ -	\$ -	\$ -	\$ -
3.14	138kV, Bus support-1 Ph, low	0	EA	2,782.00	1,919.84	1,279.89	\$ -	\$ -	\$ -	\$ -
3.15	138kV, Disconnect Switch	0	EA				\$ -	\$ -	\$ -	\$ -
3.16	138kV, Cable sealing end	2	EA	4,810.00	2,886.00	1,924.00	\$ 9,620	\$ 5,772	\$ 3,848	\$ 19,240
3.17	138kV, Surge arrester	6	EA	4,810.00	2,886.00	1,924.00	\$ 28,860	\$ 17,316	\$ 11,544	\$ 57,720
3.18	138kV, CCVT	0	EA	3,206.67	1,924.00	1,282.67	\$ -	\$ -	\$ -	\$ -
3.19	138kV, A Frame 50'	0	EA	33,000.00	19,800.00	13,200.00	\$ -	\$ -	\$ -	\$ -
3.20	AL. Bus Tubing, 5" SCH 80	750	LF	25.00	184.94	123.29	\$ 18,750	\$ 138,704	\$ 92,469	\$ 249,923
3.21	AL. Bus fittings	1	LS	22,500.00	22,500.00	11,250.00	\$ 22,500	\$ 22,500	\$ 11,250	\$ 56,250
3.22	Steel grating and support beams-transformer moat	129,840	LB	2.73	1.17	0.50	\$ 354,699	\$ 151,783	\$ 65,050	\$ 571,532
TOTAL - SUBSTATION STRUCTURES & GAS-INSULATED CONDUCTOR							\$ 725,707	\$ 520,606	\$ 307,182	\$ 1,553,495
4. MAJOR EQUIPMENT										

Item	Item Description	Estimated Quantity	Unit of Measure	Material Supply Rate	Labor Supply Rate	Const. Equipment Rate	Material Supply Cost	Labor Supply Cost	Const. Equipment Cost	TOTAL COST
4.1	345kV, Cable sealing end	3	EA	17,400.00	5,460.00	2,340.00	\$ 52,200	\$ 16,380	\$ 7,020	\$ 75,600
4.2	345kV, CCVT	3	EA	4,810.00	2,886.00	1,924.00	\$ 14,430	\$ 8,658	\$ 5,772	\$ 28,860
4.3	345kV, Disconnect Switch	5	EA	57,720.00	34,632.00	23,088.00	\$ 288,600	\$ 173,160	\$ 115,440	\$ 577,200
4.4	345/138KV, Power Transformer with oil containment	2	EA	5,020,000.00	3,520.00	880.00	\$ 10,040,000	\$ 7,040	\$ 1,760	\$ 10,048,800
4.5	Transport & Testing- Transformer	2	EA		777,400.00	514,600.00	\$ -	\$ 1,554,800	\$ 1,029,200	\$ 2,584,000
4.6	345kV, Shunt Reactor with oil containment-275MVAR	1	EA	3,332,488.00	3,520.00	880.00	\$ 3,332,488	\$ 3,520	\$ 880	\$ 3,336,888
4.7	345kV, Shunt Reactor with oil containment-100MVAR	0	EA		3,520.00	880.00	\$ -	\$ -	\$ -	\$ -
4.8	Transport & Testing- Shunt Reactor	1	EA		426,650.00	182,850.00	\$ -	\$ 426,650	\$ 182,850	\$ 609,500
4.9	345kV, Phase Angle Regulator with oil containment	0	EA		3,520.00	880.00	\$ -	\$ -	\$ -	\$ -
4.10	345kV, Circuit Breaker	2	EA	350,000.00	57,239.00	24,531.00	\$ 700,000	\$ 114,478	\$ 49,062	\$ 863,540
4.11	345kV, Circuit Breaker (GIS), outdoor rated	0	EA				\$ -	\$ -	\$ -	\$ -
4.12	345kV, Circuit Breaker (GIS), outdoor rated-Line surge Arrester ( 3phase)	0	EA				\$ -	\$ -	\$ -	\$ -
4.13	345kV, surge Arrester	6	EA	6,669.00	5,460.00	2,340.00	\$ 40,014	\$ 32,760	\$ 14,040	\$ 86,814
4.14	138kV, Phase Angle Regulator with oil containment	0	EA		3,520.00	880.00	\$ -	\$ -	\$ -	\$ -
4.15	Transport & Testing- Phase Angle Regulating Transformer, 138kV	0	EA		15,400.00	6,600.00	\$ -	\$ -	\$ -	\$ -
4.16	138kV, Gas Insulated Switchgear, BAAH Arrangement	12	BKR	478,750.00	287,250.00	191,500.00	\$ 5,745,000	\$ 3,447,000	\$ 2,298,000	\$ 11,490,000
4.17	138kV, Circuit Breaker, Hybrid circuit breaker	0	EA	920,000.00	13,559.00	5,811.00	\$ -	\$ -	\$ -	\$ -
4.18	138kV, Disconnect Switch	0	EA		3,958.50	1,696.50	\$ -	\$ -	\$ -	\$ -
4.19	138kV, Cable sealing end	6	EA	11,600.00	5,460.00	2,340.00	\$ 69,600	\$ 32,760	\$ 14,040	\$ 116,400
4.20	138kV, CCVT	0	EA		7,970.08	3,415.75	\$ -	\$ -	\$ -	\$ -
4.21	138kV, Surge arrester	6	EA	4,446.00	4,200.00	1,800.00	\$ 26,676	\$ 25,200	\$ 10,800	\$ 62,676
4.22	Station service transformers- 120/208v-250VA	2	EA	260,000.00	45,500.00	19,500.00	\$ 520,000	\$ 91,000	\$ 39,000	\$ 650,000
4.23	345kV Gas-Insulated Bus Conductor	0	LF	550.00	275.00	82.50	\$ -	\$ -	\$ -	\$ -
4.24	345kV Gas-Insulated Bus Conductor-elbow	0	EA	2,500.00	1,250.00	375.00	\$ -	\$ -	\$ -	\$ -
4.25	Transport & Testing- GIL	0	LS		-	-	\$ -	\$ -	\$ -	\$ -
							\$ -	\$ -	\$ -	\$ -
TOTAL - MAJOR EQUIPMENT							\$ 20,829,008	\$ 5,933,406	\$ 3,767,864	\$ 30,530,278
5. LOW VOLTAGE & CONTROL CABLE										
5.1	Control Cables	37,500	LF	5.30	1.43	0.29	\$ 198,656	\$ 53,719	\$ 10,744	\$ 263,119
5.2			LF		-	-	\$ -	\$ -	\$ -	\$ -
TOTAL - LOW VOLTAGE & CONTROL CABLE							\$ 198,656	\$ 53,719	\$ 10,744	\$ 263,119
6. CONDUIT & CABLE TRENCH										
6.1	Conduit, PVC, 6", SCH 40		LF	20.70	13.28	6.64	\$ -	\$ -	\$ -	\$ -
6.2	Conduit, PVC, 4", SCH 40	6,750	LF	11.15	10.80	5.40	\$ 75,263	\$ 72,900	\$ 36,450	\$ 184,613
6.3	Conduit, PVC, 3", SCH 40		LF	8.10	10.80	5.40	\$ -	\$ -	\$ -	\$ -
6.4	Conduit, PVC, 2", SCH 40		LF	3.95	10.80	5.40	\$ -	\$ -	\$ -	\$ -
6.5	Conduit, PVC, 1", SCH 40		LF	1.90	10.80	5.40	\$ -	\$ -	\$ -	\$ -
6.6	Cable Trench	1,275	LF	266.50	53.04	13.26	\$ 339,788	\$ 67,626	\$ 16,907	\$ 424,320
6.7										
6.8	138kV UG- Conduit	3,499	LF	266.73	202.15	100.00	\$ 933,291	\$ 707,311	\$ 349,917	\$ 1,990,519
6.9	138kV UG- Cable	11,022	LF	145.00	87.00	58.00	\$ 1,598,168	\$ 958,901	\$ 639,267	\$ 3,196,337
6.10	138kV UG- Termination	30	EA	27,805.00	9,846.48	2,813.28	\$ 834,150	\$ 295,394	\$ 84,398	\$ 1,213,943
6.13	Fiber Optic Cable	3,674	LF	7.40	3.33	2.22	\$ 27,176	\$ 12,236	\$ 8,158	\$ 47,570
6.14	Ground Continuity Conductor	3,674	LF	13.04	7.53	5.02	\$ 47,905	\$ 27,654	\$ 18,436	\$ 93,994
6.11							\$ -	\$ -	\$ -	\$ -
TOTAL - CONDUIT & CABLE TRENCH							\$ 3,855,740	\$ 2,142,022	\$ 1,153,533	\$ 7,151,296
7. GROUND GRID										
7.1	Cable, 4/0 AWG Bare Copper, 7 Strand Ground Conductor	12,705	LF	2.09	3.42	1.46	\$ 26,566	\$ 43,391	\$ 18,596	\$ 88,554
7.2	Caweld, DSA, 4/0 , T, CROSS	351	EA	165.00	75.00		\$ 57,915	\$ 26,325	\$ -	\$ 84,240
7.3	Ground Rod, 3/4" x 15'	312	EA	135.00	67.50	7.50	\$ 42,120	\$ 21,060	\$ 2,340	\$ 65,520
TOTAL - GROUND GRID							\$ 126,601	\$ 90,776	\$ 20,936	\$ 238,314
8. CONTROL ENCLOSURE										
8.1	345kv Control Bldg	1	EA	407,211.00	285,047.70	122,163.30	\$ 407,211	\$ 285,048	\$ 122,163	\$ 814,422
8.2	138kv GIS/Control Bldg	1	EA	1,145,280.92	801,696.65	343,584.28	\$ 1,145,281	\$ 801,697	\$ 343,584	\$ 2,290,562
8.3	Primary Line Relays (87L): SEL-411L	7	EA	21,328.12	17,062.49	4,265.62	\$ 149,297	\$ 119,437	\$ 29,859	\$ 298,594
8.4	Backup Line Relays (87L): GE L90	7	EA	21,328.12	17,062.49	4,265.62	\$ 149,297	\$ 119,437	\$ 29,859	\$ 298,594
8.5	Primary Bay Control: SEL-451	5	EA	21,328.12	17,062.49	4,265.62	\$ 106,641	\$ 85,312	\$ 21,328	\$ 213,281
8.6	Backup Bay Control: SEL-451	5	EA	21,328.12	17,062.49	4,265.62	\$ 106,641	\$ 85,312	\$ 21,328	\$ 213,281
8.7	Primary Transformer/Reactor/PAR Differential Relays: SEL-487E	3	EA	21,328.12	17,062.49	4,265.62	\$ 63,984	\$ 51,187	\$ 12,797	\$ 127,969
8.8	Backup Transformer/Reactor/PAR Differential Relays: GE T60	3	EA	21,328.12	17,062.49	4,265.62	\$ 63,984	\$ 51,187	\$ 12,797	\$ 127,969
8.9	Primary Bus Differential Relays: SEL-487B	2	EA	21,328.12	17,062.49	4,265.62	\$ 42,656	\$ 34,125	\$ 8,531	\$ 85,312
8.10	Backup Bus Differential Relays: GE B90	2	EA	21,328.12	17,062.49	4,265.62	\$ 42,656	\$ 34,125	\$ 8,531	\$ 85,312
8.11	RTU Panel A: SEL-2240 Axion, SEL-2730M ENET SW., SEL-2407 GPS, Modem, SEL-2523 Annunc	1	EA	12,500.00	10,000.00	2,500.00	\$ 12,500	\$ 10,000	\$ 2,500	\$ 25,000
8.12	RTU Panel B: SEL-2730M Ethernet Switch, SEL-2407 GPS Clock, SEL-2523 Annunciator	1	EA	12,500.00	10,000.00	2,500.00	\$ 12,500	\$ 10,000	\$ 2,500	\$ 25,000
8.13	HMI Panel	1	EA	12,500.00	10,000.00	2,500.00	\$ 12,500	\$ 10,000	\$ 2,500	\$ 25,000
8.14	Primary Line Relays (87L): SEL-411L	3	EA	21,328.12	17,062.49	4,265.62	\$ 63,984	\$ 51,187	\$ 12,797	\$ 127,969
8.15	Backup Line Relays (87L): GE L90	3	EA	21,328.12	17,062.49	4,265.62	\$ 63,984	\$ 51,187	\$ 12,797	\$ 127,969



Item	Item Description	Estimated Quantity	Unit of Measure	Material Supply Rate	Labor Supply Rate	Const. Equipment Rate	Material Supply Cost	Labor Supply Cost	Const. Equipment Cost	TOTAL COST
8.16	Primary Bay Control: SEL-451	1	EA	21,328.12	17,062.49	4,265.62	\$ 21,328	\$ 17,062	\$ 4,266	\$ 42,656
8.17	Backup Bay Control: SEL-451	1	EA	21,328.12	17,062.49	4,265.62	\$ 21,328	\$ 17,062	\$ 4,266	\$ 42,656
8.18	Primary Bus Differential Relays: SEL-487B	1	EA	21,328.12	17,062.49	4,265.62	\$ 21,328	\$ 17,062	\$ 4,266	\$ 42,656
8.19	Backup Bus Differential Relays: GE B90	1	EA	21,328.12	17,062.49	4,265.62	\$ 21,328	\$ 17,062	\$ 4,266	\$ 42,656
8.20	125VDC Battery System	4	LS	25,000.00	22,750.00	9,750.00	\$ 100,000	\$ 91,000	\$ 39,000	\$ 230,000
8.21	Control house AC Panel	3	EA	65,000.00	91,000.00	39,000.00	\$ 195,000	\$ 273,000	\$ 117,000	\$ 585,000
8.22	Control House DC Panel	3	EA	65,000.00	91,000.00	39,000.00	\$ 195,000	\$ 273,000	\$ 117,000	\$ 585,000
8.23	Generator	1	EA	130,000.00	72,800.00	31,200.00	\$ 130,000	\$ 72,800	\$ 31,200	\$ 234,000
TOTAL - CONTROL ENCLOSURE							\$ 3,148,429	\$ 2,577,294	\$ 965,135	\$ 6,690,858
1. Station 29 New Ruland Road 345kv Substation							\$ 31,906,422	\$ 14,324,879	\$ 8,056,013	\$ 54,287,315
9. MOB/DEMOB, ENGINEERING, PERMITTING, T&C, PM & INDIRECTS										
	Contractor Mobilization / Demobilization									
9.1	Mob / Demob	1.0	LS		582,256.23	249,538.38	\$ -	\$ 582,256	\$ 249,538	\$ 831,795
	Project Management, Material Handling & Amenities									
9.2	Preconstruction Supervision (Engineering, Permitting, Procurement)	1	LS		427,973.15		\$ -	\$ 427,973	\$ -	\$ 427,973
9.3	Project Management & Staffing (includes PM, Field Engineers / Supervision, Scheduler and Cost Manager, SHEQ Staff, and Admin Staff)	1	LS		1,711,892.59		\$ -	\$ 1,711,893	\$ -	\$ 1,711,893
9.4	Utility PM and Project Oversight	1	LS		427,973.15		\$ -	\$ 427,973	\$ -	\$ 427,973
9.5	Site Accommodation, Facilities, Storage	1	LS	427,973.15			\$ 427,973	\$ -	\$ -	\$ 427,973
	Engineering									
9.6	Design Engineering	1.00	LS		3,423,785.17		\$ -	\$ 3,423,785	\$ -	\$ 3,423,785
9.7	LiDAR /GPR	1.00	LS		-		\$ -	\$ -	\$ -	\$ -
9.8	Geotech	5.00	EA		2,730.00	1,820.00	\$ -	\$ 13,650	\$ 9,100	\$ 22,750
9.9	Surveying/Staking	1.00	Site		299,581.20		\$ -	\$ 299,581	\$ -	\$ 299,581
	Testing & Commissioning									
9.10	Testing & Commissioning of SS and Equipment	1.00	LS		1,604,899.30		\$ -	\$ 1,604,899	\$ -	\$ 1,604,899
	Permitting and Additional Costs									
9.11	Physical Security	1.00	LS		6,546.96		\$ -	\$ 6,547	\$ -	\$ 6,547
9.12	Environmental Licensing & Permitting Costs & related legal cost	1.00	LS		427,973.15		\$ -	\$ 427,973	\$ -	\$ 427,973
9.13	Environmental-special studies/investigation	-	LS		-		\$ -	\$ -	\$ -	\$ -
9.14	Warranties / LOC's	1.00	LS		128,391.94		\$ -	\$ 128,392	\$ -	\$ 128,392
9.15	Laydown Lease	-	LS				\$ -	\$ -	\$ -	\$ -
9.16	Real Estate ( Acquisition)	1.00	LS		-	1,158,245.00	\$ -	\$ -	\$ 1,158,245	\$ 1,158,245
9.17	Legal Fees (Real estate)	1.00	LS		-	34,747.35	\$ -	\$ -	\$ 34,747	\$ 34,747
9.18	Insurance	-	LS		-	-	\$ -	\$ -	\$ -	\$ -
9.19	Bonds	1	LS		-	\$ 1,940,000	\$ -	\$ -	\$ 1,940,000	\$ 1,940,000
9.20	Sales Tax on Materials	8.80%	LS	31,906,422.41			\$ 2,807,765	\$ -	\$ -	\$ 2,807,765
9.21	Fees for permits, including roadway, railroad, building or other local permits	1.00	LS		54,287.31		\$ -	\$ 54,287	\$ -	\$ 54,287
TOTAL - MOB/DEMOB, ENGINEERING, PERMITTING, T&C, PM & INDIRECTS:							\$ 3,235,738	\$ 9,109,210	\$ 3,391,631	\$ 15,736,579

NEXTera Energy- TO36 Core 1

2.Station 252 New East Garden City 345 Substation

Total:     \$           347,939,735

NEXTera Energy- TO36 Core 1				
	Material Supply	Labor Supply	Equip Supply	Total
2.Station 252 New East Garden City 345 Substation				
1. SITE PREP/ GRADING/ FENCING / CIVIL	\$ 1,520,689	\$ 1,991,295	\$ 1,238,557	\$ 4,750,541
2. SUBSTATION FOUNDATIONS	\$ 6,183,051	\$ 6,672,230	\$ 4,188,294	\$ 17,043,576
3. SUBSTATION STRUCTURES	\$ 2,079,686	\$ 1,420,019	\$ 821,171	\$ 4,320,876
4. MAJOR EQUIPTMENT	\$ 86,834,800	\$ 16,766,972	\$ 11,053,048	\$ 114,654,820
5. LOW VOLTAGE & CONTROL CABLE	\$ 138,265	\$ 37,388	\$ 7,478	\$ 183,131
6. CONDUIT & CABLE TRENCH	\$ 8,746,451	\$ 4,970,057	\$ 2,720,221	\$ 16,436,729
7. GROUND GRID	\$ 150,907	\$ 108,737	\$ 25,280	\$ 284,924
8. CONTROL ENCLOSURE	\$ 5,830,727	\$ 4,413,122	\$ 1,666,606	\$ 11,910,455
9. MOB/DEMOB, ENGINEERING, PERMITTING, T&C, PM & INDIRECTS	\$ 11,154,293	\$ 28,760,396	\$ 39,802,107	\$ 79,716,796
Turnkey cost (HVDC, GIS)	\$ 17,610,000	\$ 10,566,000	\$ 7,044,000	\$ 35,220,000
Non-Turnkey cost	\$ 105,028,869	\$ 54,574,217	\$ 54,478,761	\$ 214,081,847
SUBTOTAL (Costs):	\$ 122,638,869	\$ 65,140,217	\$ 61,522,761	\$ 249,301,847
CONTRACTOR MARK-UP (OH&P)	\$ 19,961,796	\$ 10,457,319	\$ 10,228,817	\$ 40,647,932
SUBTOTAL:	\$ 142,600,665	\$ 75,597,536	\$ 71,751,578	\$ 289,949,779
CONTINGENCY ON ENTIRE PROJECT	\$ 28,520,133	\$ 15,119,507	\$ 14,350,316	\$ 57,989,956
TOTAL:	\$ 171,120,798	\$ 90,717,043	\$ 86,101,894	\$ 347,939,735

Description of Work: New East Garden City 345 kV/138 kV GIS Substation										
Item	Item Description	Estimated Quantity	Unit of Measure	Material Supply Rate	Labor Supply Rate	Const. Equipment Rate	Material Supply Cost	Labor Supply Cost	Const. Equipment Cost	TOTAL COST
2.Station 252 New East Garden City 345 Substation										
1. SITE PREP/ GRADING/ FENCING / CIVIL										
1.1	Site Clearing	0.0	ACRE	-	10,800.00	7,200.00	\$ -	\$ -	\$ -	\$ -
1.2	Demolition	1	LS	-	900,000.00	600,000.00	\$ -	\$ 900,000	\$ 600,000	\$ 1,500,000
1.3	New Access Road - 20'	3,149	SY	4.85	7.20	4.80	\$ 15,272	\$ 22,672	\$ 15,115	\$ 53,059
1.4	Strip and Dispose Top Soil	0	CY		24.50	10.50	\$ -	\$ -	\$ -	\$ -
1.5	Site Grading- Excavation for Substation Pad	27,443	CY		9.00	6.00	\$ -	\$ 246,985	\$ 164,657	\$ 411,642
1.6	Site Grading- Excavation for Substation Pad-Rock excavation-Hauling and disposal	14,819	CY		21.00	9.00	\$ -	\$ 311,201.35	\$ 133,372.01	\$ 444,573.36
1.7	Site Grading- Fill for Substation Pad (site borrow, compacted in place)	22,229	CY		2.40	1.60	\$ -	\$ 53,349	\$ 35,566	\$ 88,915
1.8	Site Grading -Fill for Substation Pad (import, compacted in place)	14,819	CY	25.00	2.40	1.60	\$ 370,478	\$ 35,566	\$ 23,711	\$ 429,754
1.9	Blasting		EA				\$ -	\$ -	\$ -	\$ -
1.10	Install substation 8" pad base	21,780	SY	11.00	6.00	4.00	\$ 239,580	\$ 130,680	\$ 87,120	\$ 457,380
1.11	Site Surfacing - Aggregate 6" Thick	21,780	SY	16.50	4.50	3.00	\$ 359,370	\$ 98,010	\$ 65,340	\$ 522,720
1.12	7' Station Fence w/ Barbed Wire & Grounding	2,094	LF	13.85	13.85	6.92	\$ 28,998	\$ 28,998	\$ 14,499	\$ 72,494
1.13	20' Slide Gate & Grounding	2	EA	8,100.00	3,245.00	1,305.00	\$ 16,200	\$ 6,490	\$ 2,610	\$ 25,300
1.14	4' Pedestrian gate	2	EA	2,500.00	1,000.00	350.00	\$ 5,000	\$ 2,000	\$ 700	\$ 7,700
1.15	Storm drain-15" HDPE, INFILTRATION TRENCH, INLET and Hydrodynamic Separator	1	LS	446,976.00	115,200.00	76,104.00	\$ 446,976	\$ 115,200	\$ 76,104	\$ 638,280
1.16	Seeding	0	SF	1.50	1.50	1.00	\$ -	\$ -	\$ -	\$ -
1.17	Erosion Control-Silt fence install & remove	3,285	LF	2.41	3.16	0.72	\$ 7,917	\$ 10,381	\$ 2,365	\$ 20,663
1.18	Temporary fencing	2,190	LF	7.50	5.25	2.25	\$ 16,425	\$ 11,498	\$ 4,928	\$ 32,850
1.19	Substation entrance with asphalt	556	SY	19.50	26.00	19.50	\$ 10,833	\$ 14,444	\$ 10,833	\$ 36,111

Item	Item Description	Estimated Quantity	Unit of Measure	Material Supply Rate	Labor Supply Rate	Const. Equipment Rate	Material Supply Cost	Labor Supply Cost	Const. Equipment Cost	TOTAL COST
1.20	Concrete curb	140	LF	26.00	27.30	11.70	\$ 3,640	\$ 3,822	\$ 1,638	\$ 9,100
1.21	Retaining Wall	0	LF	156.00	117.00	117.00	\$ -	\$ -	\$ -	\$ -
TOTAL - SITE PREP/ GRADING/ FENCING / CIVIL							\$ 1,520,689	\$ 1,991,295	\$ 1,238,557	\$ 4,750,541
2. SUBSTATION FOUNDATIONS										
2.1	345kV, Lightning mast	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.2	345kV, A Frame 70'	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.3	345kV, Bus support-3 Ph	95	CY	703.89	804.44	502.78	\$ 66,897	\$ 76,454	\$ 47,784	\$ 191,135
2.4	345kV, Bus support-3 Ph, low	332	CY	703.89	804.44	502.78	\$ 233,549	\$ 266,913	\$ 166,821	\$ 667,283
2.5	345kV, Bus support-1 Ph	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.6	345kV, GIS air terminal	277	CY	703.89	804.44	502.78	\$ 195,117	\$ 222,991	\$ 139,369	\$ 557,477
2.7	345kV, GIS support-1 Ph	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.8	345kV, GIS support-3 Ph	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.9	345kV, GIS Cable sealing end	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.10	345kV, Cable sealing end	107	CY	703.89	804.44	502.78	\$ 75,316	\$ 86,075	\$ 53,797	\$ 215,188
2.11	345kV, CCVT	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.12	345kV, Disconnect Switch	190	CY	703.89	804.44	502.78	\$ 133,794	\$ 152,908	\$ 95,567	\$ 382,270
2.13	345/138KV, Power Transformer with oil containment	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.14	345kV, Shunt Reactor with oil containment-225MVAR	610	CY	703.89	804.44	502.78	\$ 429,370	\$ 490,708	\$ 306,693	\$ 1,226,771
2.15	345kV, Shunt Reactor with oil containment-50MVAR	378	CY	703.89	804.44	502.78	\$ 266,069	\$ 304,078	\$ 190,049	\$ 760,196
2.16	345kV, Shunt Reactor with oil containment-25MVAR	200	CY	703.89	804.44	502.78	\$ 140,777	\$ 160,888	\$ 100,555	\$ 402,220
2.17	345kV, Phase Angle Regulator with oil containment	1,780	CY	703.89	804.44	502.78	\$ 1,252,915	\$ 1,431,903	\$ 894,940	\$ 3,579,758
2.18	345kV, Circuit Breaker (PASS)	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.19	345kV, Circuit Breaker (GIS), outdoor rated	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.20	345Kv, GIS Enclosure-BLDG with generator pad	1,867	CY	703.89	804.44	502.78	\$ 1,314,153	\$ 1,501,889	\$ 938,681	\$ 3,754,724
2.21	345kV, Surge arrester	161	CY	-	-	-	\$ -	\$ -	\$ -	\$ -
2.22	138kV, Phase Angle Regulator with oil containment	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.23	138kV, Circuit Breaker, Hybrid circuit breaker	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.24	138kV, Bus support-3 Ph, low	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.25	138kV, Bus support-1 Ph, low	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.26	138kV, Disconnect Switch	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.27	138kV, Cable sealing end	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.28	138kV, CCVT	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.29	138kV, A Frame 50'	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.30	Firewall Foundation	1,917	CY	703.89	804.44	502.78	\$ 1,349,094	\$ 1,541,822	\$ 963,639	\$ 3,854,555
2.31	Precast Firewall for transformer, PARs, reactors	29,040	SF	25.00	15.00	10.00	\$ 726,000	\$ 435,600	\$ 290,400	\$ 1,452,000
2.32	Precast Concrete Piles-12"X80'	-	EA	18,000.00	3,200.00	2,800.00	\$ -	\$ -	\$ -	\$ -
2.33	Local Control Cabinet foundation	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.34	138kV, GIS Enclosure-BLDG & control room	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
TOTAL - 345KV FOUNDATION							\$ 6,183,051	\$ 6,672,230	\$ 4,188,294	\$ 17,043,576
3. SUBSTATION STRUCTURES										
3.1	345kV, Lightning mast	0	EA				\$ -	\$ -	\$ -	\$ -
3.2	345kV, A Frame 70'	0	EA	48,100.00	28,860.00	19,240.00	\$ -	\$ -	\$ -	\$ -
3.3	345kV, Bus support-3 Ph	6	EA	8,346.00	5,758.74	3,839.16	\$ 50,076	\$ 34,552	\$ 23,035	\$ 107,663
3.4	345kV, Bus support-3 Ph, low	30	EA	8,346.00	5,758.74	3,839.16	\$ 250,380	\$ 172,762	\$ 115,175	\$ 538,317
3.5	345kV, Bus support-1 Ph	0	EA	4,810.00	2,886.00	1,924.00	\$ -	\$ -	\$ -	\$ -
3.6	345kV, GIS air terminal	21	EA	8,346.00	5,758.74	3,839.16	\$ 175,266	\$ 120,934	\$ 80,622	\$ 376,822
3.7	345kV, GIS support-1 Ph	0	EA	8,346.00	5,758.74	3,839.16	\$ -	\$ -	\$ -	\$ -
3.8	345kV, GIS support-3 Ph	0	EA	4,810.00	2,886.00	1,924.00	\$ -	\$ -	\$ -	\$ -
3.9	345kV, GIS Cable sealing end	0	EA	8,346.00	5,758.74	3,839.16	\$ -	\$ -	\$ -	\$ -
3.10	345kV, Cable sealing end	10	EA	8,346.00	5,758.74	3,839.16	\$ 83,460	\$ 57,587	\$ 38,392	\$ 179,439
3.11	345kV, CCVT	0	EA	4,810.00	2,886.00	1,924.00	\$ -	\$ -	\$ -	\$ -
3.12	345kV, Disconnect Switch	6	EA	19,240.00	11,544.00	7,696.00	\$ 115,440	\$ 69,264	\$ 46,176	\$ 230,880
3.13	138kV, Bus support-3 Ph, low	0	EA	4,173.00	2,879.76	1,919.84	\$ -	\$ -	\$ -	\$ -
3.14	138kV, Bus support-1 Ph, low	0	EA	2,782.00	1,919.84	1,279.89	\$ -	\$ -	\$ -	\$ -
3.15	138kV, Disconnect Switch	0	EA				\$ -	\$ -	\$ -	\$ -
3.16	138kV, Cable sealing end	0	EA	4,810.00	2,886.00	1,924.00	\$ -	\$ -	\$ -	\$ -
3.17	138kV, CCVT	0	EA	3,206.67	1,924.00	1,282.67	\$ -	\$ -	\$ -	\$ -
3.18	138kV, A Frame 50'	0	EA	33,000.00	19,800.00	13,200.00	\$ -	\$ -	\$ -	\$ -
3.19	345kV Gas-Insulated Bus Conductor	0	LF	550.00	275.00	82.50	\$ -	\$ -	\$ -	\$ -
3.20	345kV Gas-Insulated Bus Conductor-elbow	0	EA	2,500.00	1,250.00	375.00	\$ -	\$ -	\$ -	\$ -
3.21	AL. Bus Tubing, 5" SCH 80	1,900	LF	25.00	184.94	123.29	\$ 47,500	\$ 351,382	\$ 234,255	\$ 633,137
3.22	AL. Bus fittings	1	LS	57,000.00	57,000.00	45,000.00	\$ 57,000	\$ 57,000	\$ 45,000	\$ 159,000
3.23	Steel grating and support beams-transformer moat	476,080	LB	2.73	1.17	0.50	\$ 1,300,564	\$ 556,538	\$ 238,516	\$ 2,095,617



Item	Item Description	Estimated Quantity	Unit of Measure	Material Supply Rate	Labor Supply Rate	Const. Equipment Rate	Material Supply Cost	Labor Supply Cost	Const. Equipment Cost	TOTAL COST
TOTAL - SUBSTATION STRUCTURES & GAS-INSULATED CONDUCTOR							\$ 2,079,686	\$ 1,420,019	\$ 821,171	\$ 4,320,876
4. MAJOR EQUIPMENT										
4.1	345kV, GIS air terminal	21	EA				\$ -	\$ -	\$ -	\$ -
4.2	345kV, GIS Cable sealing end	0	EA				\$ -	\$ -	\$ -	\$ -
4.3	345kV, Cable sealing end	30	EA	17,400.00	5,460.00	2,340.00	\$ 522,000	\$ 163,800	\$ 70,200	\$ 756,000
4.4	345kV, CCVT	0	EA		15,941.99	6,832.28	\$ -	\$ -	\$ -	\$ -
4.5	345kV, Disconnect Switch	6	EA	57,720.00	34,632.00	23,088.00	\$ 346,320	\$ 207,792	\$ 138,528	\$ 692,640
4.6	345/138KV, Power Transformer with oil containment	0	EA		3,520.00	880.00	\$ -	\$ -	\$ -	\$ -
4.7	Transport & Testing- Transformer	0	EA		15,400.00	6,600.00	\$ -	\$ -	\$ -	\$ -
4.8	345kV, Shunt Reactor with oil containment-225MVAR	2	EA	3,026,425.00	3,520.00	880.00	\$ 6,052,850	\$ 7,040	\$ 1,760	\$ 6,061,650
4.9	345kV, Shunt Reactor with oil containment-50MVAR	3	EA	2,138,451.50	3,520.00	880.00	\$ 6,415,355	\$ 10,560	\$ 2,640	\$ 6,428,555
4.10	345kV, Shunt Reactor with oil containment-25MVAR	2	EA	1,900,130.50	3,520.00	880.00	\$ 3,800,261	\$ 7,040	\$ 1,760	\$ 3,809,061
4.11	Transport & Testing- Shunt Reactor	7	EA		457,900.00	301,600.00	\$ -	\$ 3,205,300	\$ 2,111,200	\$ 5,316,500
4.12	345kV, Phase Angle Regulator with oil containment	4	EA	12,882,000.00	3,520.00	880.00	\$ 51,528,000	\$ 14,080	\$ 3,520	\$ 51,545,600
4.7	Transport & Testing- PAR	4	EA		615,400.00	406,600.00	\$ -	\$ 2,461,600	\$ 1,626,400	\$ 4,088,000
4.13	345kV, Gas Insulated Switchgear, BAAH Arrangement	21	BKR	838,571.43	503,142.86	335,428.57	\$ 17,610,000	\$ 10,566,000	\$ 7,044,000	\$ 35,220,000
4.14	345kV, Circuit Breaker (PASS)	0	EA		57,239.00	24,531.00	\$ -	\$ -	\$ -	\$ -
4.15	345kV, Circuit Breaker (GIS), outdoor rated	0	EA				\$ -	\$ -	\$ -	\$ -
4.16	345kV, Circuit Breaker (GIS), outdoor rated-Line surge Arrester ( 3phase)	0	EA				\$ -	\$ -	\$ -	\$ -
4.17	345kV, surge Arrester	6	EA	6,669.00	5,460.00	2,340.00	\$ 40,014	\$ 32,760	\$ 14,040	\$ 86,814
4.18	138kV, Phase Angle Regulator with oil containment	0	EA	10,366,370.00	3,520.00	880.00	\$ -	\$ -	\$ -	\$ -
4.19	Transport & Testing- Phase Angle Regulating Transformer, 138kV	0	EA		336,400.00	220,600.00	\$ -	\$ -	\$ -	\$ -
4.20	138kV, Gas Insulated Switchgear, BAAH Arrangement	0	BKR		205,800.00	4,200.00	\$ -	\$ -	\$ -	\$ -
4.21	138kV, Circuit Breaker, Hybrid circuit breaker	0	EA		13,559.00	5,811.00	\$ -	\$ -	\$ -	\$ -
4.22	138kV, Disconnect Switch	0	EA		3,958.50	1,696.50	\$ -	\$ -	\$ -	\$ -
4.23	138kV, Cable sealing end	0	EA	11,600.00	5,460.00	2,340.00	\$ -	\$ -	\$ -	\$ -
4.24	138kV, CCVT	0	EA		7,970.08	3,415.75	\$ -	\$ -	\$ -	\$ -
4.25	138kV, Surge arrester	0	EA	4,446.00	4,200.00	1,800.00	\$ -	\$ -	\$ -	\$ -
4.26	Station service transformers- 120/208v-250VA	2	EA	260,000.00	45,500.00	19,500.00	\$ 520,000	\$ 91,000	\$ 39,000	\$ 650,000
TOTAL - MAJOR EQUIPMENT							\$ 86,834,800	\$ 16,766,972	\$ 11,053,048	\$ 114,654,820
5. LOW VOLTAGE & CONTROL CABLE										
5.1	Control Cables	26,100	LF	5.30	1.43	0.29	\$ 138,265	\$ 37,388	\$ 7,478	\$ 183,131
5.2			LF		-	-	\$ -	\$ -	\$ -	\$ -
TOTAL - LOW VOLTAGE & CONTROL CABLE							\$ 138,265	\$ 37,388	\$ 7,478	\$ 183,131
6. CONDUIT & CABLE TRENCH										
6.1	Conduit, PVC, 6", SCH 40		LF	20.70	13.28	6.64	\$ -	\$ -	\$ -	\$ -
6.2	Conduit, PVC, 4", SCH 40	5,400	LF	11.15	10.80	5.40	\$ 60,210	\$ 58,320	\$ 29,160	\$ 147,690
6.3	Conduit, PVC, 3", SCH 40		LF	8.10	10.80	5.40	\$ -	\$ -	\$ -	\$ -
6.4	Conduit, PVC, 2", SCH 40		LF	3.95	10.80	5.40	\$ -	\$ -	\$ -	\$ -
6.5	Conduit, PVC, 1", SCH 40		LF	1.90	10.80	5.40	\$ -	\$ -	\$ -	\$ -
6.6	Cable Trench	1,063	LF	266.50	53.04	13.26	\$ 283,156	\$ 56,355	\$ 14,089	\$ 353,600
6.7										
6.8	138kV UG- Conduit		LF	266.73	202.15	100.00	\$ -	\$ -	\$ -	\$ -
6.9	138kV UG- Cable		LF	145.00	87.00	58.00	\$ -	\$ -	\$ -	\$ -
6.10	138kV UG- Termination		EA	27,805.00	9,846.48	2,813.28	\$ -	\$ -	\$ -	\$ -
6.11	345kV UG- Conduit	8,016	LF	266.73	202.15	100.00	\$ 2,138,035	\$ 1,620,346	\$ 801,609	\$ 4,559,990
6.12	345kV UG- Cable	24,047	LF	167.00	100.20	66.80	\$ 4,015,866	\$ 2,409,519	\$ 1,606,346	\$ 8,031,731
6.13	345kV UG- Termination	75	EA	27,805.00	9,846.48	2,813.28	\$ 2,085,375	\$ 738,486	\$ 210,996	\$ 3,034,857
6.14	Fiber Optic Cable	8,016	LF	7.40	3.33	2.22	\$ 59,292	\$ 26,697	\$ 17,798	\$ 103,787
6.15	Ground Continuity Conductor	8,016	LF	13.04	7.53	5.02	\$ 104,517	\$ 60,334	\$ 40,223	\$ 205,074
TOTAL - CONDUIT & CABLE TRENCH							\$ 8,746,451	\$ 4,970,057	\$ 2,720,221	\$ 16,436,729
7. GROUND GRID										
7.1	Cable, 4/0 AWG Bare Copper, 7 Strand Ground Conductor	15,355	LF	2.09	3.42	1.46	\$ 32,107	\$ 52,442	\$ 22,475	\$ 107,024
7.2	Caweld, DSA, 4/0 , T, CROSS	414	EA	165.00	75.00		\$ 68,310	\$ 31,050	\$ -	\$ 99,360
7.3	Ground Rod, 3/4" x 15'	374	EA	135.00	67.50	7.50	\$ 50,490	\$ 25,245	\$ 2,805	\$ 78,540
TOTAL - GROUND GRID							\$ 150,907	\$ 108,737	\$ 25,280	\$ 284,924
8. CONTROL ENCLOSURE										
8.1	345kv GIS Bldg	1	EA	3,817,603.08	2,672,322.16	1,145,280.92	\$ 3,817,603	\$ 2,672,322	\$ 1,145,281	\$ 7,635,206
8.2	138kv GIS/Control Bldg	0	EA	1,145,280.92	801,696.65	343,584.28	\$ -	\$ -	\$ -	\$ -
8.3	Primary Line Relays (87L): SEL-411L	11	EA	21,328.12	17,062.49	4,265.62	\$ 234,609	\$ 187,687	\$ 46,922	\$ 469,219
8.4	Backup Line Relays (87L): GE L90	11	EA	21,328.12	17,062.49	4,265.62	\$ 234,609	\$ 187,687	\$ 46,922	\$ 469,219
8.5	Primary Bay Control: SEL-451	7	EA	21,328.12	17,062.49	4,265.62	\$ 149,297	\$ 119,437	\$ 29,859	\$ 298,594
8.6	Backup Bay Control: SEL-451	7	EA	21,328.12	17,062.49	4,265.62	\$ 149,297	\$ 119,437	\$ 29,859	\$ 298,594

Item	Item Description	Estimated Quantity	Unit of Measure	Material Supply Rate	Labor Supply Rate	Const. Equipment Rate	Material Supply Cost	Labor Supply Cost	Const. Equipment Cost	TOTAL COST
8.7	Primary Transformer/Reactor/PAR Differential Relays: SEL-487E	9	EA	21,328.12	17,062.49	4,265.62	\$ 191,953	\$ 153,562	\$ 38,391	\$ 383,906
8.8	Backup Transformer/Reactor/PAR Differential Relays: GE T60	9	EA	21,328.12	17,062.49	4,265.62	\$ 191,953	\$ 153,562	\$ 38,391	\$ 383,906
8.9	Primary Bus Differential Relays: SEL-487B	5	EA	21,328.12	17,062.49	4,265.62	\$ 106,641	\$ 85,312	\$ 21,328	\$ 213,281
8.10	Backup Bus Differential Relays: GE B90	5	EA	21,328.12	17,062.49	4,265.62	\$ 106,641	\$ 85,312	\$ 21,328	\$ 213,281
8.11	RTU Panel A: SEL-2240 Axion, SEL-2730M ENET SW., SEL-2407 GPS, Modem, SEL-2523 Annunci	1	EA	12,500.00	10,000.00	2,500.00	\$ 12,500	\$ 10,000	\$ 2,500	\$ 25,000
8.12	RTU Panel B: SEL-2730M Ethernet Switch, SEL-2407 GPS Clock, SEL-2523 Annunciator	1	EA	12,500.00	10,000.00	2,500.00	\$ 12,500	\$ 10,000	\$ 2,500	\$ 25,000
8.13	HMI Panel	1	EA	12,500.00	10,000.00	2,500.00	\$ 12,500	\$ 10,000	\$ 2,500	\$ 25,000
8.14	Primary Line Relays (87L): SEL-411L	4	EA	21,328.12	17,062.49	4,265.62	\$ 85,312	\$ 68,250	\$ 17,062	\$ 170,625
8.15	Backup Line Relays (87L): GE L90	4	EA	21,328.12	17,062.49	4,265.62	\$ 85,312	\$ 68,250	\$ 17,062	\$ 170,625
8.16	Primary Line Relays (87L): SEL-411L		EA	21,328.12	17,062.49	4,265.62	\$ -	\$ -	\$ -	\$ -
8.17	Backup Line Relays (87L): GE L90		EA	21,328.12	17,062.49	4,265.62	\$ -	\$ -	\$ -	\$ -
8.18	Primary Transformer/Reactor/PAR Differential Relays: SEL-487E		EA	21,328.12	17,062.49	4,265.62	\$ -	\$ -	\$ -	\$ -
8.19	Backup Transformer/Reactor/PAR Differential Relays: GE T60		EA	21,328.12	17,062.49	4,265.62	\$ -	\$ -	\$ -	\$ -
8.20	Primary Bus Differential Relays: SEL-487B		EA	21,328.12	17,062.49	4,265.62	\$ -	\$ -	\$ -	\$ -
8.21	Backup Bus Differential Relays: GE B90		EA	21,328.12	17,062.49	4,265.62	\$ -	\$ -	\$ -	\$ -
8.22	125VDC Battery System	2	LS	25,000.00	22,750.00	9,750.00	\$ 50,000	\$ 45,500	\$ 19,500	\$ 115,000
8.23	Control house AC Panel	2	EA	65,000.00	91,000.00	39,000.00	\$ 130,000	\$ 182,000	\$ 78,000	\$ 390,000
8.24	Control House DC Panel	2	EA	65,000.00	91,000.00	39,000.00	\$ 130,000	\$ 182,000	\$ 78,000	\$ 390,000
8.25	Generator	1	EA	130,000.00	72,800.00	31,200.00	\$ 130,000	\$ 72,800	\$ 31,200	\$ 234,000
TOTAL - CONTROL ENCLOSURE							\$ 5,830,727	\$ 4,413,122	\$ 1,666,606	\$ 11,910,455
2.Station 252 New East Garden City 345 Substation							\$ 111,484,576	\$ 36,379,821	\$ 21,720,654	\$ 169,585,051
9. MOB/DEMOB, ENGINEERING, PERMITTING, T&C, PM & INDIRECTS										
	Contractor Mobilization / Demobilization									
9.1	Mob / Demob	1.0	LS		2,033,516.63	871,507.13	\$ -	\$ 2,033,517	\$ 871,507	\$ 2,905,024
	Project Management, Material Handling & Amenities									
9.2	Preconstruction Supervision (Engineering, Permitting, Procurement)	1	LS		1,343,650.51		\$ -	\$ 1,343,651	\$ -	\$ 1,343,651
9.3	Project Management & Staffing (includes PM, Field Engineers / Supervision, Scheduler and Cost Manager, SHEQ Staff, and Admin Staff)	1	LS		5,374,602.02		\$ -	\$ 5,374,602	\$ -	\$ 5,374,602
9.4	Utility PM and Project Oversight	1	LS		1,343,650.51		\$ -	\$ 1,343,651	\$ -	\$ 1,343,651
9.5	Site Accommodation, Facilities, Storage	1	LS	1,343,650.51			\$ 1,343,651	\$ -	\$ -	\$ 1,343,651
	Engineering									
9.6	Design Engineering	1.00	LS		10,749,204.05		\$ -	\$ 10,749,204	\$ -	\$ 10,749,204
9.7	LiDAR /GPR	-	LS				\$ -	\$ -	\$ -	\$ -
9.8	Geotech	5.00	EA		2,730.00	1,820.00	\$ -	\$ 13,650	\$ 9,100	\$ 22,750
9.9	Surveying/Staking	1.00	Site		940,555.35		\$ -	\$ 940,555	\$ -	\$ 940,555
	Testing & Commissioning									
9.10	Testing & Commissioning of SS and Equipment	1.00	LS		5,038,689.40		\$ -	\$ 5,038,689	\$ -	\$ 5,038,689
	Permitting and Additional Costs									
9.11	Physical Security	1.00	LS		6,546.96		\$ -	\$ 6,547	\$ -	\$ 6,547
9.12	Environmental Licensing & Permitting Costs & related legal cost	1.00	LS		1,343,650.51		\$ -	\$ 1,343,651	\$ -	\$ 1,343,651
9.13	Environmental-special studies/investigation	-	LS		-		\$ -	\$ -	\$ -	\$ -
9.14	Warranties / LOC's	1.00	LS		403,095.15		\$ -	\$ 403,095	\$ -	\$ 403,095
9.15	Laydown Lease	-	LS				\$ -	\$ -	\$ -	\$ -
9.16	Real Estate ( Acquisition)	1.00	LS		-	31,050,000.00	\$ -	\$ -	\$ 31,050,000	\$ 31,050,000
9.17	Legal Fees (Real estate)	1.00	LS		-	931,500.00	\$ -	\$ -	\$ 931,500	\$ 931,500
9.18	Insurance	-	LS		-	-	\$ -	\$ -	\$ -	\$ -
9.19	Bonds	1	LS		-	\$ 6,940,000	\$ -	\$ -	\$ 6,940,000	\$ 6,940,000
9.20	Sales Tax on Materials	8.80%	LS	111,484,575.51			\$ 9,810,643	\$ -	\$ -	\$ 9,810,643
9.21	Fees for permits, including roadway, railroad, building or other local permits	1.00	LS		169,585.05		\$ -	\$ 169,585	\$ -	\$ 169,585
TOTAL - MOB/DEMOB, ENGINEERING, PERMITTING, T&C, PM & INDIRECTS:							\$ 11,154,293	\$ 28,760,396	\$ 39,802,107	\$ 79,716,796

NEXTera Energy- TO36 Core 1

3.Station 48 Valley Stream 345/138 kV Substation Upgrades

Total:                      Total:    \$            143,522,216

NEXTera Energy- TO36 Core 1				
	Material Supply	Labor Supply	Equip Supply	Total
3.Station 48 Valley Stream 345/138 kV Substation Upgrades				
1. SITE PREP/ GRADING/ FENCING / CIVIL	\$ 903,828	\$ 1,042,806	\$ 681,014	\$ 2,627,648
2. SUBSTATION FOUNDATIONS	\$ 2,969,736	\$ 3,393,984	\$ 2,121,289	\$ 8,485,009
3. SUBSTATION STRUCTURES	\$ 1,692,012	\$ 862,489	\$ 392,825	\$ 2,947,326
4. MAJOR EQUIPTMENT	\$ 33,770,383	\$ 9,893,022	\$ 6,376,108	\$ 50,039,513
5. LOW VOLTAGE & CONTROL CABLE	\$ 98,534	\$ 26,645	\$ 5,329	\$ 130,507
6. CONDUIT & CABLE TRENCH	\$ 3,169,320	\$ 1,626,898	\$ 829,928	\$ 5,626,146
7. GROUND GRID	\$ 100,333	\$ 72,239	\$ 16,752	\$ 189,324
8. CONTROL ENCLOSURE	\$ 4,172,141	\$ 3,175,330	\$ 1,245,811	\$ 8,593,282
9. MOB/DEMOB, ENGINEERING, PERMITTING, T&C, PM & INDIRECTS	\$ 4,708,201	\$ 13,997,126	\$ 6,080,873	\$ 24,786,200
Turnkey cost (HVDC, GIS)	\$ 10,165,000	\$ 6,099,000	\$ 4,066,000	\$ 20,330,000
Non-Turnkey cost	\$ 41,419,488	\$ 27,991,539	\$ 13,683,929	\$ 83,094,955
SUBTOTAL (Costs):	\$ 51,584,488	\$ 34,090,539	\$ 17,749,929	\$ 103,424,955
CONTRACTOR MARK-UP (OH&P)	\$ 8,065,408	\$ 5,404,417	\$ 2,707,067	\$ 16,176,892
SUBTOTAL:	\$ 59,649,895	\$ 39,494,955	\$ 20,456,996	\$ 119,601,847
CONTINGENCY ON ENTIRE PROJECT	\$ 11,929,979	\$ 7,898,991	\$ 4,091,399	\$ 23,920,369
TOTAL:	\$ 71,579,875	\$ 47,393,947	\$ 24,548,395	\$ 143,522,216

Description of Work: New East Garden City 345 kV/138 kV GIS Substation, and modification at exisitng 138kv EGC station										
Item	Item Description	Estimated Quantity	Unit of Measure	Material Supply Rate	Labor Supply Rate	Const. Equipment Rate	Material Supply Cost	Labor Supply Cost	Const. Equipment Cost	TOTAL COST
3.Station 48 Valley Stream 345/138 kV Substation Upgrades										
1. SITE PREP/ GRADING/ FENCING / CIVIL										
1.1	Site Clearing	0.0	ACRE	-	10,800.00	7,200.00	\$ -	\$ -	\$ -	\$ -
1.2	Demolition	1	LS	-	620,000.00	415,000.00	\$ -	\$ 620,000	\$ 415,000	\$ 1,035,000
1.3	New Access Road - 20'	889	SY	4.85	7.20	4.80	\$ 4,312	\$ 6,401	\$ 4,267	\$ 14,980
1.4	Strip and Dispose Top Soil	0	CY		24.50	10.50	\$ -	\$ -	\$ -	\$ -
1.5	Site Grading- Excavation for Substation Pad	11,761	CY		9.00	6.00	\$ -	\$ 105,849	\$ 70,566	\$ 176,415
1.6	Site Grading- Excavation for Substation Pad-Rock excavation-Hauling and disposal		CY		21.00	9.00	\$ -	\$ -	\$ -	\$ -
1.7	Site Grading- Fill for Substation Pad (site borrow, compacted in place)	7,057	CY		2.40	1.60	\$ -	\$ 16,937	\$ 11,291	\$ 28,228
1.8	Site Grading -Fill for Substation Pad (import, compacted in place)	4,704	CY	25.00	2.40	1.60	\$ 117,600	\$ 11,290	\$ 7,526	\$ 136,416
1.9	Blasting		EA				\$ -	\$ -	\$ -	\$ -
1.10	Install substation 8" pad base	8,712	SY	11.00	6.00	4.00	\$ 95,832	\$ 52,272	\$ 34,848	\$ 182,952
1.11	Site Surfacing - Aggregate 6" Thick	8,712	SY	16.50	4.50	3.00	\$ 143,748	\$ 39,204	\$ 26,136	\$ 209,088
1.12	7' Station Fence w/ Barbed Wire & Grounding	2,222	LF	13.85	13.85	6.92	\$ 30,770	\$ 30,770	\$ 15,385	\$ 76,926
1.13	20' Slide Gate & Grounding	3	EA	8,100.00	3,245.00	1,305.00	\$ 24,300	\$ 9,735	\$ 3,915	\$ 37,950
1.14	4' Pedestrian gate	3	EA	2,500.00	1,000.00	350.00	\$ 7,500	\$ 3,000	\$ 1,050	\$ 11,550
1.15	Storm drain-15" HDPE, INFILTRATION TRENCH, INLET and Hydrodynamic Separator	1	LS	446,976.00	115,200.00	76,104.00	\$ 446,976	\$ 115,200	\$ 76,104	\$ 638,280
1.16	Seeding	0	SF	1.50	1.50	1.00	\$ -	\$ -	\$ -	\$ -
1.17	Erosion Control-Silt fence install & remove	2,583	LF	2.41	3.16	0.72	\$ 6,225	\$ 8,162	\$ 1,860	\$ 16,247
1.18	Temporary fencing	2,190	LF	7.50	5.25	2.25	\$ 16,425	\$ 11,498	\$ 4,928	\$ 32,850
1.19	Substation entrance with asphalt	333	SY	19.50	26.00	19.50	\$ 6,500	\$ 8,667	\$ 6,500	\$ 21,667
1.20	Concrete curb	140	LF	26.00	27.30	11.70	\$ 3,640	\$ 3,822	\$ 1,638	\$ 9,100
1.21	Retaining Wall	0	LF	156.00	117.00	117.00	\$ -	\$ -	\$ -	\$ -

Item	Item Description	Estimated Quantity	Unit of Measure	Material Supply Rate	Labor Supply Rate	Const. Equipment Rate	Material Supply Cost	Labor Supply Cost	Const. Equipment Cost	TOTAL COST
TOTAL - SITE PREP/ GRADING/ FENCING / CIVIL							\$ 903,828	\$ 1,042,806	\$ 681,014	\$ 2,627,648
2. SUBSTATION FOUNDATIONS										
2.1	345kV, Lightning mast	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.2	345kV, A Frame 70'	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.3	345kV, Bus support-3 Ph	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.4	345kV, Bus support-3 Ph, low	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.5	345kV, Bus support-1 Ph	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.6	345kV, GIS air terminal	178	CY	703.89	804.44	502.78	\$ 125,432	\$ 143,351	\$ 89,595	\$ 358,378
2.7	345kV, GIS support-1 Ph	146	CY	703.89	804.44	502.78	\$ 102,880	\$ 117,577	\$ 73,486	\$ 293,942
2.8	345kV, GIS support-3 Ph	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.9	345kV, GIS Cable sealing end	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.10	345kV, Cable sealing end	32	CY	703.89	804.44	502.78	\$ 22,595	\$ 25,823	\$ 16,139	\$ 64,556
2.11	345kV, CCVT	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.12	345kV, Disconnect Switch	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.13	345/138KV, Power Transformer with oil containment	984	CY	703.89	804.44	502.78	\$ 692,623	\$ 791,569	\$ 494,731	\$ 1,978,922
2.14	345kV, Shunt Reactor with oil containment-150MVAR	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.15	345kV, Shunt Reactor with oil containment-50 MVAR	378	CY	703.89	804.44	502.78	\$ 266,069	\$ 304,078	\$ 190,049	\$ 760,196
2.16	345kV, Phase Angle Regulator with oil containment	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.17	345kV, Circuit Breaker (PASS)	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.18	345kV, Circuit Breaker (GIS), outdoor rated	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.19	345Kv, GIS Enclosure-BLDG with generator pad	1,481	CY	703.89	804.44	502.78	\$ 1,042,454	\$ 1,191,376	\$ 744,610	\$ 2,978,439
2.20	345kV, Surge arrester	48	CY	-	-	-	\$ -	\$ -	\$ -	\$ -
2.21	138kV, Phase Angle Regulator with oil containment	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.22	138kV, Circuit Breaker, Hybrid circuit breaker	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.23	138kV, Circuit Breaker-relocation only	4.4	CY	703.89	804.44	502.78	\$ 3,128	\$ 3,575	\$ 2,235	\$ 8,938
2.24	138kV, Bus support-3 Ph, low	43	CY	703.89	804.44	502.78	\$ 30,126	\$ 34,430	\$ 21,519	\$ 86,075
2.25	138kV, Bus support-1 Ph, low	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.26	138kV, Disconnect Switch	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.27	138kV, Disconnect Switch- RELOCATION ONLY	48	CY	703.89	804.44	503.78	\$ 34,124	\$ 38,999	\$ 24,423	\$ 97,547
2.28	138kV, Cable sealing end	61	CY	703.89	804.44	502.78	\$ 42,655	\$ 48,749	\$ 30,468	\$ 121,873
2.29	138kV, Surge arrester	48	CY	-	-	-	\$ -	\$ -	\$ -	\$ -
2.30	138kV, CCVT	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.31	138kV, A Frame 50'	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.32	Firewall Foundation	863	CY	703.89	804.44	502.78	\$ 607,650	\$ 694,457	\$ 434,036	\$ 1,736,142
2.33	Precast Firewall for transformer, PARs, reactors	-	SF	25.00	15.00	10.00	\$ -	\$ -	\$ -	\$ -
2.34	Precast Concrete Piles-12"X80'	-	EA	18,000.00	3,200.00	2,800.00	\$ -	\$ -	\$ -	\$ -
2.35	Local Control Cabinet foundation	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.36	138kV, GIS Enclosure-BLDG & control room	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
TOTAL - 345KV FOUNDATION							\$ 2,969,736	\$ 3,393,984	\$ 2,121,289	\$ 8,485,009
3. SUBSTATION STRUCTURES										
3.1	345kV, Lightning mast	0	EA				\$ -	\$ -	\$ -	\$ -
3.2	345kV, A Frame 70'	0	EA	48,100.00	28,860.00	19,240.00	\$ -	\$ -	\$ -	\$ -
3.3	345kV, Bus support-3 Ph	0	EA	8,346.00	5,758.74	3,839.16	\$ -	\$ -	\$ -	\$ -
3.4	345kV, Bus support-3 Ph, low	0	EA	8,346.00	5,758.74	3,839.16	\$ -	\$ -	\$ -	\$ -
3.5	345kV, Bus support-1 Ph	0	EA	4,810.00	2,886.00	1,924.00	\$ -	\$ -	\$ -	\$ -
3.6	345kV, GIS air terminal	27	EA	8,346.00	5,758.74	3,839.16	\$ 225,342	\$ 155,486	\$ 103,657	\$ 484,485
3.7	345kV, GIS support-1 Ph	36	EA	8,346.00	5,758.74	3,839.16	\$ 300,456	\$ 207,315	\$ 138,210	\$ 645,980
3.8	345kV, GIS support-3 Ph	0	EA	4,810.00	2,886.00	1,924.00	\$ -	\$ -	\$ -	\$ -
3.9	345kV, GIS Cable sealing end	0	EA	8,346.00	5,758.74	3,839.16	\$ -	\$ -	\$ -	\$ -
3.10	345kV, Cable sealing end	3	EA	8,346.00	5,758.74	3,839.16	\$ 25,038	\$ 17,276	\$ 11,517	\$ 53,832
3.11	345kV, CCVT	0	EA	4,810.00	2,886.00	1,924.00	\$ -	\$ -	\$ -	\$ -
3.12	345kV, Disconnect Switch	0	EA	19,240.00	11,544.00	7,696.00	\$ -	\$ -	\$ -	\$ -
3.13	138kV, Bus support-3 Ph, low	4	EA	4,173.00	2,879.76	1,919.84	\$ 16,692	\$ 11,519	\$ 7,679	\$ 35,890
3.14	138kV, Bus support-1 Ph, low	0	EA	2,782.00	1,919.84	1,279.89	\$ -	\$ -	\$ -	\$ -
3.15	138kV, Disconnect Switch	0	EA				\$ -	\$ -	\$ -	\$ -
3.16	138kV, Cable sealing end	3	EA	4,810.00	2,886.00	1,924.00	\$ 14,430	\$ 8,658	\$ 5,772	\$ 28,860
3.17	138kV, Surge arrester	9	EA	4,810.00	2,886.00	1,924.00	\$ 43,290	\$ 25,974	\$ 17,316	\$ 86,580
3.18	138kV, CCVT	0	EA	3,206.67	1,924.00	1,282.67	\$ -	\$ -	\$ -	\$ -
3.19	138kV, A Frame 50'	0	EA	33,000.00	19,800.00	13,200.00	\$ -	\$ -	\$ -	\$ -
3.20	AL. Bus Tubing, 5" SCH 80	240	LF	25.00	184.94	123.29	\$ 6,000	\$ 44,385	\$ 29,590	\$ 79,975
3.21	AL. Bus fittings	1	LS	30,240.00	30,240.00	15,120.00	\$ 30,240	\$ 30,240	\$ 15,120	\$ 75,600
3.22	Steel grating and support beams-transformer moat	259,680	LB	2.73	1.17	0.50	\$ 709,398	\$ 303,566	\$ 130,100	\$ 1,143,064
TOTAL - SUBSTATION STRUCTURES & GAS-INSULATED CONDUCTOR							\$ 1,692,012	\$ 862,489	\$ 392,825	\$ 2,947,326
4. MAJOR EQUIPMENT										
4.1	345kV, GIS air terminal	27	EA				\$ -	\$ -	\$ -	\$ -

Item	Item Description	Estimated Quantity	Unit of Measure	Material Supply Rate	Labor Supply Rate	Const. Equipment Rate	Material Supply Cost	Labor Supply Cost	Const. Equipment Cost	TOTAL COST
4.2	345kV, GIS Cable sealing end	0	EA				\$ -	\$ -	\$ -	\$ -
4.3	345kV, Cable sealing end	9	EA	17,400.00	5,460.00	2,340.00	\$ 156,600	\$ 49,140	\$ 21,060	\$ 226,800
4.4	345kV, CCVT	0	EA		15,941.99	6,832.28	\$ -	\$ -	\$ -	\$ -
4.5	345kV, Disconnect Switch	0	EA	57,720.00	34,632.00	23,088.00	\$ -	\$ -	\$ -	\$ -
4.6	345/138KV, Power Transformer with oil containment	3	EA	5,220,000.00	3,520.00	880.00	\$ 15,660,000	\$ 10,560	\$ 2,640	\$ 15,673,200
4.7	Transport & Testing- Transformer	3	EA		771,400.00	510,600.00	\$ -	\$ 2,314,200	\$ 1,531,800	\$ 3,846,000
4.8	345kV, Shunt Reactor with oil containment-150MVAR	0	EA		3,520.00	880.00	\$ -	\$ -	\$ -	\$ -
4.9	345kV, Shunt Reactor with oil containment-50 MVAR	3	EA	2,138,451.50	3,520.00	880.00	\$ 6,415,355	\$ 10,560	\$ 2,640	\$ 6,428,555
4.10	Transport & Testing- Shunt Reactor	3	EA		240,400.00	156,600.00	\$ -	\$ 721,200	\$ 469,800	\$ 1,191,000
4.11	345kV, Phase Angle Regulator with oil containment	0	EA		3,520.00	880.00	\$ -	\$ -	\$ -	\$ -
4.12	345kV, Gas Insulated Switchgear, BAAH Arrangement	12	BKR	847,083.33	508,250.00	338,833.33	\$ 10,165,000	\$ 6,099,000	\$ 4,066,000	\$ 20,330,000
4.13	345kV, Circuit Breaker (PASS)	0	EA		57,239.00	24,531.00	\$ -	\$ -	\$ -	\$ -
4.14	345kV, Circuit Breaker (GIS), outdoor rated	0	EA				\$ -	\$ -	\$ -	\$ -
4.15	345kV, Circuit Breaker (GIS), outdoor rated-Line surge Arrester ( 3phase)	0	EA				\$ -	\$ -	\$ -	\$ -
4.16	345kV, surge Arrester	6	EA	6,669.00	5,460.00	2,340.00	\$ 40,014	\$ 32,760	\$ 14,040	\$ 86,814
4.17	138kV, Phase Angle Regulator with oil containment	0	EA		3,520.00	880.00	\$ -	\$ -	\$ -	\$ -
4.18	Transport & Testing- Phase Angle Regulating Transformer, 138kV	0	EA		15,400.00	6,600.00	\$ -	\$ -	\$ -	\$ -
4.19	138kV, Gas Insulated Switchgear, BAAH Arrangement	0	BKR				\$ -	\$ -	\$ -	\$ -
4.20	138kV, Circuit Breaker, Hybrid circuit breaker	0	EA		13,559.00	5,811.00	\$ -	\$ -	\$ -	\$ -
4.21	138kV, Circuit Breaker-relocation only	1	EA		13,559.00	5,811.00	\$ -	\$ 13,559	\$ 5,811	\$ 19,370
4.22	138kV, Disconnect Switch-3 Ph	0	EA	37,700.00	11,875.50	5,089.50	\$ -	\$ -	\$ -	\$ -
4.23	138kV, Disconnect Switch- RELOCATION ONLY	2	EA		11,875.50	5,089.50	\$ -	\$ 23,751	\$ 10,179	\$ 33,930
4.24	138kV, Cable sealing end-3 Ph	15	EA	11,600.00	5,460.00	2,340.00	\$ 174,000	\$ 81,900	\$ 35,100	\$ 291,000
4.25	138kV, CCVT	0	EA		7,970.08	3,415.75	\$ -	\$ -	\$ -	\$ -
4.26	138kV, Surge arrester	9	EA	4,446.00	4,200.00	1,800.00	\$ 40,014	\$ 37,800	\$ 16,200	\$ 94,014
4.27	Station service transformers- 120/208v-250VA	2	EA	260,000.00	45,500.00	19,500.00	\$ 520,000	\$ 91,000	\$ 39,000	\$ 650,000
4.28	345kV Gas-Insulated Bus Conductor	1,008	LF	550.00	275.00	82.50	\$ 554,400	\$ 277,200	\$ 83,160	\$ 914,760.00
4.29	345kV Gas-Insulated Bus Conductor-elbow	18	EA	2,500.00	1,250.00	375.00	\$ 45,000	\$ 22,500	\$ 6,750	\$ 74,250
4.30	Transport & Testing- GIL	1	LS		107,892.00	71,928.00	\$ -	\$ 107,892	\$ 71,928	\$ 179,820
TOTAL - MAJOR EQUIPMENT							\$ 33,770,383	\$ 9,893,022	\$ 6,376,108	\$ 50,039,513
5. LOW VOLTAGE & CONTROL CABLE										
5.1	Control Cables	18,600	LF	5.30	1.43	0.29	\$ 98,534	\$ 26,645	\$ 5,329	\$ 130,507
5.2			LF		-	-	\$ -	\$ -	\$ -	\$ -
TOTAL - LOW VOLTAGE & CONTROL CABLE							\$ 98,534	\$ 26,645	\$ 5,329	\$ 130,507
6. CONDUIT & CABLE TRENCH										
6.1	Conduit, PVC, 6", SCH 40		LF	20.70	-	-	\$ -	\$ -	\$ -	\$ -
6.2	Conduit, PVC, 4", SCH 40	3,600	LF	11.15	10.80	5.40	\$ 40,140	\$ 38,880	\$ 19,440	\$ 98,460
6.3	Conduit, PVC, 3", SCH 40		LF	8.10	-	-	\$ -	\$ -	\$ -	\$ -
6.4	Conduit, PVC, 2", SCH 40		LF	3.95	-	-	\$ -	\$ -	\$ -	\$ -
6.5	Conduit, PVC, 1", SCH 40		LF	1.90	-	-	\$ -	\$ -	\$ -	\$ -
6.6	Cable Trench	1,325	LF	266.50	53.04	13.26	\$ 353,113	\$ 70,278	\$ 17,570	\$ 440,960
6.7										
6.8	138kV UG- Conduit	1,919	LF	266.73	202.15	100.00	\$ 511,963	\$ 388,000	\$ 191,949	\$ 1,091,913
6.9	138kV UG- Cable	5,758	LF	145.00	87.00	58.00	\$ 834,939	\$ 500,963	\$ 333,976	\$ 1,669,878
6.10	138kV UG- Termination	18	EA	27,805.00	9,846.48	2,813.28	\$ 500,490	\$ 177,237	\$ 50,639	\$ 728,366
6.11	345kV UG- Conduit	494	LF	266.73	202.15	100.00	\$ 131,632	\$ 99,759	\$ 49,352	\$ 280,743
6.12	345kV UG- Cable	1,481	LF	167.00	100.20	66.80	\$ 247,244	\$ 148,346	\$ 98,897	\$ 494,487
6.13	345kV UG- Termination	18	EA	27,805.00	9,846.48	2,813.28	\$ 500,490	\$ 177,237	\$ 50,639	\$ 728,366
6.14	Fiber Optic Cable	2,413	LF	7.40	3.33	2.22	\$ 17,848	\$ 8,036	\$ 5,358	\$ 31,242
6.15	Ground Continuity Conductor	2,413	LF	13.04	7.53	5.02	\$ 31,462	\$ 18,162	\$ 12,108	\$ 61,732
TOTAL - CONDUIT & CABLE TRENCH							\$ 3,169,320	\$ 1,626,898	\$ 829,928	\$ 5,626,146
7. GROUND GRID										
7.1	Cable, 4/0 AWG Bare Copper, 7 Strand Ground Conductor	10,200	LF	2.09	3.42	1.46	\$ 21,328	\$ 34,836	\$ 14,930	\$ 71,094
7.2	Caweld, DSA, 4/0 , T, CROSS	280	EA	165.00	75.00		\$ 46,200	\$ 21,000	\$ -	\$ 67,200
7.3	Ground Rod, 3/4" x 15'	243	EA	135.00	67.50	7.50	\$ 32,805	\$ 16,403	\$ 1,823	\$ 51,030
TOTAL - GROUND GRID							\$ 100,333	\$ 72,239	\$ 16,752	\$ 189,324
8. CONTROL ENCLOSURE										
8.1	345kv GIS Bldg	1	EA	2,926,829.03	2,048,780.32	878,048.71	\$ 2,926,829	\$ 2,048,780	\$ 878,049	\$ 5,853,658
8.2	138kv GIS/Control Bldg	0	EA	-	-	-	\$ -	\$ -	\$ -	\$ -
8.3	Primary Line Relays (87L): SEL-411L	3	EA	21,328.12	17,062.49	4,265.62	\$ 63,984	\$ 51,187	\$ 12,797	\$ 127,969
8.4	Backup Line Relays (87L): GE L90	3	EA	21,328.12	17,062.49	4,265.62	\$ 63,984	\$ 51,187	\$ 12,797	\$ 127,969
8.5	Primary Bay Control: SEL-451	4	EA	21,328.12	17,062.49	4,265.62	\$ 85,312	\$ 68,250	\$ 17,062	\$ 170,625
8.6	Backup Bay Control: SEL-451	4	EA	21,328.12	17,062.49	4,265.62	\$ 85,312	\$ 68,250	\$ 17,062	\$ 170,625
8.7	Primary Transformer/Reactor/PAR Differential Relays: SEL-487E	6	EA	21,328.12	17,062.49	4,265.62	\$ 127,969	\$ 102,375	\$ 25,594	\$ 255,937
8.8	Backup Transformer/Reactor/PAR Differential Relays: GE T60	6	EA	21,328.12	17,062.49	4,265.62	\$ 127,969	\$ 102,375	\$ 25,594	\$ 255,937
8.9	Primary Bus Differential Relays: SEL-487B	4	EA	21,328.12	17,062.49	4,265.62	\$ 85,312	\$ 68,250	\$ 17,062	\$ 170,625



Item	Item Description	Estimated Quantity	Unit of Measure	Material Supply Rate	Labor Supply Rate	Const. Equipment Rate	Material Supply Cost	Labor Supply Cost	Const. Equipment Cost	TOTAL COST
8.10	Backup Bus Differential Relays: GE B90	4	EA	21,328.12	17,062.49	4,265.62	\$ 85,312	\$ 68,250	\$ 17,062	\$ 170,625
8.11	RTU Panel A: SEL-2240 Axion, SEL-2730M ENET SW., SEL-2407 GPS, Modem, SEL-2523 Ann	1	EA	12,500.00	10,000.00	2,500.00	\$ 12,500	\$ 10,000	\$ 2,500	\$ 25,000
8.12	RTU Panel B: SEL-2730M Ethernet Switch, SEL-2407 GPS Clock, SEL-2523 Annunciator	1	EA	12,500.00	10,000.00	2,500.00	\$ 12,500	\$ 10,000	\$ 2,500	\$ 25,000
8.13	HMI Panel	1	EA	12,500.00	10,000.00	2,500.00	\$ 12,500	\$ 10,000	\$ 2,500	\$ 25,000
8.14	Primary Line Relays (87L): SEL-411L	1	EA	21,328.12	17,062.49	4,265.62	\$ 21,328	\$ 17,062	\$ 4,266	\$ 42,656
8.15	Backup Line Relays (87L): GE L90	1	EA	21,328.12	17,062.49	4,265.62	\$ 21,328	\$ 17,062	\$ 4,266	\$ 42,656
8.16	125VDC Battery System	2	LS	25,000.00	22,750.00	9,750.00	\$ 50,000	\$ 45,500	\$ 19,500	\$ 115,000
8.17	Control house AC Panel	2	EA	65,000.00	91,000.00	39,000.00	\$ 130,000	\$ 182,000	\$ 78,000	\$ 390,000
8.18	Control House DC Panel	2	EA	65,000.00	91,000.00	39,000.00	\$ 130,000	\$ 182,000	\$ 78,000	\$ 390,000
8.19	Generator	1	EA	130,000.00	72,800.00	31,200.00	\$ 130,000	\$ 72,800	\$ 31,200	\$ 234,000
TOTAL - CONTROL ENCLOSURE							\$ 4,172,141	\$ 3,175,330	\$ 1,245,811	\$ 8,593,282
3.Station 48 Valley Stream 345/138 kV Substation Upgrades							\$ 46,876,287	\$ 20,093,412	\$ 11,669,056	\$ 78,638,755
9. MOB/DEMOB, ENGINEERING, PERMITTING, T&C, PM & INDIRECTS										
	Contractor Mobilization / Demobilization									
9.1	Mob / Demob	1.0	LS		755,911.39	323,962.02	\$ -	\$ 755,911	\$ 323,962	\$ 1,079,873
	Project Management, Material Handling & Amenities									
9.2	Preconstruction Supervision (Engineering, Permitting, Procurement)	1	LS		583,087.55		\$ -	\$ 583,088	\$ -	\$ 583,088
9.3	Project Management & Staffing (includes PM, Field Engineers / Supervision, Scheduler and Cost Manager, SHEQ Staff, and Admin Staff)	1	LS		2,332,350.20		\$ -	\$ 2,332,350	\$ -	\$ 2,332,350
9.4	Utility PM and Project Oversight	1	LS		583,087.55		\$ -	\$ 583,088	\$ -	\$ 583,088
9.5	Site Accommodation, Facilities, Storage	1	LS	583,087.55			\$ 583,088	\$ -	\$ -	\$ 583,088
	Engineering									
9.6	Design Engineering	1.00	LS		6,291,100.41		\$ -	\$ 6,291,100	\$ -	\$ 6,291,100
9.7	LiDAR /GPR	-	LS		-		\$ -	\$ -	\$ -	\$ -
9.8	Geotech	5.00	EA		2,730.00	1,820.00	\$ -	\$ 13,650	\$ 9,100	\$ 22,750
9.9	Surveying/Staking	1.00	Site		408,161.29		\$ -	\$ 408,161	\$ -	\$ 408,161
	Testing & Commissioning									
9.10	Testing & Commissioning of SS and Equipment	1.00	LS		2,186,578.32		\$ -	\$ 2,186,578	\$ -	\$ 2,186,578
	Permitting and Additional Costs									
9.11	Physical Security	1.00	LS		6,546.96		\$ -	\$ 6,547	\$ -	\$ 6,547
9.12	Environmental Licensing & Permitting Costs & related legal cost	1.00	LS		583,087.55		\$ -	\$ 583,088	\$ -	\$ 583,088
9.13	Environmental-special studies/investigation	-	LS		-		\$ -	\$ -	\$ -	\$ -
9.14	Warranties / LOC's	1.00	LS		174,926.27		\$ -	\$ 174,926	\$ -	\$ 174,926
9.15	Laydown Lease	-	LS				\$ -	\$ -	\$ -	\$ -
9.16	Real Estate ( Acquisition)	1.00	LS		-	2,803,700.00	\$ -	\$ -	\$ 2,803,700	\$ 2,803,700
9.17	Legal Fees (Real estate)	1.00	LS		-	84,111.00	\$ -	\$ -	\$ 84,111	\$ 84,111
9.18	Insurance	-	LS		-	-	\$ -	\$ -	\$ -	\$ -
9.19	Bonds	1	LS		-	\$ 2,860,000	\$ -	\$ -	\$ 2,860,000	\$ 2,860,000
9.20	Sales Tax on Materials	8.80%	LS	46,876,286.85			\$ 4,125,113	\$ -	\$ -	\$ 4,125,113
9.21	Fees for permits, including roadway, railroad, building or other local permits	1.00	LS		78,638.76		\$ -	\$ 78,639	\$ -	\$ 78,639
TOTAL - MOB/DEMOB, ENGINEERING, PERMITTING, T&C, PM & INDIRECTS:							\$ 4,708,201	\$ 13,997,126	\$ 6,080,873	\$ 24,786,200

<u><b>NEXtera Energy- TO36 Core 1</b></u>	
<u><b>4.Barrett 138 kV Substation Upgrades</b></u>	
Total:	\$ 77,248,534

	Total:	\$	<b>77,248,534</b>
--	--------	----	-------------------

NEXtera Energy- TO36 Core 1				
	Material Supply	Labor Supply	Equip Supply	Total
4.Barrett 138 kV Substation Upgrades				
1. SITE PREP/ GRADING/ FENCING / CIVIL	\$ 944,373	\$ 647,031	\$ 373,996	\$ 1,965,400
2. SUBSTATION FOUNDATIONS	\$ 710,473	\$ 811,970	\$ 507,481	\$ 2,029,924
3. SUBSTATION STRUCTURES	\$ 309,543	\$ 377,952	\$ 233,921	\$ 921,416
4. MAJOR EQUIPMENT	\$ 17,187,548	\$ 4,238,507	\$ 2,776,589	\$ 24,202,643
5. LOW VOLTAGE & CONTROL CABLE	\$ 25,428	\$ 6,876	\$ 1,375	\$ 33,679
6. CONDUIT & CABLE TRENCH	\$ 3,912,346	\$ 2,183,727	\$ 1,172,833	\$ 7,268,907
7. GROUND GRID	\$ 75,572	\$ 54,743	\$ 12,811	\$ 143,125
8. CONTROL ENCLOSURE	\$ 2,347,937	\$ 1,894,121	\$ 702,815	\$ 4,944,874
9. MOB/DEMOB, ENGINEERING, PERMITTING, T&C, PM & INDIRECTS	\$ 2,545,363	\$ 6,349,462	\$ 5,317,732	\$ 14,212,557
Turnkey cost (HVDC, GIS)	\$ 5,745,000	\$ 3,447,000	\$ 2,298,000	\$ 11,490,000
Non-Turnkey cost	\$ 22,313,583	\$ 13,117,388	\$ 8,801,554	\$ 44,232,524
SUBTOTAL (Costs):	\$ 28,058,583	\$ 16,564,388	\$ 11,099,554	\$ 55,722,524
CONTRACTOR MARK-UP (OH&P)	\$ 4,361,145	\$ 2,567,950	\$ 1,722,160	\$ 8,651,254
SUBTOTAL:	\$ 32,419,728	\$ 19,132,338	\$ 12,821,713	\$ 64,373,779
CONTINGENCY ON ENTIRE PROJECT	\$ 6,483,946	\$ 3,826,468	\$ 2,564,343	\$ 12,874,756
TOTAL:	\$ 38,903,673	\$ 22,958,805	\$ 15,386,056	\$ 77,248,534

Description of Work: Construct a Barrett 138kV GIS substation adjacent to the existing Barrett 138kV substation.										
Item	Item Description	Estimated Quantity	Unit of Measure	Material Supply Rate	Labor Supply Rate	Const. Equipment Rate	Material Supply Cost	Labor Supply Cost	Const. Equipment Cost	TOTAL COST
4.Barrett 138 kV Substation Upgrades										
1. SITE PREP/ GRADING/ FENCING / CIVIL										
1.1	Site Clearing	2.2	ACRE	-	10,800.00	7,200.00	\$ -	\$ 23,760	\$ 15,840	\$ 39,600
1.2	Demolition	0	LS	-	600,000.00	400,000.00	\$ -	\$ -	\$ -	\$ -
1.3	New Access Road - 20'	2,115	SY	4.85	7.20	4.80	\$ 10,257	\$ 15,227	\$ 10,151	\$ 35,636
1.4	Strip and Dispose Top Soil	3,549	CY		24.50	10.50	\$ -	\$ 86,959	\$ 37,268	\$ 124,227
1.5	Site Grading- Excavation for Substation Pad	10,648	CY		9.00	6.00	\$ -	\$ 95,832	\$ 63,888	\$ 159,720
1.6	Site Grading- Excavation for Substation Pad-Rock excavation-Hauling and disposal	5,750	CY		21.00	9.00	\$ -	\$ 120,748.32	\$ 51,749.28	\$ 172,497.60
1.7	Site Grading- Fill for Substation Pad (site borrow, compacted in place)	8,625	CY		2.40	1.60	\$ -	\$ 20,700	\$ 13,800	\$ 34,500
1.8	Site Grading -Fill for Substation Pad (import, compacted in place)	5,750	CY	25.00	2.40	1.60	\$ 143,748	\$ 13,800	\$ 9,200	\$ 166,748
1.9	Blasting		EA				\$ -	\$ -	\$ -	\$ -
1.10	Install substation 8" pad base	10,648	SY	11.00	6.00	4.00	\$ 117,128	\$ 63,888	\$ 42,592	\$ 223,608
1.11	Site Surfacing - Aggregate 6" Thick	10,648	SY	16.50	4.50	3.00	\$ 175,692	\$ 47,916	\$ 31,944	\$ 255,552
1.12	7' Station Fence w/ Barbed Wire & Grounding	1,056	LF	13.85	13.85	6.92	\$ 14,623	\$ 14,623	\$ 7,312	\$ 36,559
1.13	20' Slide Gate & Grounding	1	EA	8,100.00	3,245.00	1,305.00	\$ 8,100	\$ 3,245	\$ 1,305	\$ 12,650
1.14	4' Pedestrian gate	1	EA	2,500.00	1,000.00	350.00	\$ 2,500	\$ 1,000	\$ 350	\$ 3,850
1.15	Storm drain-15" HDPE, INFILTRATION TRENCH, INLET and Hydrodynamic Separator	1	LS	446,976.00	115,200.00	76,104.00	\$ 446,976	\$ 115,200	\$ 76,104	\$ 638,280
1.16	Seeding	8,896	SF	1.50	1.50	1.00	\$ 13,344	\$ 13,344	\$ 8,896	\$ 35,584
1.17	Erosion Control-Silt fence install & remove	1,620	LF	2.41	3.16	0.72	\$ 3,904	\$ 5,119	\$ 1,166	\$ 10,190
1.18	Temporary fencing	1,080	LF	7.50	5.25	2.25	\$ 8,100	\$ 5,670	\$ 2,430	\$ 16,200
1.19	Substation entrance with asphalt	0	SY	19.50	26.00	19.50	\$ -	\$ -	\$ -	\$ -

Item	Item Description	Estimated Quantity	Unit of Measure	Material Supply Rate	Labor Supply Rate	Const. Equipment Rate	Material Supply Cost	Labor Supply Cost	Const. Equipment Cost	TOTAL COST
1.20	Concrete curb	0	LF	26.00	27.30	11.70	\$ -	\$ -	\$ -	\$ -
1.21	Retaining Wall	0	LF	156.00	117.00	117.00	\$ -	\$ -	\$ -	\$ -
TOTAL - SITE PREP/ GRADING/ FENCING / CIVIL							\$ 944,373	\$ 647,031	\$ 373,996	\$ 1,965,400
2. SUBSTATION FOUNDATIONS										
2.1	345kV, Lightning mast	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.2	345kV, A Frame 70'	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.3	345kV, Bus support-3 Ph	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.4	345kV, Bus support-3 Ph, low	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.5	345kV, Bus support-1 Ph	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.6	345kV, GIS air terminal	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.7	345kV, GIS support-1 Ph	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.8	345kV, GIS support-3 Ph	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.9	345kV, GIS Cable sealing end	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.10	345kV, Cable sealing end	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.11	345kV, CCVT	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.12	345kV, Disconnect Switch	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.13	345/138KV, Power Transformer with oil containment	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.14	345kV, Shunt Reactor with oil containment-150MVAR	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.15	345kV, Shunt Reactor with oil containment-100MVAR	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.16	345kV, Phase Angle Regulator with oil containment	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.17	345kV, Circuit Breaker (PASS)	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.18	345kV, Circuit Breaker (GIS), outdoor rated	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.19	345Kv, GIS Enclosure-BLDG with generator pad	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.20	345kV, Surge arrester	-	CY	-	-	-	\$ -	\$ -	\$ -	\$ -
2.21	138kV, Phase Angle Regulator with oil containment	154	CY	703.89	804.44	502.78	\$ 108,398	\$ 123,884	\$ 77,427	\$ 309,709
2.22	138kV, Circuit Breaker, Hybrid circuit breaker	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.23	138kV, Bus support-3 Ph, low	128	CY	703.89	804.44	502.78	\$ 90,379	\$ 103,290	\$ 64,556	\$ 258,225
2.24	138kV, Bus support-1 Ph, low	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.25	138kV, Disconnect Switch	73	CY	703.89	804.44	502.78	\$ 51,187	\$ 58,499	\$ 36,562	\$ 146,247
2.26	138kV, Cable sealing end	24	CY	703.89	804.44	502.78	\$ 17,062	\$ 19,500	\$ 12,187	\$ 48,749
2.27	138kV, Surge arrester	32	CY	-	-	-	\$ -	\$ -	\$ -	\$ -
2.28	138kV, CCVT	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.29	138kV, A Frame 50'	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.30	Firewall Foundation	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.31	Precast Firewall for transformer, PARs, reactors	-	SF	25.00	15.00	10.00	\$ -	\$ -	\$ -	\$ -
2.32	Precast Concrete Piles-12"X80'	-	EA	18,000.00	3,200.00	2,800.00	\$ -	\$ -	\$ -	\$ -
2.33	Local Control Cabinet foundation	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.34	138kV, GIS Enclosure-BLDG & control room	630	CY	703.89	804.44	502.78	\$ 443,448	\$ 506,797	\$ 316,748	\$ 1,266,993
TOTAL - 345KV FOUNDATION							\$ 710,473	\$ 811,970	\$ 507,481	\$ 2,029,924
3. SUBSTATION STRUCTURES										
3.1	345kV, Lightning mast	0	EA				\$ -	\$ -	\$ -	\$ -
3.2	345kV, A Frame 70'	0	EA	48,100.00	28,860.00	19,240.00	\$ -	\$ -	\$ -	\$ -
3.3	345kV, Bus support-3 Ph	0	EA	8,346.00	5,758.74	3,839.16	\$ -	\$ -	\$ -	\$ -
3.4	345kV, Bus support-3 Ph, low	0	EA	8,346.00	5,758.74	3,839.16	\$ -	\$ -	\$ -	\$ -
3.5	345kV, Bus support-1 Ph	0	EA	4,810.00	2,886.00	1,924.00	\$ -	\$ -	\$ -	\$ -
3.6	345kV, GIS air terminal	0	EA	8,346.00	5,758.74	3,839.16	\$ -	\$ -	\$ -	\$ -
3.7	345kV, GIS support-1 Ph	0	EA	8,346.00	5,758.74	3,839.16	\$ -	\$ -	\$ -	\$ -
3.8	345kV, GIS support-3 Ph	0	EA	4,810.00	2,886.00	1,924.00	\$ -	\$ -	\$ -	\$ -
3.9	345kV, GIS Cable sealing end	0	EA	8,346.00	5,758.74	3,839.16	\$ -	\$ -	\$ -	\$ -
3.10	345kV, Cable sealing end	0	EA	8,346.00	5,758.74	3,839.16	\$ -	\$ -	\$ -	\$ -
3.11	345kV, CCVT	0	EA	4,810.00	2,886.00	1,924.00	\$ -	\$ -	\$ -	\$ -
3.12	345kV, Disconnect Switch	0	EA	19,240.00	11,544.00	7,696.00	\$ -	\$ -	\$ -	\$ -
3.13	138kV, Bus support-3 Ph, low	12	EA	4,173.00	2,879.76	1,919.84	\$ 50,076	\$ 34,557	\$ 23,038	\$ 107,671
3.14	138kV, Bus support-1 Ph, low	0	EA	2,782.00	1,919.84	1,279.89	\$ -	\$ -	\$ -	\$ -
3.15	138kV, Disconnect Switch	3	EA	12,251.20	3,928.86	2,619.24	\$ 36,754	\$ 11,787	\$ 7,858	\$ 56,398
3.16	138kV, Cable sealing end	2	EA	4,810.00	2,886.00	1,924.00	\$ 9,620	\$ 5,772	\$ 3,848	\$ 19,240
3.17	138kV, Surge arrester	6	EA	4,810.00	2,886.00	1,924.00	\$ 28,860	\$ 17,316	\$ 11,544	\$ 57,720
3.18	138kV, CCVT	0	EA	3,206.67	1,924.00	1,282.67	\$ -	\$ -	\$ -	\$ -
3.19	138kV, A Frame 50'	0	EA	33,000.00	19,800.00	13,200.00	\$ -	\$ -	\$ -	\$ -
3.20	AL Bus Tubing, 5" SCH 80	1,200	LF	25.00	184.94	123.29	\$ 30,000	\$ 221,926	\$ 147,950	\$ 399,876
3.21	AL Bus fittings	1	LS	36,000.00	36,000.00	18,000.00	\$ 36,000	\$ 36,000	\$ 18,000	\$ 90,000
3.22	Steel grating and support beams-transformer moat	43,280	LB	2.73	1.17	0.50	\$ 118,233	\$ 50,594	\$ 21,683	\$ 190,511
TOTAL - SUBSTATION STRUCTURES & GAS-INSULATED CONDUCTOR							\$ 309,543	\$ 377,952	\$ 233,921	\$ 921,416

Item	Item Description	Estimated Quantity	Unit of Measure	Material Supply Rate	Labor Supply Rate	Const. Equipment Rate	Material Supply Cost	Labor Supply Cost	Const. Equipment Cost	TOTAL COST
<b>4. MAJOR EQUIPMENT</b>										
4.1	345kV, GIS air terminal	0	EA				\$ -	\$ -	\$ -	\$ -
4.2	345kV, GIS Cable sealing end	0	EA				\$ -	\$ -	\$ -	\$ -
4.3	345kV, Cable sealing end	0	EA		5,460.00	2,340.00	\$ -	\$ -	\$ -	\$ -
4.4	345kV, CCVT	0	EA		15,941.99	6,832.28	\$ -	\$ -	\$ -	\$ -
4.5	345kV, Disconnect Switch	0	EA		7,234.50	3,100.50	\$ -	\$ -	\$ -	\$ -
4.6	345/138KV, Power Transformer with oil containment	0	EA		3,520.00	880.00	\$ -	\$ -	\$ -	\$ -
4.7	Transport & Testing- Transformer	0	EA		15,400.00	6,600.00	\$ -	\$ -	\$ -	\$ -
4.8	345kV, Shunt Reactor with oil containment-150MVAR	0	EA		3,520.00	880.00	\$ -	\$ -	\$ -	\$ -
4.9	345kV, Shunt Reactor with oil containment-100MVAR	0	EA		3,520.00	880.00	\$ -	\$ -	\$ -	\$ -
4.10	Transport & Testing- Shunt Reactor	0	EA		15,400.00	6,600.00	\$ -	\$ -	\$ -	\$ -
4.11	345kV, Phase Angle Regulator with oil containment	0	EA		3,520.00	880.00	\$ -	\$ -	\$ -	\$ -
4.12	345kV, Gas Insulated Switchgear, BAAH Arrangement	0	BKR		205,800.00	4,200.00	\$ -	\$ -	\$ -	\$ -
4.13	345kV, Circuit Breaker (PASS)	0	EA		57,239.00	24,531.00	\$ -	\$ -	\$ -	\$ -
4.14	345kV, Circuit Breaker (GIS), outdoor rated	0	EA				\$ -	\$ -	\$ -	\$ -
4.15	345kV, Circuit Breaker (GIS), outdoor rated-Line surge Arrester ( 3phase)	0	EA				\$ -	\$ -	\$ -	\$ -
4.16	345kV, surge Arrester	0	EA		5,460.00	2,340.00	\$ -	\$ -	\$ -	\$ -
4.17	138kV, Phase Angle Regulator with oil containment	1	EA	10,713,172.00	3,520.00	880.00	\$ 10,713,172	\$ 3,520	\$ 880	\$ 10,717,572
4.18	Transport & Testing- Phase Angle Regulating Transformer, 138kV	1	EA		603,400.00	398,600.00	\$ -	\$ 603,400	\$ 398,600	\$ 1,002,000
4.19	138kV, Gas Insulated Switchgear, BAAH Arrangement	12	BKR	478,750.00	287,250.00	191,500.00	\$ 5,745,000	\$ 3,447,000	\$ 2,298,000	\$ 11,490,000
4.20	138kV, Circuit Breaker, Hybrid circuit breaker	0	EA		13,559.00	5,811.00	\$ -	\$ -	\$ -	\$ -
4.21	138kV, Disconnect Switch	3	EA	37,700.00	11,875.50	5,089.50	\$ 113,100	\$ 35,627	\$ 15,269	\$ 163,995
4.22	138kV, Cable sealing end	6	EA	11,600.00	5,460.00	2,340.00	\$ 69,600	\$ 32,760	\$ 14,040	\$ 116,400
4.23	138kV, CCVT	0	EA		7,970.08	3,415.75	\$ -	\$ -	\$ -	\$ -
4.24	138kV, Surge arrester	6	EA	4,446.00	4,200.00	1,800.00	\$ 26,676	\$ 25,200	\$ 10,800	\$ 62,676
4.25	Station service transformers- 120/208v-250VA	2	EA	260,000.00	45,500.00	19,500.00	\$ 520,000	\$ 91,000	\$ 39,000	\$ 650,000
4.26	345kV Gas-Insulated Bus Conductor	0	LF	550.00	275.00	82.50	\$ -	\$ -	\$ -	\$ -
4.27	345kV Gas-Insulated Bus Conductor-elbow	0	EA	2,500.00	1,250.00	375.00	\$ -	\$ -	\$ -	\$ -
4.28	Transport & Testing- GIL	0	LS		-	-	\$ -	\$ -	\$ -	\$ -
<b>TOTAL - MAJOR EQUIPMENT</b>							\$ 17,187,548	\$ 4,238,507	\$ 2,776,589	\$ 24,202,643
<b>5. LOW VOLTAGE &amp; CONTROL CABLE</b>										
5.1	Control Cables	4,800	LF	5.30	1.43	0.29	\$ 25,428	\$ 6,876	\$ 1,375	\$ 33,679
5.2			LF		-	-	\$ -	\$ -	\$ -	\$ -
<b>TOTAL - LOW VOLTAGE &amp; CONTROL CABLE</b>							\$ 25,428	\$ 6,876	\$ 1,375	\$ 33,679
<b>6. CONDUIT &amp; CABLE TRENCH</b>										
6.1	Conduit, PVC, 6", SCH 40		LF	20.70	13.28	6.64	\$ -	\$ -	\$ -	\$ -
6.2	Conduit, PVC, 4", SCH 40	1,050	LF	11.15	10.80	5.40	\$ 11,708	\$ 11,340	\$ 5,670	\$ 28,718
6.3	Conduit, PVC, 3", SCH 40		LF	8.10	10.80	5.40	\$ -	\$ -	\$ -	\$ -
6.4	Conduit, PVC, 2", SCH 40		LF	3.95	10.80	5.40	\$ -	\$ -	\$ -	\$ -
6.5	Conduit, PVC, 1", SCH 40		LF	1.90	10.80	5.40	\$ -	\$ -	\$ -	\$ -
6.6	Cable Trench	700	LF	266.50	53.04	13.26	\$ 186,550	\$ 37,128	\$ 9,282	\$ 232,960
6.7							\$ -	\$ -	\$ -	\$ -
6.8	138kV UG- Conduit	3,757	LF	266.73	202.15	100.00	\$ 1,002,081	\$ 759,444	\$ 375,708	\$ 2,137,234
6.9	138kV UG- Cable	11,271	LF	145.00	87.00	58.00	\$ 1,634,252	\$ 980,551	\$ 653,701	\$ 3,268,503
6.10	138kV UG- Termination	36	EA	27,805.00	9,846.48	2,813.28	\$ 1,000,980	\$ 354,473	\$ 101,278	\$ 1,456,731
6.11	345kV UG- Conduit		LF	266.73	202.15	100.00	\$ -	\$ -	\$ -	\$ -
6.12	345kV UG- Cable		LF	167.00	100.20	66.80	\$ -	\$ -	\$ -	\$ -
6.13	345kV UG- Termination		EA	27,805.00	9,846.48	2,813.28	\$ -	\$ -	\$ -	\$ -
6.14	Fiber Optic Cable	3,757	LF	7.40	3.33	2.22	\$ 27,790	\$ 12,513	\$ 8,342	\$ 48,644
6.15	Ground Continuity Conductor	3,757	LF	13.04	7.53	5.02	\$ 48,986	\$ 28,278	\$ 18,852	\$ 96,117
<b>TOTAL - CONDUIT &amp; CABLE TRENCH</b>							\$ 3,912,346	\$ 2,183,727	\$ 1,172,833	\$ 7,268,907
<b>7. GROUND GRID</b>										
7.1	Cable, 4/0 AWG Bare Copper, 7 Strand Ground Conductor	7,820	LF	2.09	3.42	1.46	\$ 16,352	\$ 26,708	\$ 11,446	\$ 54,505
7.2	Caweld, DSA, 4/0 , T, CROSS	210	EA	165.00	75.00		\$ 34,650	\$ 15,750	\$ -	\$ 50,400
7.3	Ground Rod, 3/4" x 15'	182	EA	135.00	67.50	7.50	\$ 24,570	\$ 12,285	\$ 1,365	\$ 38,220
<b>TOTAL - GROUND GRID</b>							\$ 75,572	\$ 54,743	\$ 12,811	\$ 143,125
<b>8. CONTROL ENCLOSURE</b>										
8.1	345kv GIS Bldg	0	EA	2,926,829.03	2,048,780.32	878,048.71	\$ -	\$ -	\$ -	\$ -
8.2	138kv GIS/Control Bldg	1	EA	1,145,280.92	801,696.65	343,584.28	\$ 1,145,281	\$ 801,697	\$ 343,584	\$ 2,290,562
8.3	Primary Line Relays (87L): SEL-411L	5	EA	21,328.12	17,062.49	4,265.62	\$ 106,641	\$ 85,312	\$ 21,328	\$ 213,281
8.4	Backup Line Relays (87L): GE L90	5	EA	21,328.12	17,062.49	4,265.62	\$ 106,641	\$ 85,312	\$ 21,328	\$ 213,281
8.5	Primary Bay Control: SEL-451	4	EA	21,328.12	17,062.49	4,265.62	\$ 85,312	\$ 68,250	\$ 17,062	\$ 170,625
8.6	Backup Bay Control: SEL-451	4	EA	21,328.12	17,062.49	4,265.62	\$ 85,312	\$ 68,250	\$ 17,062	\$ 170,625
8.7	Primary Transformer/Reactor/PAR Differential Relays: SEL-487E	1	EA	21,328.12	17,062.49	4,265.62	\$ 21,328	\$ 17,062	\$ 4,266	\$ 42,656

Item	Item Description	Estimated Quantity	Unit of Measure	Material Supply Rate	Labor Supply Rate	Const. Equipment Rate	Material Supply Cost	Labor Supply Cost	Const. Equipment Cost	TOTAL COST
8.8	Backup Transformer/Reactor/PAR Differential Relays: GE T60	1	EA	21,328.12	17,062.49	4,265.62	\$ 21,328	\$ 17,062	\$ 4,266	\$ 42,656
8.9	Primary Bus Differential Relays: SEL-487B	5	EA	21,328.12	17,062.49	4,265.62	\$ 106,641	\$ 85,312	\$ 21,328	\$ 213,281
8.10	Backup Bus Differential Relays: GE B90	5	EA	21,328.12	17,062.49	4,265.62	\$ 106,641	\$ 85,312	\$ 21,328	\$ 213,281
8.11	RTU Panel A: SEL-2240 Axion, SEL-2730M ENET SW., SEL-2407 GPS, Modem, SEL-2523 Ann	1	EA	12,500.00	10,000.00	2,500.00	\$ 12,500	\$ 10,000	\$ 2,500	\$ 25,000
8.12	RTU Panel B: SEL-2730M Ethernet Switch, SEL-2407 GPS Clock, SEL-2523 Annunciator	1	EA	12,500.00	10,000.00	2,500.00	\$ 12,500	\$ 10,000	\$ 2,500	\$ 25,000
8.13	HMI Panel	1	EA	12,500.00	10,000.00	2,500.00	\$ 12,500	\$ 10,000	\$ 2,500	\$ 25,000
8.14	Primary Line Relays (87L): SEL-411L	2	EA	21,328.12	17,062.49	4,265.62	\$ 42,656	\$ 34,125	\$ 8,531	\$ 85,312
8.15	Backup Line Relays (87L): GE L90	2	EA	21,328.12	17,062.49	4,265.62	\$ 42,656	\$ 34,125	\$ 8,531	\$ 85,312
8.16	125VDC Battery System	2	LS	25,000.00	22,750.00	9,750.00	\$ 50,000	\$ 45,500	\$ 19,500	\$ 115,000
8.17	Control house AC Panel	2	EA	65,000.00	91,000.00	39,000.00	\$ 130,000	\$ 182,000	\$ 78,000	\$ 390,000
8.18	Control House DC Panel	2	EA	65,000.00	91,000.00	39,000.00	\$ 130,000	\$ 182,000	\$ 78,000	\$ 390,000
8.19	Generator	1	EA	130,000.00	72,800.00	31,200.00	\$ 130,000	\$ 72,800	\$ 31,200	\$ 234,000
TOTAL - CONTROL ENCLOSURE							\$ 2,347,937	\$ 1,894,121	\$ 702,815	\$ 4,944,874
4.Barrett 138 kV Substation Upgrades							\$ 25,513,220	\$ 10,214,926	\$ 5,781,821	\$ 41,509,967
9. MOB/DEMOB, ENGINEERING, PERMITTING, T&C, PM & INDIRECTS										
	Contractor Mobilization / Demobilization									
9.1	Mob / Demob	1.0	LS		358,811.17	153,776.22	\$ -	\$ 358,811	\$ 153,776	\$ 512,587
	Project Management, Material Handling & Amenities									
9.2	Preconstruction Supervision (Engineering, Permitting, Procurement)	1	LS		300,199.67		\$ -	\$ 300,200	\$ -	\$ 300,200
9.3	Project Management & Staffing (includes PM, Field Engineers / Supervision, Scheduler and Cost Manager, SHEQ Staff, and Admin Staff)	1	LS		1,200,798.69		\$ -	\$ 1,200,799	\$ -	\$ 1,200,799
9.4	Utility PM and Project Oversight	1	LS		300,199.67		\$ -	\$ 300,200	\$ -	\$ 300,200
9.5	Site Accommodation, Facilities, Storage	1	LS	300,199.67			\$ 300,200	\$ -	\$ -	\$ 300,200
	Engineering									
9.6	Design Engineering	1.00	LS		2,401,597.39		\$ -	\$ 2,401,597	\$ -	\$ 2,401,597
9.7	LiDAR /GPR	-	LS		-		\$ -	\$ -	\$ -	\$ -
9.8	Geotech	5.00	EA		2,730.00	1,820.00	\$ -	\$ 13,650	\$ 9,100	\$ 22,750
9.9	Surveying/Staking	1.00	Site		210,139.77		\$ -	\$ 210,140	\$ -	\$ 210,140
	Testing & Commissioning									
9.10	Testing & Commissioning of SS and Equipment	1.00	LS		1,125,748.78		\$ -	\$ 1,125,749	\$ -	\$ 1,125,749
	Permitting and Additional Costs									
9.11	Physical Security	1.00	LS		6,546.96		\$ -	\$ 6,547	\$ -	\$ 6,547
9.12	Environmental Licensing & Permitting Costs & related legal cost	1.00	LS		300,199.67		\$ -	\$ 300,200	\$ -	\$ 300,200
9.13	Environmental-special studies/investigation	1.00	LS		-	1,600,000.00	\$ -	\$ -	\$ 1,600,000	\$ 1,600,000
9.14	Warranties / LOC's	1.00	LS		90,059.90		\$ -	\$ 90,060	\$ -	\$ 90,060
9.15	Laydown Lease	-	LS				\$ -	\$ -	\$ -	\$ -
9.16	Real Estate ( Acquisition)	1.00	LS		-	1,956,171.00	\$ -	\$ -	\$ 1,956,171	\$ 1,956,171
9.17	Legal Fees (Real estate)	1.00	LS		-	58,685.13	\$ -	\$ -	\$ 58,685	\$ 58,685
9.18	Insurance	-	LS		-	-	\$ -	\$ -	\$ -	\$ -
9.19	Bonds	1	LS		-	\$ 1,540,000	\$ -	\$ -	\$ 1,540,000	\$ 1,540,000
9.20	Sales Tax on Materials	8.80%	LS	25,513,219.69			\$ 2,245,163	\$ -	\$ -	\$ 2,245,163
9.21	Fees for permits, including roadway, railroad, building or other local permits	1.00	LS		41,509.97		\$ -	\$ 41,510	\$ -	\$ 41,510
TOTAL - MOB/DEMOB, ENGINEERING, PERMITTING, T&C, PM & INDIRECTS:							\$ 2,545,363	\$ 6,349,462	\$ 5,317,732	\$ 14,212,557



## **5.Dunwoodie 345 kV GIS Substation**

NEXtera Energy- TO36 Core 1				
	Material Supply	Labor Supply	Equip Supply	Total
5.Dunwoodie 345 kV GIS Substation				
1. SITE PREP/ GRADING/ FENCING / CIVIL	\$ 715,227	\$ 492,489	\$ 284,198	\$ 1,491,913
2. SUBSTATION FOUNDATIONS	\$ 1,502,773	\$ 1,654,755	\$ 1,037,109	\$ 4,194,637
3. SUBSTATION STRUCTURES	\$ 118,233	\$ 50,594	\$ 21,683	\$ 190,511
4. MAJOR EQUIPMENT	\$ 13,711,425	\$ 6,531,420	\$ 4,327,480	\$ 24,570,325
5. LOW VOLTAGE & CONTROL CABLE	\$ 7,946	\$ 2,149	\$ 430	\$ 10,525
6. CONDUIT & CABLE TRENCH	\$ 193,893	\$ 41,164	\$ 11,101	\$ 246,157
7. GROUND GRID	\$ 38,496	\$ 27,323	\$ 6,181	\$ 72,001
8. CONTROL ENCLOSURE	\$ 3,554,098	\$ 2,647,434	\$ 1,025,664	\$ 7,227,196
9. MOB/DEMOB, ENGINEERING, PERMITTING, T&C, PM & INDIRECTS	\$ 1,922,837	\$ 3,828,536	\$ 3,989,193	\$ 9,740,565
Turnkey cost (HVDC, GIS)	\$ 10,165,000	\$ 6,099,000	\$ 4,066,000	\$ 20,330,000
Non-Turnkey cost	\$ 11,599,927	\$ 9,176,864	\$ 6,637,039	\$ 27,413,830
SUBTOTAL (Costs):	\$ 21,764,927	\$ 15,275,864	\$ 10,703,039	\$ 47,743,830
CONTRACTOR MARK-UP (OH&P)	\$ 2,697,887	\$ 2,017,775	\$ 1,438,627	\$ 6,154,289
SUBTOTAL:	\$ 24,462,814	\$ 17,293,639	\$ 12,141,665	\$ 53,898,119
CONTINGENCY ON ENTIRE PROJECT	\$ 4,892,563	\$ 3,458,728	\$ 2,428,333	\$ 10,779,624
TOTAL:	\$ 29,355,377	\$ 20,752,367	\$ 14,569,999	\$ 64,677,743

Description of Work: Construct a new Dunwoodie 345kV GIS substation. Loop in the Pleasantville (2) and Sprain Brook lines and connect back to the existing Dunwoodie 345kV substation.										
Item	Item Description	Estimated Quantity	Unit of Measure	Material Supply Rate	Labor Supply Rate	Const. Equipment Rate	Material Supply Cost	Labor Supply Cost	Const. Equipment Cost	TOTAL COST
5.Dunwoodie 345 kV GIS Substation										
1. SITE PREP / GRADING/ FENCING / CIVIL										
1.1	Site Clearing	1.6	ACRE	-	10,800.00	7,200.00	\$ -	\$ 17,137	\$ 11,425	\$ 28,562
1.2	Demolition	0	LS	-	600,000.00	400,000.00	\$ -	\$ -	\$ -	\$ -
1.3	New Access Road - 20'	1,263	SY	4.85	7.20	4.80	\$ 6,124	\$ 9,092	\$ 6,061	\$ 21,278
1.4	Strip and Dispose Top Soil	2,560	CY		24.50	10.50	\$ -	\$ 62,720	\$ 26,880	\$ 89,600
1.5	Site Grading- Excavation for Substation Pad	7,680	CY		9.00	6.00	\$ -	\$ 69,120	\$ 46,080	\$ 115,200
1.6	Site Grading- Excavation for Substation Pad-Rock excavation-Hauling and disposal	4,147	CY		21.00	9.00	\$ -	\$ 87,091.20	\$ 37,324.80	\$ 124,416.00
1.7	Site Grading- Fill for Substation Pad (site borrow, compacted in place)	6,221	CY		2.40	1.60	\$ -	\$ 14,930	\$ 9,953	\$ 24,883
1.8	Site Grading -Fill for Substation Pad (import, compacted in place)	4,147	CY	25.00	2.40	1.60	\$ 103,680	\$ 9,953	\$ 6,636	\$ 120,269
1.9	Blasting		EA				\$ -	\$ -	\$ -	\$ -
1.10	Install substation 8" pad base	7,680	SY	11.00	6.00	4.00	\$ 84,480	\$ 46,080	\$ 30,720	\$ 161,280
1.11	Site Surfacing - Aggregate 6" Thick	7,680	SY	16.50	4.50	3.00	\$ 126,720	\$ 34,560	\$ 23,040	\$ 184,320
1.12	7' Station Fence w/ Barbed Wire & Grounding	864	LF	13.85	13.85	6.92	\$ 11,965	\$ 11,965	\$ 5,982	\$ 29,912
1.13	20' Slide Gate & Grounding	2	EA	8,100.00	3,245.00	1,305.00	\$ 16,200	\$ 6,490	\$ 2,610	\$ 25,300
1.14	4' Pedestrian gate	2	EA	2,500.00	1,000.00	350.00	\$ 5,000	\$ 2,000	\$ 700	\$ 7,700
1.15	Storm drain-15" HDPE, INFILTRATION TRENCH, INLET and Hydrodynamic Separator	1	LS	325,073.45	83,781.82	55,348.36	\$ 325,073	\$ 83,782	\$ 55,348	\$ 464,204
1.16	Seeding	7,296	SF	1.50	1.50	1.00	\$ 10,944	\$ 10,944	\$ 7,296	\$ 29,184
1.17	Erosion Control-Silt fence install & remove	2,100	LF	2.41	3.16	0.72	\$ 5,061	\$ 6,636	\$ 1,512	\$ 13,209
1.18	Temporary fencing	1,400	LF	7.50	5.25	2.25	\$ 10,500	\$ 7,350	\$ 3,150	\$ 21,000
1.19	Substation entrance with asphalt	486	SY	19.50	26.00	19.50	\$ 9,479	\$ 12,639	\$ 9,479	\$ 31,597

Item	Item Description	Estimated Quantity	Unit of Measure	Material Supply Rate	Labor Supply Rate	Const. Equipment Rate	Material Supply Cost	Labor Supply Cost	Const. Equipment Cost	TOTAL COST
1.20	Concrete curb	0	LF	26.00	27.30	11.70	\$ -	\$ -	\$ -	\$ -
1.21	Retaining Wall	0	LF	156.00	117.00	117.00	\$ -	\$ -	\$ -	\$ -
TOTAL - SITE PREP/ GRADING/ FENCING / CIVIL							\$ 715,227	\$ 492,489	\$ 284,198	\$ 1,491,913
2. SUBSTATION FOUNDATIONS										
2.1	345kV, Lightning mast	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.2	345kV, A Frame 70'	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.3	345kV, Bus support-3 Ph	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.4	345kV, Bus support-3 Ph, low	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.5	345kV, Bus support-1 Ph	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.6	345kV, GIS air terminal	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.7	345kV, GIS support-1 Ph	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.8	345kV, GIS support-3 Ph	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.9	345kV, GIS Cable sealing end	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.10	345kV, Cable sealing end	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.11	345kV, CCVT	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.12	345kV, Disconnect Switch	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.13	345/138KV, Power Transformer with oil containment	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.14	345kV, Shunt Reactor with oil containment-225MVAR	305	CY	703.89	804.44	502.78	\$ 214,685	\$ 245,354	\$ 153,346	\$ 613,386
2.15	345kV, Shunt Reactor with oil containment-100MVAR	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.16	345kV, Phase Angle Regulator with oil containment	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.17	345kV, Circuit Breaker (PASS)	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.18	345kV, Circuit Breaker (GIS), outdoor rated	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.19	345Kv, GIS Enclosure-BLDG with generator pad	1,357	CY	703.89	804.44	502.78	\$ 955,172	\$ 1,091,625	\$ 682,266	\$ 2,729,063
2.20	345kV, Surge arrester	48	CY	-	-	-	\$ -	\$ -	\$ -	\$ -
2.21	138kV, Phase Angle Regulator with oil containment	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.22	138kV, Circuit Breaker, Hybrid circuit breaker	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.23	138kV, Bus support-3 Ph, low	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.24	138kV, Bus support-1 Ph, low	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.25	138kV, Disconnect Switch	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.26	138kV, Cable sealing end	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.27	138kV, Surge arrester	-	CY	-	-	-	\$ -	\$ -	\$ -	\$ -
2.28	138kV, CCVT	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.29	138kV, A Frame 50'	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.30	Firewall Foundation	309	CY	703.89	804.44	502.78	\$ 217,416	\$ 248,475	\$ 155,297	\$ 621,189
2.31	Precast Firewall for transformer, PARs, reactors	4,620	SF	25.00	15.00	10.00	\$ 115,500	\$ 69,300	\$ 46,200	\$ 231,000
2.32	Precast Concrete Piles-12"X80'	-	EA	18,000.00	3,200.00	2,800.00	\$ -	\$ -	\$ -	\$ -
2.33	Local Control Cabinet foundation	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.34	138kV, GIS Enclosure-BLDG & control room	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
TOTAL - 345KV FOUNDATION							\$ 1,502,773	\$ 1,654,755	\$ 1,037,109	\$ 4,194,637
3. SUBSTATION STRUCTURES										
3.1	345kV, Lightning mast	0	EA				\$ -	\$ -	\$ -	\$ -
3.2	345kV, A Frame 70'	0	EA	48,100.00	28,860.00	19,240.00	\$ -	\$ -	\$ -	\$ -
3.3	345kV, Bus support-3 Ph	0	EA	8,346.00	5,758.74	3,839.16	\$ -	\$ -	\$ -	\$ -
3.4	345kV, Bus support-3 Ph, low	0	EA	8,346.00	5,758.74	3,839.16	\$ -	\$ -	\$ -	\$ -
3.5	345kV, Bus support-1 Ph	0	EA	4,810.00	2,886.00	1,924.00	\$ -	\$ -	\$ -	\$ -
3.6	345kV, GIS air terminal	0	EA	8,346.00	5,758.74	3,839.16	\$ -	\$ -	\$ -	\$ -
3.7	345kV, GIS support-1 Ph	0	EA	8,346.00	5,758.74	3,839.16				\$ -
3.8	345kV, GIS support-3 Ph	0	EA	4,810.00	2,886.00	1,924.00	\$ -	\$ -	\$ -	\$ -
3.9	345kV, GIS Cable sealing end	0	EA	8,346.00	5,758.74	3,839.16	\$ -	\$ -	\$ -	\$ -
3.10	345kV, Cable sealing end	0	EA	8,346.00	5,758.74	3,839.16	\$ -	\$ -	\$ -	\$ -
3.11	345kV, CCVT	0	EA	4,810.00	2,886.00	1,924.00	\$ -	\$ -	\$ -	\$ -
3.12	345kV, Disconnect Switch	0	EA	19,240.00	11,544.00	7,696.00	\$ -	\$ -	\$ -	\$ -
3.13	138kV, Bus support-3 Ph, low	0	EA	4,173.00	2,879.76	1,919.84	\$ -	\$ -	\$ -	\$ -
3.14	138kV, Bus support-1 Ph, low	0	EA	2,782.00	1,919.84	1,279.89	\$ -	\$ -	\$ -	\$ -
3.15	138kV, Disconnect Switch	0	EA				\$ -	\$ -	\$ -	
3.16	138kV, Cable sealing end	0	EA	4,810.00	2,886.00	1,924.00	\$ -	\$ -	\$ -	\$ -
3.17	138kV, Surge arrester	0	EA	4,810.00	2,886.00	1,924.00	\$ -	\$ -	\$ -	\$ -
3.18	138kV, CCVT	0	EA	3,206.67	1,924.00	1,282.67	\$ -	\$ -	\$ -	\$ -
3.19	138kV, A Frame 50'	0	EA	33,000.00	19,800.00	13,200.00	\$ -	\$ -	\$ -	\$ -
3.20	AL. Bus Tubing, 5" SCH 80	0	LF	25.00	184.94	123.29	\$ -	\$ -	\$ -	\$ -
3.21	AL. Bus fittings	0	LS	-	-	-	\$ -	\$ -	\$ -	\$ -
3.22	Steel grating and support beams-transformer moat	43,280	LB	2.73	1.17	0.50	\$ 118,233	\$ 50,594	\$ 21,683	\$ 190,511
TOTAL - SUBSTATION STRUCTURES & GAS-INSULATED CONDUCTOR							\$ 118,233	\$ 50,594	\$ 21,683	\$ 190,511

Item	Item Description	Estimated Quantity	Unit of Measure	Material Supply Rate	Labor Supply Rate	Const. Equipment Rate	Material Supply Cost	Labor Supply Cost	Const. Equipment Cost	TOTAL COST
4. MAJOR EQUIPMENT										
4.1	345kV, GIS air terminal	0	EA				\$ -	\$ -	\$ -	\$ -
4.2	345kV, GIS Cable sealing end	0	EA				\$ -	\$ -	\$ -	\$ -
4.3	345kV, Cable sealing end	0	EA	17,400.00	5,460.00	2,340.00	\$ -	\$ -	\$ -	\$ -
4.4	345kV, CCVT	0	EA		15,941.99	6,832.28	\$ -	\$ -	\$ -	\$ -
4.5	345kV, Disconnect Switch	0	EA	57,720.00	34,632.00	23,088.00	\$ -	\$ -	\$ -	\$ -
4.6	345/138KV, Power Transformer with oil containment	0	EA		3,520.00	880.00	\$ -	\$ -	\$ -	\$ -
4.7	Transport & Testing- Transformer	0	EA		15,400.00	6,600.00	\$ -	\$ -	\$ -	\$ -
4.8	345kV, Shunt Reactor with oil containment-225MVAR	1	EA	3,026,425.00	3,520.00	880.00	\$ 3,026,425	\$ 3,520	\$ 880	\$ 3,030,825
4.9	345kV, Shunt Reactor with oil containment-100MVAR	0	EA		3,520.00	880.00	\$ -	\$ -	\$ -	\$ -
4.10	Transport & Testing- Shunt Reactor	1	EA		337,900.00	221,600.00	\$ -	\$ 337,900	\$ 221,600	\$ 559,500
4.11	345kV, Phase Angle Regulator with oil containment	0	EA		3,520.00	880.00	\$ -	\$ -	\$ -	\$ -
4.12	345kV, Gas Insulated Switchgear, BAAH Arrangement	12	BKR	847,083.33	508,250.00	338,833.33	\$ 10,165,000	\$ 6,099,000	\$ 4,066,000	\$ 20,330,000
4.13	345kV, Circuit Breaker (PASS)	0	EA		57,239.00	24,531.00	\$ -	\$ -	\$ -	\$ -
4.14	345kV, Circuit Breaker (GIS), outdoor rated	0	EA				\$ -	\$ -	\$ -	\$ -
4.15	345kV, Circuit Breaker (GIS), outdoor rated-Line surge Arrester ( 3phase)	0	EA				\$ -	\$ -	\$ -	\$ -
4.16	345kV, surge Arrester	0	EA	6,669.00	5,460.00	2,340.00	\$ -	\$ -	\$ -	\$ -
4.17	138kV, Phase Angle Regulator with oil containment	0	EA		3,520.00	880.00	\$ -	\$ -	\$ -	\$ -
4.18	Transport & Testing- Phase Angle Regulating Transformer, 138kV	0	EA		15,400.00	6,600.00	\$ -	\$ -	\$ -	\$ -
4.19	138kV, Gas Insulated Switchgear, BAAH Arrangement	0	BKR		205,800.00	4,200.00	\$ -	\$ -	\$ -	\$ -
4.20	138kV, Circuit Breaker, Hybrid circuit breaker	0	EA		13,559.00	5,811.00	\$ -	\$ -	\$ -	\$ -
4.21	138kV, Disconnect Switch	0	EA	37,700.00	11,875.50	5,089.50	\$ -	\$ -	\$ -	\$ -
4.22	138kV, Cable sealing end	0	EA	11,600.00	5,460.00	2,340.00	\$ -	\$ -	\$ -	\$ -
4.23	138kV, CCVT	0	EA		7,970.08	3,415.75	\$ -	\$ -	\$ -	\$ -
4.24	138kV, Surge arrester	0	EA		4,200.00	1,800.00	\$ -	\$ -	\$ -	\$ -
4.25	Station service transformers- 120/208v-250VA	2	EA	260,000.00	45,500.00	19,500.00	\$ 520,000	\$ 91,000	\$ 39,000	\$ 650,000
4.26	345kV Gas-Insulated Bus Conductor	0	LF	550.00	275.00	82.50				\$ -
4.27	345kV Gas-Insulated Bus Conductor-elbow	0	EA	2,500.00	1,250.00	375.00				\$ -
4.28	Transport & Testing- GIL	0	LS		-	-				\$ -
TOTAL - MAJOR EQUIPMENT							\$ 13,711,425	\$ 6,531,420	\$ 4,327,480	\$ 24,570,325
5. LOW VOLTAGE & CONTROL CABLE										
5.1	Control Cables	1,500	LF	5.30	1.43	0.29	\$ 7,946	\$ 2,149	\$ 430	\$ 10,525
5.2			LF		-	-	\$ -	\$ -	\$ -	\$ -
TOTAL - LOW VOLTAGE & CONTROL CABLE							\$ 7,946	\$ 2,149	\$ 430	\$ 10,525
6. CONDUIT & CABLE TRENCH										
6.1	Conduit, PVC, 6", SCH 40		LF	20.70	13.28	6.64	\$ -	\$ -	\$ -	\$ -
6.2	Conduit, PVC, 4", SCH 40	300	LF	11.15	10.80	5.40	\$ 3,345	\$ 3,240	\$ 1,620	\$ 8,205
6.3	Conduit, PVC, 3", SCH 40		LF	8.10	10.80	5.40	\$ -	\$ -	\$ -	\$ -
6.4	Conduit, PVC, 2", SCH 40		LF	3.95	10.80	5.40	\$ -	\$ -	\$ -	\$ -
6.5	Conduit, PVC, 1", SCH 40		LF	1.90	10.80	5.40	\$ -	\$ -	\$ -	\$ -
6.6	Cable Trench	715	LF	266.50	53.04	13.26	\$ 190,548	\$ 37,924	\$ 9,481	\$ 237,952
6.7										
6.8	138kV UG- Conduit		LF	266.73	202.15	100.00	\$ -	\$ -	\$ -	\$ -
6.9	138kV UG- Cable		LF	145.00	87.00	58.00	\$ -	\$ -	\$ -	\$ -
6.10	138kV UG- Termination		EA	27,805.00	9,846.48	2,813.28	\$ -	\$ -	\$ -	\$ -
6.11	345kV UG- Conduit		LF	266.73	202.15	100.00	\$ -	\$ -	\$ -	\$ -
6.12	345kV UG- Cable		LF	167.00	100.20	66.80	\$ -	\$ -	\$ -	\$ -
6.13	345kV UG- Termination		EA	27,805.00	9,846.48	2,813.28	\$ -	\$ -	\$ -	\$ -
6.14	Fiber Optic Cable			7.40	3.33	2.22				
6.15	Ground Continuity Conductor			13.04	7.53	5.02	\$ -	\$ -	\$ -	\$ -
TOTAL - CONDUIT & CABLE TRENCH							\$ 193,893	\$ 41,164	\$ 11,101	\$ 246,157
7. GROUND GRID										
7.1	Cable, 4/0 AWG Bare Copper, 7 Strand Ground Conductor	3,762	LF	2.09	3.42	1.46	\$ 7,866	\$ 12,848	\$ 5,506	\$ 26,221
7.2	Caweld, DSA, 4/0 , T, CROSS	112	EA	165.00	75.00		\$ 18,480	\$ 8,400	\$ -	\$ 26,880
7.3	Ground Rod, 3/4" x 15'	90	EA	135.00	67.50	7.50	\$ 12,150	\$ 6,075	\$ 675	\$ 18,900
TOTAL - GROUND GRID							\$ 38,496	\$ 27,323	\$ 6,181	\$ 72,001
8. CONTROL ENCLOSURE										
8.1	345kv GIS Bldg	1	EA	2,481,442.00	1,737,009.40	744,432.60	\$ 2,481,442	\$ 1,737,009	\$ 744,433	\$ 4,962,884
8.2	138kv GIS/Control Bldg	0	EA	1,145,280.92	801,696.65	343,584.28	\$ -	\$ -	\$ -	\$ -
8.3	Primary Line Relays (87L): SEL-411L	7	EA	21,328.12	17,062.49	4,265.62	\$ 149,297	\$ 119,437	\$ 29,859	\$ 298,594
8.4	Backup Line Relays (87L): GE L90	7	EA	21,328.12	17,062.49	4,265.62	\$ 149,297	\$ 119,437	\$ 29,859	\$ 298,594
8.5	Primary Bay Control: SEL-451	4	EA	21,328.12	17,062.49	4,265.62	\$ 85,312	\$ 68,250	\$ 17,062	\$ 170,625
8.6	Backup Bay Control: SEL-451	4	EA	21,328.12	17,062.49	4,265.62	\$ 85,312	\$ 68,250	\$ 17,062	\$ 170,625
8.7	Primary Transformer/Reactor/PAR Differential Relays: SEL-487E	1	EA	21,328.12	17,062.49	4,265.62	\$ 21,328	\$ 17,062	\$ 4,266	\$ 42,656
8.8	Backup Transformer/Reactor/PAR Differential Relays: GE T60	1	EA	21,328.12	17,062.49	4,265.62	\$ 21,328	\$ 17,062	\$ 4,266	\$ 42,656

Item	Item Description	Estimated Quantity	Unit of Measure	Material Supply Rate	Labor Supply Rate	Const. Equipment Rate	Material Supply Cost	Labor Supply Cost	Const. Equipment Cost	TOTAL COST
8.9	Primary Bus Differential Relays: SEL-487B	3	EA	21,328.12	17,062.49	4,265.62	\$ 63,984	\$ 51,187	\$ 12,797	\$ 127,969
8.10	Backup Bus Differential Relays: GE B90	3	EA	21,328.12	17,062.49	4,265.62	\$ 63,984	\$ 51,187	\$ 12,797	\$ 127,969
8.11	RTU Panel A: SEL-2240 Axion, SEL-2730M ENET SW., SEL-2407 GPS, Modem, SEL-2523 Ann	1	EA	12,500.00	10,000.00	2,500.00	\$ 12,500	\$ 10,000	\$ 2,500	\$ 25,000
8.12	RTU Panel B: SEL-2730M Ethernet Switch, SEL-2407 GPS Clock, SEL-2523 Annunciator	1	EA	12,500.00	10,000.00	2,500.00	\$ 12,500	\$ 10,000	\$ 2,500	\$ 25,000
8.13	HMI Panel	1	EA	12,500.00	10,000.00	2,500.00	\$ 12,500	\$ 10,000	\$ 2,500	\$ 25,000
8.14	Primary Line Relays (87L): SEL-411L	2	EA	21,328.12	17,062.49	4,265.62	\$ 42,656	\$ 34,125	\$ 8,531	\$ 85,312
8.15	Backup Line Relays (87L): GE L90	2	EA	21,328.12	17,062.49	4,265.62	\$ 42,656	\$ 34,125	\$ 8,531	\$ 85,312
8.14	125VDC Battery System	2	LS	25,000.00	22,750.00	9,750.00	\$ 50,000	\$ 45,500	\$ 19,500	\$ 115,000
8.15	Control house AC Panel	1	EA	65,000.00	91,000.00	39,000.00	\$ 65,000	\$ 91,000	\$ 39,000	\$ 195,000
8.16	Control House DC Panel	1	EA	65,000.00	91,000.00	39,000.00	\$ 65,000	\$ 91,000	\$ 39,000	\$ 195,000
8.17	Generator	1	EA	130,000.00	72,800.00	31,200.00	\$ 130,000	\$ 72,800	\$ 31,200	\$ 234,000
TOTAL - CONTROL ENCLOSURE							\$ 3,554,098	\$ 2,647,434	\$ 1,025,664	\$ 7,227,196
5.Dunwoodie 345 kV GIS Substation							\$ 19,842,091	\$ 11,447,328	\$ 6,713,846	\$ 38,003,264
9. MOB/DEMOB, ENGINEERING, PERMITTING, T&C, PM & INDIRECTS										
	Contractor Mobilization / Demobilization									
9.1	Mob / Demob	1.0	LS		279,866.08	119,942.61	\$ -	\$ 279,866	\$ 119,943	\$ 399,809
	Project Management, Material Handling & Amenities									
9.2	Preconstruction Supervision (Engineering, Permitting, Procurement)	1	LS		176,732.64		\$ -	\$ 176,733	\$ -	\$ 176,733
9.3	Project Management & Staffing (includes PM, Field Engineers / Supervision, Scheduler and Cost Manager, SHEQ Staff, and Admin Staff)	1	LS		706,930.58		\$ -	\$ 706,931	\$ -	\$ 706,931
9.4	Utility PM and Project Oversight	1	LS		176,732.64		\$ -	\$ 176,733	\$ -	\$ 176,733
9.5	Site Accommodation, Facilities, Storage	1	LS	176,732.64			\$ 176,733	\$ -	\$ -	\$ 176,733
	Engineering									
9.6	Design Engineering	1.00	LS		1,413,861.16		\$ -	\$ 1,413,861	\$ -	\$ 1,413,861
9.7	LiDAR /GPR	-	LS		-		\$ -	\$ -	\$ -	\$ -
9.8	Geotech	5.00	EA		2,730.00	1,820.00	\$ -	\$ 13,650	\$ 9,100	\$ 22,750
9.9	Surveying/Staking	1.00	Site		123,712.85		\$ -	\$ 123,713	\$ -	\$ 123,713
	Testing & Commissioning									
9.10	Testing & Commissioning of SS and Equipment	1.00	LS		662,747.42		\$ -	\$ 662,747	\$ -	\$ 662,747
	Permitting and Additional Costs									
9.11	Physical Security	1.00	LS		6,546.96		\$ -	\$ 6,547	\$ -	\$ 6,547
9.12	Environmental Licensing & Permitting Costs & related legal cost	1.00	LS		176,732.64		\$ -	\$ 176,733	\$ -	\$ 176,733
9.13	Environmental-special studies/investigation	-	LS		-		\$ -	\$ -	\$ -	\$ -
9.14	Warranties / LOC's	1.00	LS		53,019.79		\$ -	\$ 53,020	\$ -	\$ 53,020
9.15	Laydown Lease	-	LS				\$ -	\$ -	\$ -	\$ -
9.16	Real Estate ( Acquisition)	1.00	LS			2,505,000.00	\$ -	\$ -	\$ 2,505,000	\$ 2,505,000
9.17	Legal Fees (Real estate)	1.00	LS		-	75,150.00	\$ -	\$ -	\$ 75,150	\$ 75,150
9.18	Insurance	-	LS		-	-	\$ -	\$ -	\$ -	\$ -
9.19	Bonds	1	LS		-	\$ 1,280,000	\$ -	\$ -	\$ 1,280,000	\$ 1,280,000
9.20	Sales Tax on Materials	8.80%	LS	19,842,090.70			\$ 1,746,104	\$ -	\$ -	\$ 1,746,104
9.21	Fees for permits, including roadway, railroad, building or other local permits	1.00	LS		38,003.26		\$ -	\$ 38,003	\$ -	\$ 38,003
TOTAL - MOB/DEMOB, ENGINEERING, PERMITTING, T&C, PM & INDIRECTS:							\$ 1,922,837	\$ 3,828,536	\$ 3,989,193	\$ 9,740,565

<u>NEXTera Energy- TO36 Core 1</u>		
<u>6.Elwood 138 kV Substation Upgrades</u>		
Total:	\$	7,946,839

<u>NEXTera Energy- TO36 Core 1</u>		
<u>6.Elwood 138 kV Substation Upgrades</u>		
Total:	\$	7,946,839

NEXtera Energy- TO36 Core 1				
	Material Supply	Labor Supply	Equip Supply	Total
6.Elwood 138 kV Substation Upgrades				
1. SITE PREP/ GRADING/ FENCING / CIVIL	\$ -	\$ 60,000	\$ 40,000	\$ 100,000
2. SUBSTATION FOUNDATIONS	\$ 88,690	\$ 101,359	\$ 63,350	\$ 253,399
3. SUBSTATION STRUCTURES	\$ 118,233	\$ 50,594	\$ 21,683	\$ 190,511
4. MAJOR EQUIPMENT	\$ 3,226,531	\$ 201,920	\$ 129,480	\$ 3,557,931
5. LOW VOLTAGE & CONTROL CABLE	\$ 15,893	\$ 4,298	\$ 860	\$ 21,050
6. CONDUIT & CABLE TRENCH	\$ 6,690	\$ 6,480	\$ 3,240	\$ 16,410
7. GROUND GRID	\$ -	\$ -	\$ -	\$ -
8. CONTROL ENCLOSURE	\$ 42,656	\$ 34,125	\$ 8,531	\$ 85,312
9. MOB/DEMOB, ENGINEERING, PERMITTING, T&C, PM & INDIRECTS	\$ 350,131	\$ 866,723	\$ 170,709	\$ 1,387,563
SUBTOTAL (Costs):	\$ 3,848,823	\$ 1,325,499	\$ 437,852	\$ 5,612,175
CONTRACTOR MARK-UP (OH&P)	\$ 692,788	\$ 238,590	\$ 78,813	\$ 1,010,191
SUBTOTAL:	\$ 4,541,612	\$ 1,564,089	\$ 516,666	\$ 6,622,366
CONTINGENCY ON ENTIRE PROJECT	\$ 908,322	\$ 312,818	\$ 103,333	\$ 1,324,473
TOTAL:	\$ 5,449,934	\$ 1,876,907	\$ 619,999	\$ 7,946,839

Description of Work: Replace the existing 80MVAr reactor (1 block) at the exisitng elwood 138kv station with an 80 MVAR reactor (2 blocks of 40 MVAr)										
Item	Item Description	Estimated Quantity	Unit of Measure	Material Supply Rate	Labor Supply Rate	Const. Equipment Rate	Material Supply Cost	Labor Supply Cost	Const. Equipment Cost	TOTAL COST
6.Elwood 138 kV Substation Upgrades										
1. SITE PREP/ GRADING/ FENCING / CIVIL										
1.1	Site Clearing		ACRE	-	10,800.00	7,200.00	\$ -	\$ -	\$ -	\$ -
1.2	Demolition	1	LS	-	60,000.00	40,000.00	\$ -	\$ 60,000	\$ 40,000	\$ 100,000
1.3	New Access Road - 20'		SY	4.85	7.20	4.80	\$ -	\$ -	\$ -	\$ -
1.4	Strip and Dispose Top Soil	0	CY		24.50	10.50	\$ -	\$ -	\$ -	\$ -
1.5	Site Grading- Excavation for Substation Pad	0	CY		9.00	6.00	\$ -	\$ -	\$ -	\$ -
1.6	Site Grading- Excavation for Substation Pad-Rock excavation-Hauling and disposal	0	CY		21.00	9.00	\$ -	\$ -	\$ -	\$ -
1.7	Site Grading- Fill for Substation Pad (site borrow, compacted in place)	0	CY		2.40	1.60	\$ -	\$ -	\$ -	\$ -
1.8	Site Grading -Fill for Substation Pad (import, compacted in place)	0	CY	25.00	2.40	1.60	\$ -	\$ -	\$ -	\$ -
1.9	Blasting		EA				\$ -	\$ -	\$ -	\$ -
1.10	Install substation 8" pad base	0	SY	11.00	6.00	4.00	\$ -	\$ -	\$ -	\$ -
1.11	Site Surfacing - Aggregate 6" Thick	0	SY	16.50	4.50	3.00	\$ -	\$ -	\$ -	\$ -
1.12	7' Station Fence w/ Barbed Wire & Grounding		LF	13.85	13.85	6.92	\$ -	\$ -	\$ -	\$ -
1.13	20' Slide Gate & Grounding		EA	8,100.00	3,245.00	1,305.00	\$ -	\$ -	\$ -	\$ -
1.14	4' Pedestrian gate		EA	2,500.00	1,000.00	350.00	\$ -	\$ -	\$ -	\$ -
1.15	Storm drain-15" HDPE, INFILTRATION TRENCH, INLET and Hydrodynamic Separator		LS	446,976.00	-	-	\$ -	\$ -	\$ -	\$ -
1.16	Seeding		SF	1.50	1.50	1.00	\$ -	\$ -	\$ -	\$ -
1.17	Erosion Control-Silt fence install & remove		LF	2.41	3.16	0.72	\$ -	\$ -	\$ -	\$ -
1.18	Temporary fencing		LF	7.50	5.25	2.25	\$ -	\$ -	\$ -	\$ -
1.19	Substation entrance with asphalt		SY	19.50	26.00	19.50	\$ -	\$ -	\$ -	\$ -
1.20	Concrete curb	0	LF	26.00	27.30	11.70	\$ -	\$ -	\$ -	\$ -
1.21	Retaining Wall	0	LF	156.00	117.00	117.00	\$ -	\$ -	\$ -	\$ -



Item	Item Description	Estimated Quantity	Unit of Measure	Material Supply Rate	Labor Supply Rate	Const. Equipment Rate	Material Supply Cost	Labor Supply Cost	Const. Equipment Cost	TOTAL COST
TOTAL - SITE PREP/ GRADING/ FENCING / CIVIL							\$ -	\$ 60,000	\$ 40,000	\$ 100,000
2. SUBSTATION FOUNDATIONS										
2.1	345kV, Lightning mast	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.2	345kV, A Frame 70'	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.3	345kV, Bus support-3 Ph	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.4	345kV, Bus support-3 Ph, low	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.5	345kV, Bus support-1 Ph	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.6	345kV, GIS air terminal	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.7	345kV, GIS support-1 Ph	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.8	345kV, GIS support-3 Ph	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.9	345kV, GIS Cable sealing end	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.10	345kV, Cable sealing end	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.11	345kV, CCVT	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.12	345kV, Disconnect Switch	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.13	345/138KV, Power Transformer with oil containment	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.14	345kV, Shunt Reactor with oil containment-150MVAR	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.15	345kV, Shunt Reactor with oil containment-100MVAR	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.16	345kV, Phase Angle Regulator with oil containment	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.17	345kV, Circuit Breaker (PASS)	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.18	345kV, Circuit Breaker (GIS), outdoor rated	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.19	345Kv, GIS Enclosure-BLDG with generator pad	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.20	345kV, Surge arrester	-	CY	-	-	-	\$ -	\$ -	\$ -	\$ -
2.21	138kV, Phase Angle Regulator with oil containment	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.22	138kV, Shunt Reactor with oil containment-80MVAR	126	CY	703.89	804.44	502.78	\$ 88,690	\$ 101,359	\$ 63,350	\$ 253,399
2.23	138kV, Circuit Breaker, Hybrid circuit breaker	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.24	138kV, Bus support-3 Ph, low	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.25	138kV, Bus support-1 Ph, low	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.26	138kV, Disconnect Switch	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.27	138kV, Cable sealing end	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.28	138kV, Surge arrester	-	CY	-	-	-	\$ -	\$ -	\$ -	\$ -
2.29	138kV, CCVT	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.30	138kV, A Frame 50'	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.31	Firewall Foundation	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.32	Precast Firewall for transformer, PARs, reactors		SF	25.00	15.00	10.00	\$ -	\$ -	\$ -	\$ -
2.33	Precast Concrete Piles-12"X80'	-	EA	18,000.00	3,200.00	2,800.00	\$ -	\$ -	\$ -	\$ -
2.34	Local Control Cabinet foundation	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.35	138kV, GIS Enclosure-BLDG & control room	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
TOTAL - 345KV FOUNDATION							\$ 88,690	\$ 101,359	\$ 63,350	\$ 253,399
3. SUBSTATION STRUCTURES										
3.1	345kV, Lightning mast	0	EA				\$ -	\$ -	\$ -	\$ -
3.2	345kV, A Frame 70'	0	EA	48,100.00	28,860.00	19,240.00	\$ -	\$ -	\$ -	\$ -
3.3	345kV, Bus support-3 Ph	0	EA	8,346.00	5,758.74	3,839.16	\$ -	\$ -	\$ -	\$ -
3.4	345kV, Bus support-3 Ph, low	0	EA	8,346.00	5,758.74	3,839.16	\$ -	\$ -	\$ -	\$ -
3.5	345kV, Bus support-1 Ph	0	EA	4,810.00	2,886.00	1,924.00	\$ -	\$ -	\$ -	\$ -
3.6	345kV, GIS air terminal	0	EA	8,346.00	5,758.74	3,839.16	\$ -	\$ -	\$ -	\$ -
3.7	345kV, GIS support-1 Ph	0	EA	8,346.00	5,758.74	3,839.16	\$ -	\$ -	\$ -	\$ -
3.8	345kV, GIS support-3 Ph	0	EA	4,810.00	2,886.00	1,924.00	\$ -	\$ -	\$ -	\$ -
3.9	345kV, GIS Cable sealing end	0	EA	8,346.00	5,758.74	3,839.16	\$ -	\$ -	\$ -	\$ -
3.10	345kV, Cable sealing end	0	EA	8,346.00	5,758.74	3,839.16	\$ -	\$ -	\$ -	\$ -
3.11	345kV, CCVT	0	EA	4,810.00	2,886.00	1,924.00	\$ -	\$ -	\$ -	\$ -
3.12	345kV, Disconnect Switch	0	EA	19,240.00	11,544.00	7,696.00	\$ -	\$ -	\$ -	\$ -
3.13	138kV, Bus support-3 Ph, low	0	EA	4,173.00	2,879.76	1,919.84	\$ -	\$ -	\$ -	\$ -
3.14	138kV, Bus support-1 Ph, low	0	EA	2,782.00	1,919.84	1,279.89	\$ -	\$ -	\$ -	\$ -
3.15	138kV, Disconnect Switch	0	EA				\$ -	\$ -	\$ -	\$ -
3.16	138kV, Cable sealing end	0	EA	4,810.00	2,886.00	1,924.00	\$ -	\$ -	\$ -	\$ -
3.17	138kV, Surge arrester	0	EA	4,810.00	2,886.00	1,924.00	\$ -	\$ -	\$ -	\$ -
3.18	138kV, CCVT	0	EA	3,206.67	1,924.00	1,282.67	\$ -	\$ -	\$ -	\$ -
3.19	138kV, A Frame 50'	0	EA	33,000.00	19,800.00	13,200.00	\$ -	\$ -	\$ -	\$ -
3.20	AL. Bus Tubing, 5" SCH 80	0	LF	25.00	184.94	123.29	\$ -	\$ -	\$ -	\$ -
3.21	AL. Bus fittings	0	LS	-	-	-	\$ -	\$ -	\$ -	\$ -
3.22	Steel grating and support beams-transformer moat	43,280	LB	2.73	1.17	0.50	\$ 118,233	\$ 50,594	\$ 21,683	\$ 190,511
TOTAL - SUBSTATION STRUCTURES & GAS-INSULATED CONDUCTOR							\$ 118,233	\$ 50,594	\$ 21,683	\$ 190,511
4. MAJOR EQUIPMENT										

Item	Item Description	Estimated Quantity	Unit of Measure	Material Supply Rate	Labor Supply Rate	Const. Equipment Rate	Material Supply Cost	Labor Supply Cost	Const. Equipment Cost	TOTAL COST
4.1	345kV, GIS air terminal	0	EA				\$ -	\$ -	\$ -	\$ -
4.2	345kV, GIS Cable sealing end	0	EA				\$ -	\$ -	\$ -	\$ -
4.3	345kV, Cable sealing end	0	EA		5,460.00	2,340.00	\$ -	\$ -	\$ -	\$ -
4.4	345kV, CCVT	0	EA		15,941.99	6,832.28	\$ -	\$ -	\$ -	\$ -
4.5	345kV, Disconnect Switch	0	EA		7,234.50	3,100.50	\$ -	\$ -	\$ -	\$ -
4.6	345/138KV, Power Transformer with oil containment	0	EA		3,520.00	880.00	\$ -	\$ -	\$ -	\$ -
4.7	Transport & Testing- Transformer	0	EA		15,400.00	6,600.00	\$ -	\$ -	\$ -	\$ -
4.8	345kV, Shunt Reactor with oil containment-150MVAR	0	EA		3,520.00	880.00	\$ -	\$ -	\$ -	\$ -
4.9	345kV, Shunt Reactor with oil containment-100MVAR	0	EA		3,520.00	880.00	\$ -	\$ -	\$ -	\$ -
4.10	Transport & Testing- Shunt Reactor	0	EA		15,400.00	6,600.00	\$ -	\$ -	\$ -	\$ -
4.11	345kV, Phase Angle Regulator with oil containment	0	EA		3,520.00	880.00	\$ -	\$ -	\$ -	\$ -
4.12	345kV, Gas Insulated Switchgear, BAAH Arrangement	0	BKR		205,800.00	4,200.00	\$ -	\$ -	\$ -	\$ -
4.13	345kV, Circuit Breaker (PASS)	0	EA		57,239.00	24,531.00	\$ -	\$ -	\$ -	\$ -
4.14	345kV, Circuit Breaker (GIS), outdoor rated	0	EA				\$ -	\$ -	\$ -	\$ -
4.15	345kV, Circuit Breaker (GIS), outdoor rated-Line surge Arrester ( 3phase)	0	EA				\$ -	\$ -	\$ -	\$ -
4.16	345kV, surge Arrester	0	EA		5,460.00	2,340.00	\$ -	\$ -	\$ -	\$ -
4.17	138kV, Phase Angle Regulator with oil containment	0	EA		3,520.00	880.00	\$ -	\$ -	\$ -	\$ -
4.18	Transport & Testing- Phase Angle Regulating Transformer, 138kV	0	EA		15,400.00	6,600.00	\$ -	\$ -	\$ -	\$ -
4.19	Transport & Testing- Transformer	0	EA		15,400.00	6,600.00	\$ -	\$ -	\$ -	\$ -
4.20	138kV, Shunt Reactor with oil containment-80MVAR	1	EA	3,226,531.00	3,520.00	880.00	\$ 3,226,531	\$ 3,520	\$ 880	\$ 3,230,931
4.21	Transport & Testing- Shunt Reactor	1	EA		198,400.00	128,600.00	\$ -	\$ 198,400	\$ 128,600	\$ 327,000
4.22	138kV, Gas Insulated Switchgear, BAAH Arrangement	0	BKR		205,800.00	4,200.00	\$ -	\$ -	\$ -	\$ -
4.23	138kV, Circuit Breaker, Hybrid circuit breaker	0	EA		13,559.00	5,811.00	\$ -	\$ -	\$ -	\$ -
4.24	138kV, Disconnect Switch	0	EA	37,700.00	11,875.50	5,089.50	\$ -	\$ -	\$ -	\$ -
4.25	138kV, Cable sealing end	0	EA	11,600.00	5,460.00	2,340.00	\$ -	\$ -	\$ -	\$ -
4.26	138kV, CCVT	0	EA		7,970.08	3,415.75	\$ -	\$ -	\$ -	\$ -
4.27	138kV, Surge arrester	0	EA		4,200.00	1,800.00	\$ -	\$ -	\$ -	\$ -
4.28	Station service transformers- 120/208v-250VA	0	EA		45,500.00	19,500.00	\$ -	\$ -	\$ -	\$ -
4.29	345kV Gas-Insulated Bus Conductor	0	LF	550.00	275.00	82.50	\$ -	\$ -	\$ -	\$ -
4.30	345kV Gas-Insulated Bus Conductor-elbow	0	EA	2,500.00	1,250.00	375.00	\$ -	\$ -	\$ -	\$ -
TOTAL - MAJOR EQUIPMENT							\$ 3,226,531	\$ 201,920	\$ 129,480	\$ 3,557,931
5. LOW VOLTAGE & CONTROL CABLE										
5.1	Control Cables	3,000	LF	5.30	1.43	0.29	\$ 15,893	\$ 4,298	\$ 860	\$ 21,050
5.2			LF		-	-	\$ -	\$ -	\$ -	\$ -
TOTAL - LOW VOLTAGE & CONTROL CABLE							\$ 15,893	\$ 4,298	\$ 860	\$ 21,050
6. CONDUIT & CABLE TRENCH										
6.1	Conduit, PVC, 6", SCH 40		LF	20.70	13.28	6.64	\$ -	\$ -	\$ -	\$ -
6.2	Conduit, PVC, 4", SCH 40	600	LF	11.15	10.80	5.40	\$ 6,690	\$ 6,480	\$ 3,240	\$ 16,410
6.3	Conduit, PVC, 3", SCH 40		LF	8.10	10.80	5.40	\$ -	\$ -	\$ -	\$ -
6.4	Conduit, PVC, 2", SCH 40		LF	3.95	10.80	5.40	\$ -	\$ -	\$ -	\$ -
6.5	Conduit, PVC, 1", SCH 40		LF	1.90	10.80	5.40	\$ -	\$ -	\$ -	\$ -
6.6	Cable Trench		LF	266.50	53.04	13.26	\$ -	\$ -	\$ -	\$ -
6.7										
6.8	138kV UG- Conduit		LF	266.73	202.15	100.00	\$ -	\$ -	\$ -	\$ -
6.9	138kV UG- Cable		LF	145.00	87.00	58.00	\$ -	\$ -	\$ -	\$ -
6.10	138kV UG- Termination		EA	27,805.00	9,846.48	2,813.28	\$ -	\$ -	\$ -	\$ -
6.11	345kV UG- Conduit		LF	266.73	202.15	100.00	\$ -	\$ -	\$ -	\$ -
6.12	345kV UG- Cable		LF	167.00	100.20	66.80	\$ -	\$ -	\$ -	\$ -
6.13	345kV UG- Termination		EA	27,805.00	9,846.48	2,813.28	\$ -	\$ -	\$ -	\$ -
6.14	Fiber Optic Cable			7.40	3.33	2.22				
6.15	Ground Continuity Conductor			13.04	7.53	5.02	\$ -	\$ -	\$ -	\$ -
TOTAL - CONDUIT & CABLE TRENCH							\$ 6,690	\$ 6,480	\$ 3,240	\$ 16,410
7. GROUND GRID										
7.1	Cable, 4/0 AWG Bare Copper, 7 Strand Ground Conductor	0	LF	2.09	3.42	1.46	\$ -	\$ -	\$ -	\$ -
7.2	Caweld, DSA, 4/0 , T, CROSS	0	EA	165.00	75.00		\$ -	\$ -	\$ -	\$ -
7.3	Ground Rod, 3/4" x 15'	0	EA	135.00	67.50	7.50	\$ -	\$ -	\$ -	\$ -
TOTAL - GROUND GRID							\$ -	\$ -	\$ -	\$ -
8. CONTROL ENCLOSURE										
8.1	345kv GIS Bldg	0	EA	2,481,442.00	1,737,009.40	744,432.60	\$ -	\$ -	\$ -	\$ -
8.2	138kv GIS/Control Bldg	0	EA	1,145,280.92	801,696.65	343,584.28	\$ -	\$ -	\$ -	\$ -
8.3	Primary Transformer/Reactor/PAR Differential Relays: SEL-487E	1	EA	21,328.12	17,062.49	4,265.62	\$ 21,328	\$ 17,062	\$ 4,266	\$ 42,656
8.4	Backup Transformer/Reactor/PAR Differential Relays: GE T60	1	EA	21,328.12	17,062.49	4,265.62	\$ 21,328	\$ 17,062	\$ 4,266	\$ 42,656
8.5	125VDC Battery System		LS	25,000.00	22,750.00		\$ -	\$ -	\$ -	\$ -
8.6	Control house AC Panel		EA	65,000.00	91,000.00	39,000.00	\$ -	\$ -	\$ -	\$ -

Item	Item Description	Estimated Quantity	Unit of Measure	Material Supply Rate	Labor Supply Rate	Const. Equipment Rate	Material Supply Cost	Labor Supply Cost	Const. Equipment Cost	TOTAL COST
8.7	Control House DC Panel		EA	65,000.00	91,000.00	39,000.00	\$ -	\$ -	\$ -	\$ -
8.8	Generator		EA	130,000.00	72,800.00	31,200.00	\$ -	\$ -	\$ -	\$ -
TOTAL - CONTROL ENCLOSURE							\$ 42,656	\$ 34,125	\$ 8,531	\$ 85,312
6.Elwood 138 kV Substation Upgrades							\$ 3,498,692	\$ 458,776	\$ 267,144	\$ 4,224,612
9. MOB/DEMOB, ENGINEERING, PERMITTING, T&C, PM & INDIRECTS										
	Contractor Mobilization / Demobilization									
9.1	Mob / Demob	1.0	LS		25,407.20	10,888.80	\$ -	\$ 25,407	\$ 10,889	\$ 36,296
	Project Management, Material Handling & Amenities									
9.2	Preconstruction Supervision (Engineering, Permitting, Procurement)	1	LS		42,246.12		\$ -	\$ 42,246	\$ -	\$ 42,246
9.3	Project Management & Staffing (includes PM, Field Engineers / Supervision, Scheduler and Cost Manager, SHEQ Staff, and Admin Staff)	1	LS		168,984.49		\$ -	\$ 168,984	\$ -	\$ 168,984
9.4	Utility PM and Project Oversight	1	LS		42,246.12		\$ -	\$ 42,246	\$ -	\$ 42,246
9.5	Site Accommodation, Facilities, Storage	1	LS	42,246.12			\$ 42,246	\$ -	\$ -	\$ 42,246
	Engineering									
9.6	Design Engineering	1.00	LS		337,968.98		\$ -	\$ 337,969	\$ -	\$ 337,969
9.7	LiDAR /GPR	1.00	LS		-		\$ -	\$ -	\$ -	\$ -
9.8	Geotech	1.00	EA		2,730.00	1,820.00	\$ -	\$ 2,730	\$ 1,820	\$ 4,550
9.9	Surveying/Staking	1.00	Site		29,572.29		\$ -	\$ 29,572	\$ -	\$ 29,572
	Testing & Commissioning									
9.10	Testing & Commissioning of SS and Equipment	1.00	LS		158,422.96		\$ -	\$ 158,423	\$ -	\$ 158,423
	Permitting and Additional Costs									
9.11	Physical Security	1.00	LS		-		\$ -	\$ -	\$ -	\$ -
9.12	Environmental Licensing & Permitting Costs & related legal cost	1.00	LS		42,246.12		\$ -	\$ 42,246	\$ -	\$ 42,246
9.13	Environmental-special studies/investigation	-	LS		-		\$ -	\$ -	\$ -	\$ -
9.14	Warranties / LOC's	1.00	LS		12,673.84		\$ -	\$ 12,674	\$ -	\$ 12,674
9.15	Laydown Lease	-	LS				\$ -	\$ -	\$ -	\$ -
9.16	Real Estate ( Acquisition)	-	LS				\$ -	\$ -	\$ -	\$ -
9.17	Legal Fees (Real estate)	-	LS		-	-	\$ -	\$ -	\$ -	\$ -
9.18	Insurance	-	LS		-	-	\$ -	\$ -	\$ -	\$ -
9.19	Bonds	1	LS		-	\$ 158,000	\$ -	\$ -	\$ 158,000	\$ 158,000
9.20	Sales Tax on Materials	8.80%	LS	3,498,692.30			\$ 307,885	\$ -	\$ -	\$ 307,885
9.21	Fees for permits, including roadway, railroad, building or other local permits	1.00	LS		4,224.61		\$ -	\$ 4,225	\$ -	\$ 4,225
TOTAL - MOB/DEMOB, ENGINEERING, PERMITTING, T&C, PM & INDIRECTS:							\$ 350,131	\$ 866,723	\$ 170,709	\$ 1,387,563

<b><u>NEXTera Energy- TO36 Core 1</u></b>		
<b><u>7.Jamaica 138 kV Substation Upgrades</u></b>		
Total:	\$	2,024,724

<b>NEXtera Energy- TO36 Core 1</b>									
------------------------------------	--	--	--	--	--	--	--	--	--

	Material Supply	Labor Supply	Equip Supply	Total
<b>7.Jamaica 138 kV Substation Upgrades</b>				
1. SITE PREP/ GRADING/ FENCING / CIVIL	\$ -	\$ 30,000	\$ 20,000	\$ 50,000
2. SUBSTATION FOUNDATIONS	\$ 8,137	\$ 9,299	\$ 5,812	\$ 23,248
3. SUBSTATION STRUCTURES	\$ 45,726	\$ 32,857	\$ 20,272	\$ 98,855
4. MAJOR EQUIPMENT	\$ 385,838	\$ 168,494	\$ 68,991	\$ 623,323
5. LOW VOLTAGE & CONTROL CABLE	\$ 20,660	\$ 5,587	\$ 1,117	\$ 27,364
6. CONDUIT & CABLE TRENCH	\$ 6,690	\$ 6,480	\$ 3,240	\$ 16,410
7. GROUND GRID	\$ -	\$ -	\$ -	\$ -
8. CONTROL ENCLOSURE	\$ 127,969	\$ 102,375	\$ 25,594	\$ 255,937
9. MOB/DEMOB, ENGINEERING, PERMITTING, T&C, PM & INDIRECTS	\$ 63,313	\$ 223,938	\$ 47,502	\$ 334,752
<b>SUBTOTAL (Costs):</b>	<b>\$ 658,333</b>	<b>\$ 579,029</b>	<b>\$ 192,528</b>	<b>\$ 1,429,890</b>
<b>CONTRACTOR MARK-UP (OH&amp;P)</b>	<b>\$ 118,500</b>	<b>\$ 104,225</b>	<b>\$ 34,655</b>	<b>\$ 257,380</b>
<b>SUBTOTAL:</b>	<b>\$ 776,832</b>	<b>\$ 683,255</b>	<b>\$ 227,183</b>	<b>\$ 1,687,270</b>
<b>CONTINGENCY ON ENTIRE PROJECT</b>	<b>\$ 155,366</b>	<b>\$ 136,651</b>	<b>\$ 45,437</b>	<b>\$ 337,454.06</b>
<b>TOTAL:</b>	<b>\$ 932,199</b>	<b>\$ 819,906</b>	<b>\$ 272,620</b>	<b>\$ 2,024,724</b>

Description of Work: Add an additional terminal at the existing Jamaica 138kV substation										
Item	Item Description	Estimated Quantity	Unit of Measure	Material Supply Rate	Labor Supply Rate	Const. Equipment Rate	Material Supply Cost	Labor Supply Cost	Const. Equipment Cost	TOTAL COST
7.Jamaica 138 kV Substation Upgrades										
1. SITE PREP/ GRADING/ FENCING / CIVIL										
1.1	Site Clearing		ACRE	-	10,800.00	7,200.00	\$ -	\$ -	\$ -	\$ -
1.2	Demolition	1	LS	-	30,000.00	20,000.00	\$ -	\$ 30,000	\$ 20,000	\$ 50,000
1.3	New Access Road - 20'		SY	4.85	7.20	4.80	\$ -	\$ -	\$ -	\$ -
1.4	Strip and Dispose Top Soil	0	CY		24.50	10.50	\$ -	\$ -	\$ -	\$ -
1.5	Site Grading- Excavation for Substation Pad	0	CY		9.00	6.00	\$ -	\$ -	\$ -	\$ -
1.6	Site Grading- Excavation for Substation Pad-Rock excavation-Hauling and disposal	0	CY		21.00	9.00	\$ -	\$ -	\$ -	\$ -
1.7	Site Grading- Fill for Substation Pad (site borrow, compacted in place)	0	CY		2.40	1.60	\$ -	\$ -	\$ -	\$ -
1.8	Site Grading -Fill for Substation Pad (import, compacted in place)	0	CY	25.00	2.40	1.60	\$ -	\$ -	\$ -	\$ -
1.9	Blasting		EA				\$ -	\$ -	\$ -	\$ -
1.10	Install substation 8" pad base	0	SY	11.00	6.00	4.00	\$ -	\$ -	\$ -	\$ -
1.11	Site Surfacing - Aggregate 6" Thick	0	SY	16.50	4.50	3.00	\$ -	\$ -	\$ -	\$ -
1.12	7' Station Fence w/ Barbed Wire & Grounding		LF	13.85	13.85	6.92	\$ -	\$ -	\$ -	\$ -
1.13	20' Slide Gate & Grounding		EA	8,100.00	3,245.00	1,305.00	\$ -	\$ -	\$ -	\$ -
1.14	4' Pedestrian gate		EA	2,500.00	1,000.00	350.00	\$ -	\$ -	\$ -	\$ -
1.15	Storm drain-15" HDPE, INFILTRATION TRENCH, INLET and Hydrodynamic Separator		LS	446,976.00	-	-	\$ -	\$ -	\$ -	\$ -
1.16	Seeding		SF	1.50	1.50	1.00	\$ -	\$ -	\$ -	\$ -
1.17	Erosion Control-Silt fence install & remove		LF	2.41	3.16	0.72	\$ -	\$ -	\$ -	\$ -
1.18	Temporary fencing		LF	7.50	5.25	2.25	\$ -	\$ -	\$ -	\$ -
1.19	Substation entrance with asphalt		SY	19.50	26.00	19.50	\$ -	\$ -	\$ -	\$ -
1.20	Concrete curb	0	LF	26.00	27.30	11.70	\$ -	\$ -	\$ -	\$ -
1.21	Retaining Wall	0	LF	156.00	117.00	117.00	\$ -	\$ -	\$ -	\$ -

Item	Item Description	Estimated Quantity	Unit of Measure	Material Supply Rate	Labor Supply Rate	Const. Equipment Rate	Material Supply Cost	Labor Supply Cost	Const. Equipment Cost	TOTAL COST
TOTAL - SITE PREP/ GRADING/ FENCING / CIVIL							\$ -	\$ 30,000	\$ 20,000	\$ 50,000
2. SUBSTATION FOUNDATIONS										
2.1	345kV, Lightning mast	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.2	345kV, A Frame 70'	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.3	345kV, Bus support-3 Ph	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.4	345kV, Bus support-3 Ph, low	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.5	345kV, Bus support-1 Ph	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.6	345kV, GIS air terminal	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.7	345kV, GIS support-1 Ph	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.8	345kV, GIS support-3 Ph	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.9	345kV, GIS Cable sealing end	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.10	345kV, Cable sealing end	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.11	345kV, CCVT	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.12	345kV, Disconnect Switch	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.13	345/138KV, Power Transformer with oil containment	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.14	345kV, Shunt Reactor with oil containment-150MVAR	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.15	345kV, Shunt Reactor with oil containment-100MVAR	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.16	345kV, Phase Angle Regulator with oil containment	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.17	345kV, Circuit Breaker (PASS)	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.18	345kV, Circuit Breaker (GIS), outdoor rated	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.19	345Kv, GIS Enclosure-BLDG with generator pad	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.20	345kV, Surge arrester	-	CY	-	-	-	\$ -	\$ -	\$ -	\$ -
2.21	138kV, Phase Angle Regulator with oil containment	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.22	138kV, Shunt Reactor with oil containment-80MVAR	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.23	138kV, Circuit Breaker, AIS breaker	4	CY	703.89	804.44	502.78	\$ 3,132	\$ 3,580	\$ 2,237	\$ 8,949
2.24	138kV, Bus support-3 Ph, low	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.25	138kV, GIS Bus support-1 Ph, low	2	CY	703.89	804.44	502.78	\$ 1,647	\$ 1,882	\$ 1,176	\$ 4,706
2.26	138kV, Disconnect Switch	2	CY	703.89	804.44	502.78	\$ 1,492	\$ 1,705	\$ 1,066	\$ 4,264
2.27	138kV, Cable sealing end	1	CY	703.89	804.44	502.78	\$ 746	\$ 853	\$ 533	\$ 2,132
2.28	138kV, Surge arrester	2	CY	703.89	804.44	502.78	\$ 1,119	\$ 1,279	\$ 799	\$ 3,198
2.29	138kV, CCVT	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.30	138kV, A Frame 50'	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.31	Firewall Foundation	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.32	Precast Firewall for transformer, PARs, reactors	-	SF	25.00	15.00	10.00	\$ -	\$ -	\$ -	\$ -
2.33	Precast Concrete Piles-12"X80'	-	EA	18,000.00	3,200.00	2,800.00	\$ -	\$ -	\$ -	\$ -
2.34	Local Control Cabinet foundation	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.35	138kV, GIS Enclosure-BLDG & control room	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
TOTAL - 345KV FOUNDATION							\$ 8,137	\$ 9,299	\$ 5,812	\$ 23,248
3. SUBSTATION STRUCTURES										
3.1	345kV, Lightning mast	0	EA				\$ -	\$ -	\$ -	\$ -
3.2	345kV, A Frame 70'	0	EA	48,100.00	28,860.00	19,240.00	\$ -	\$ -	\$ -	\$ -
3.3	345kV, Bus support-3 Ph	0	EA	8,346.00	5,758.74	3,839.16	\$ -	\$ -	\$ -	\$ -
3.4	345kV, Bus support-3 Ph, low	0	EA	8,346.00	5,758.74	3,839.16	\$ -	\$ -	\$ -	\$ -
3.5	345kV, Bus support-1 Ph	0	EA	4,810.00	2,886.00	1,924.00	\$ -	\$ -	\$ -	\$ -
3.6	345kV, GIS air terminal	0	EA	8,346.00	5,758.74	3,839.16	\$ -	\$ -	\$ -	\$ -
3.7	345kV, GIS support-1 Ph	0	EA	8,346.00	5,758.74	3,839.16	\$ -	\$ -	\$ -	\$ -
3.8	345kV, GIS support-3 Ph	0	EA	4,810.00	2,886.00	1,924.00	\$ -	\$ -	\$ -	\$ -
3.9	345kV, GIS Cable sealing end	0	EA	8,346.00	5,758.74	3,839.16	\$ -	\$ -	\$ -	\$ -
3.10	345kV, Cable sealing end	0	EA	8,346.00	5,758.74	3,839.16	\$ -	\$ -	\$ -	\$ -
3.11	345kV, CCVT	0	EA	4,810.00	2,886.00	1,924.00	\$ -	\$ -	\$ -	\$ -
3.12	345kV, Disconnect Switch	0	EA	19,240.00	11,544.00	7,696.00	\$ -	\$ -	\$ -	\$ -
3.13	138kV, Bus support-3 Ph, low	0	EA	4,173.00	2,879.76	1,919.84	\$ -	\$ -	\$ -	\$ -
3.14	138kV, GIL Bus support-1 Ph, low	6	EA	2,782.00	1,919.84	1,279.89	\$ 16,692	\$ 11,519	\$ 7,679	\$ 35,890
3.15	138kV, Disconnect Switch	2	EA	4,896.84	4,896.84	2,448.42	\$ 9,794	\$ 9,794	\$ 4,897	\$ 24,484
3.16	138kV, Cable sealing end	1	EA	4,810.00	2,886.00	1,924.00	\$ 4,810	\$ 2,886	\$ 1,924	\$ 9,620
3.17	138kV, Surge arrester	3	EA	4,810.00	2,886.00	1,924.00	\$ 14,430	\$ 8,658	\$ 5,772	\$ 28,860
3.18	138kV, CCVT	0	EA	3,206.67	1,924.00	1,282.67	\$ -	\$ -	\$ -	\$ -
3.19	138kV, A Frame 50'	0	EA	33,000.00	19,800.00	13,200.00	\$ -	\$ -	\$ -	\$ -
3.20	AL. Bus Tubing, 5" SCH 80		LF	25.00	184.94	123.29	\$ -	\$ -	\$ -	\$ -
3.21	AL. Bus fittings	0	LS	-	-	-	\$ -	\$ -	\$ -	\$ -
3.22	Steel grating and support beams-transformer moat	0	LB	2.73	1.17	0.50	\$ -	\$ -	\$ -	\$ -
TOTAL - SUBSTATION STRUCTURES & GAS-INSULATED CONDUCTOR							\$ 45,726	\$ 32,857	\$ 20,272	\$ 98,855
4. MAJOR EQUIPMENT										



Item	Item Description	Estimated Quantity	Unit of Measure	Material Supply Rate	Labor Supply Rate	Const. Equipment Rate	Material Supply Cost	Labor Supply Cost	Const. Equipment Cost	TOTAL COST
4.1	345kV, GIS air terminal	0	EA							
4.2	345kV, GIS Cable sealing end	0	EA				\$ -	\$ -	\$ -	\$ -
4.3	345kV, Cable sealing end	0	EA		5,460.00	2,340.00	\$ -	\$ -	\$ -	\$ -
4.4	345kV, CCVT	0	EA		15,941.99	6,832.28	\$ -	\$ -	\$ -	\$ -
4.5	345kV, Disconnect Switch	0	EA		7,234.50	3,100.50	\$ -	\$ -	\$ -	\$ -
4.6	345/138KV, Power Transformer with oil containment	0	EA		3,520.00	880.00	\$ -	\$ -	\$ -	\$ -
4.7	Transport & Testing- Transformer	0	EA		15,400.00	6,600.00	\$ -	\$ -	\$ -	\$ -
4.8	345kV, Shunt Reactor with oil containment-150MVAR	0	EA		3,520.00	880.00	\$ -	\$ -	\$ -	\$ -
4.9	345kV, Shunt Reactor with oil containment-100MVAR	0	EA		3,520.00	880.00	\$ -	\$ -	\$ -	\$ -
4.10	Transport & Testing- Shunt Reactor	0	EA		15,400.00	6,600.00	\$ -	\$ -	\$ -	\$ -
4.11	345kV, Phase Angle Regulator with oil containment	0	EA		3,520.00	880.00	\$ -	\$ -	\$ -	\$ -
4.12	345kV, Gas Insulated Switchgear, BAAH Arrangement	0	BKR		205,800.00	4,200.00	\$ -	\$ -	\$ -	\$ -
4.13	345kV, Circuit Breaker (PASS)	0	EA		57,239.00	24,531.00	\$ -	\$ -	\$ -	\$ -
4.14	345kV, Circuit Breaker (GIS), outdoor rated	0	EA				\$ -	\$ -	\$ -	\$ -
4.15	345kV, Circuit Breaker (GIS), outdoor rated-Line surge Arrester ( 3phase)	0	EA				\$ -	\$ -	\$ -	\$ -
4.16	345kV, surge Arrester	0	EA		5,460.00	2,340.00	\$ -	\$ -	\$ -	\$ -
4.17	138kV, Phase Angle Regulator with oil containment	0	EA		3,520.00	880.00	\$ -	\$ -	\$ -	\$ -
4.18	Transport & Testing- Phase Angle Regulating Transformer, 138kV	0	EA		15,400.00	6,600.00	\$ -	\$ -	\$ -	\$ -
4.19	Transport & Testing- Transformer	0	EA		15,400.00	6,600.00	\$ -	\$ -	\$ -	\$ -
4.20	138kV, Shunt Reactor with oil containment-80MVAR	0	EA		3,520.00	880.00	\$ -	\$ -	\$ -	\$ -
4.21	Transport & Testing- Shunt Reactor	0	EA		15,400.00	6,600.00	\$ -	\$ -	\$ -	\$ -
4.22	138kV, Gas Insulated Switchgear, BAAH Arrangement	0	BKR		205,800.00	4,200.00	\$ -	\$ -	\$ -	\$ -
4.23	138kV, Circuit Breaker, AIS breaker	1	EA	112,000.00	13,559.00	5,811.00	\$ 112,000	\$ 13,559	\$ 5,811	\$ 131,370
4.24	138kV, Disconnect Switch	2	EA	37,700.00	11,875.50	5,089.50	\$ 75,400	\$ 23,751	\$ 10,179	\$ 109,330
4.25	138kV, Cable sealing end	3	EA	11,600.00	5,460.00	2,340.00	\$ 34,800	\$ 16,380	\$ 7,020	\$ 58,200
4.26	138kV, CCVT	0	EA	3,206.67	1,924.00	1,282.67	\$ -	\$ -	\$ -	\$ -
4.27	138kV, Surge arrester	3	EA	4,446.00	4,200.00	1,800.00	\$ 13,338	\$ 12,600	\$ 5,400	\$ 31,338
4.28	Station service transformers- 120/208v-250VA	0	EA		45,500.00	19,500.00	\$ -	\$ -	\$ -	\$ -
4.29	345/138kV Gas-Insulated Bus Conductor	246	LF	550.00	275.00	82.50	\$ 135,300	\$ 67,650	\$ 20,295	\$ 223,245
4.30	345/138kV Gas-Insulated Bus Conductor-elbow	6	EA	2,500.00	1,250.00	375.00	\$ 15,000	\$ 7,500	\$ 2,250	\$ 24,750
4.31	Transport & Testing- GIL	1	LS		27,054.00	18,036.00	\$ -	\$ 27,054	\$ 18,036	\$ 45,090
TOTAL - MAJOR EQUIPMENT							\$ 385,838	\$ 168,494	\$ 68,991	\$ 623,323
5. LOW VOLTAGE & CONTROL CABLE										
5.1	Control Cables	3,900	LF	5.30	1.43	0.29	\$ 20,660	\$ 5,587	\$ 1,117	\$ 27,364
5.2			LF		-	-	\$ -	\$ -	\$ -	\$ -
TOTAL - LOW VOLTAGE & CONTROL CABLE							\$ 20,660	\$ 5,587	\$ 1,117	\$ 27,364
6. CONDUIT & CABLE TRENCH										
6.1	Conduit, PVC, 6", SCH 40		LF	20.70	13.28	6.64	\$ -	\$ -	\$ -	\$ -
6.2	Conduit, PVC, 4", SCH 40	600	LF	11.15	10.80	5.40	\$ 6,690	\$ 6,480	\$ 3,240	\$ 16,410
6.3	Conduit, PVC, 3", SCH 40		LF	8.10	10.80	5.40	\$ -	\$ -	\$ -	\$ -
6.4	Conduit, PVC, 2", SCH 40		LF	3.95	10.80	5.40	\$ -	\$ -	\$ -	\$ -
6.5	Conduit, PVC, 1", SCH 40		LF	1.90	10.80	5.40	\$ -	\$ -	\$ -	\$ -
6.6	Cable Trench		LF	266.50	53.04	13.26	\$ -	\$ -	\$ -	\$ -
6.7										
6.8	138kV UG- Conduit		LF	266.73	202.15	100.00	\$ -	\$ -	\$ -	\$ -
6.9	138kV UG- Cable		LF	145.00	87.00	58.00	\$ -	\$ -	\$ -	\$ -
6.10	138kV UG- Termination		EA	27,805.00	9,846.48	2,813.28	\$ -	\$ -	\$ -	\$ -
6.11	345kV UG- Conduit		LF	266.73	202.15	100.00	\$ -	\$ -	\$ -	\$ -
6.12	345kV UG- Cable		LF	167.00	100.20	66.80	\$ -	\$ -	\$ -	\$ -
6.13	345kV UG- Termination		EA	27,805.00	9,846.48	2,813.28	\$ -	\$ -	\$ -	\$ -
6.14										
6.15							\$ -	\$ -	\$ -	\$ -
TOTAL - CONDUIT & CABLE TRENCH							\$ 6,690	\$ 6,480	\$ 3,240	\$ 16,410
7. GROUND GRID										
7.1	Cable, 4/0 AWG Bare Copper, 7 Strand Ground Conductor	0	LF	2.09	3.42	1.46	\$ -	\$ -	\$ -	\$ -
7.2	Caweld, DSA, 4/0 , T, CROSS	0	EA	165.00	75.00		\$ -	\$ -	\$ -	\$ -
7.3	Ground Rod, 3/4" x 15'	0	EA	135.00	67.50	7.50	\$ -	\$ -	\$ -	\$ -
TOTAL - GROUND GRID							\$ -	\$ -	\$ -	\$ -
8. CONTROL ENCLOSURE										
8.1	345kv GIS Bldg	0	EA	2,481,442.00	1,737,009.40	744,432.60	\$ -	\$ -	\$ -	\$ -
8.2	138kv GIS/Control Bldg	0	EA	1,145,280.92	801,696.65	343,584.28	\$ -	\$ -	\$ -	\$ -
8.3	Primary Line Relays (87L): SEL-411L	1	EA	21,328.12	17,062.49	4,265.62	\$ 21,328	\$ 17,062	\$ 4,266	\$ 42,656
8.4	Backup Line Relays (87L): GE L90	1	EA	21,328.12	17,062.49	4,265.62	\$ 21,328	\$ 17,062	\$ 4,266	\$ 42,656
8.5	Primary Bay Control: SEL-451	1	EA	21,328.12	17,062.49	4,265.62	\$ 21,328	\$ 17,062	\$ 4,266	\$ 42,656
8.6	Backup Bay Control: SEL-451	1	EA	21,328.12	17,062.49	4,265.62	\$ 21,328	\$ 17,062	\$ 4,266	\$ 42,656

Item	Item Description	Estimated Quantity	Unit of Measure	Material Supply Rate	Labor Supply Rate	Const. Equipment Rate	Material Supply Cost	Labor Supply Cost	Const. Equipment Cost	TOTAL COST
8.7	Primary Bus Differential Relays: SEL-487B	1	EA	21,328.12	17,062.49	4,265.62	\$ 21,328	\$ 17,062	\$ 4,266	\$ 42,656
8.8	Backup Bus Differential Relays: GE B90	1	EA	21,328.12	17,062.49	4,265.62	\$ 21,328	\$ 17,062	\$ 4,266	\$ 42,656
8.14	125VDC Battery System		LS	25,000.00	22,750.00	9,750.00	\$ -	\$ -	\$ -	\$ -
8.15	Control house AC Panel		EA	65,000.00	91,000.00	39,000.00	\$ -	\$ -	\$ -	\$ -
8.16	Control House DC Panel		EA	65,000.00	91,000.00	39,000.00	\$ -	\$ -	\$ -	\$ -
8.17	Generator		EA	130,000.00	72,800.00	31,200.00	\$ -	\$ -	\$ -	\$ -
TOTAL - CONTROL ENCLOSURE							\$ 127,969	\$ 102,375	\$ 25,594	\$ 255,937
7.Jamaica 138 kV Substation Upgrades							\$ 595,020	\$ 355,092	\$ 145,026	\$ 1,095,138
9. MOB/DEMOB, ENGINEERING, PERMITTING, T&C, PM & INDIRECTS										
	Contractor Mobilization / Demobilization									
9.1	Mob / Demob	1.0	LS		17,504.13	7,501.77	\$ -	\$ 17,504	\$ 7,502	\$ 25,006
	Project Management, Material Handling & Amenities									
9.2	Preconstruction Supervision (Engineering, Permitting, Procurement)	1	LS		10,951.38		\$ -	\$ 10,951	\$ -	\$ 10,951
9.3	Project Management & Staffing (includes PM, Field Engineers / Supervision, Scheduler and Cost Manager, SHEQ Staff, and Admin Staff)	1	LS		43,805.51		\$ -	\$ 43,806	\$ -	\$ 43,806
9.4	Utility PM and Project Oversight	1	LS		10,951.38		\$ -	\$ 10,951	\$ -	\$ 10,951
9.5	Site Accommodation, Facilities, Storage	1	LS	10,951.38			\$ 10,951	\$ -	\$ -	\$ 10,951
	Engineering									
9.6	Design Engineering	1.00	LS		87,611.01		\$ -	\$ 87,611	\$ -	\$ 87,611
9.7	LiDAR /GPR	1.00	LS				\$ -	\$ -	\$ -	\$ -
9.8	Geotech	-	EA		2,730.00	1,820.00	\$ -	\$ -	\$ -	\$ -
9.9	Surveying/Staking	1.00	Site		7,665.96		\$ -	\$ 7,666	\$ -	\$ 7,666
	Testing & Commissioning									
9.10	Testing & Commissioning of SS and Equipment	1.00	LS		41,067.66		\$ -	\$ 41,068	\$ -	\$ 41,068
	Permitting and Additional Costs									
9.11	Physical Security	1.00	LS		-		\$ -	\$ -	\$ -	\$ -
9.12	Environmental Licensing & Permitting Costs & related legal cost	-	LS		10,951.38		\$ -	\$ -	\$ -	\$ -
9.13	Environmental-special studies/investigation	-	LS		-		\$ -	\$ -	\$ -	\$ -
9.14	Warranties / LOC's	1.00	LS		3,285.41		\$ -	\$ 3,285	\$ -	\$ 3,285
9.15	Laydown Lease	-	LS		-		\$ -	\$ -	\$ -	\$ -
9.16	Real Estate ( Acquisition)	-	LS		-		\$ -	\$ -	\$ -	\$ -
9.17	Legal Fees (Real estate)	-	LS		-	-	\$ -	\$ -	\$ -	\$ -
9.18	Insurance	-	LS		-	-	\$ -	\$ -	\$ -	\$ -
9.19	Bonds	1	LS		-	\$ 40,000	\$ -	\$ -	\$ 40,000	\$ 40,000
9.20	Sales Tax on Materials	8.80%	LS	595,019.53			\$ 52,362	\$ -	\$ -	\$ 52,362
9.21	Fees for permits, including roadway, railroad, building or other local permits	1.00	LS		1,095.14		\$ -	\$ 1,095	\$ -	\$ 1,095
TOTAL - MOB/DEMOB, ENGINEERING, PERMITTING, T&C, PM & INDIRECTS:							\$ 63,313	\$ 223,938	\$ 47,502	\$ 334,752

NEXTera Energy- TO36 Core 1

8.Newbridge 345/138 kV GIS Substation Upgrades

Total:   \$           89,858,233

NEXTera Energy- TO36 Core 1				
	Material Supply	Labor Supply	Equip Supply	Total
8.Newbridge 345/138 kV GIS Substation Upgrades				
1. SITE PREP/ GRADING/ FENCING / CIVIL	\$ -	\$ 180,000	\$ 120,000	\$ 300,000
2. SUBSTATION FOUNDATIONS	\$ 2,041,415	\$ 2,221,489	\$ 1,393,568	\$ 5,656,472
3. SUBSTATION STRUCTURES	\$ 429,813	\$ 203,612	\$ 99,602	\$ 733,027
4. MAJOR EQUIPTMENT	\$ 18,401,761	\$ 7,318,980	\$ 4,860,895	\$ 30,581,636
5. LOW VOLTAGE & CONTROL CABLE	\$ 31,785	\$ 8,595	\$ 1,719	\$ 42,099
6. CONDUIT & CABLE TRENCH	\$ 4,064,400	\$ 2,260,091	\$ 1,200,974	\$ 7,525,466
7. GROUND GRID	\$ 50,624	\$ 36,318	\$ 8,365	\$ 95,307
8. CONTROL ENCLOSURE	\$ 4,172,141	\$ 3,175,330	\$ 1,245,811	\$ 8,593,282
9. MOB/DEMOB, ENGINEERING, PERMITTING, T&C, PM & INDIRECTS	\$ 2,900,864	\$ 7,105,954	\$ 1,992,555	\$ 11,999,373
Turnkey cost (HVDC, GIS)	\$ 10,165,000	\$ 6,099,000	\$ 4,066,000	\$ 20,330,000
Non-Turnkey cost	\$ 21,927,804	\$ 16,411,369	\$ 6,857,489	\$ 45,196,662
SUBTOTAL (Costs):	\$ 32,092,804	\$ 22,510,369	\$ 10,923,489	\$ 65,526,662
CONTRACTOR MARK-UP (OH&P)	\$ 4,556,905	\$ 3,319,986	\$ 1,478,308	\$ 9,355,199
SUBTOTAL:	\$ 36,649,708	\$ 25,830,355	\$ 12,401,797	\$ 74,881,861
CONTINGENCY ON ENTIRE PROJECT	\$ 7,329,942	\$ 5,166,071	\$ 2,480,359	\$ 14,976,372
TOTAL:	\$ 43,979,650	\$ 30,996,426	\$ 14,882,157	\$ 89,858,233

Description of Work: Remove the northern bay at the existing Newbridge Road 138kV station for the construction of the new 345/138kV GIS.										
Item	Item Description	Estimated Quantity	Unit of Measure	Material Supply Rate	Labor Supply Rate	Const. Equipment Rate	Material Supply Cost	Labor Supply Cost	Const. Equipment Cost	TOTAL COST
8.Newbridge 345/138 kV GIS Substation Upgrades										
1. SITE PREP/ GRADING/ FENCING / CIVIL										
1.1	Site Clearing		ACRE	-	10,800.00	7,200.00	\$ -	\$ -	\$ -	\$ -
1.2	Demolition	1	LS	-	180,000.00	120,000.00	\$ -	\$ 180,000	\$ 120,000	\$ 300,000
1.3	New Access Road - 20'		SY	4.85	7.20	4.80	\$ -	\$ -	\$ -	\$ -
1.4	Strip and Dispose Top Soil	0	CY		24.50	10.50	\$ -	\$ -	\$ -	\$ -
1.5	Site Grading- Excavation for Substation Pad	0	CY		9.00	6.00	\$ -	\$ -	\$ -	\$ -
1.6	Site Grading- Excavation for Substation Pad-Rock excavation-Hauling and disposal	0	CY		21.00	9.00	\$ -	\$ -	\$ -	\$ -
1.7	Site Grading- Fill for Substation Pad (site borrow, compacted in place)	0	CY		2.40	1.60	\$ -	\$ -	\$ -	\$ -
1.8	Site Grading -Fill for Substation Pad (import, compacted in place)	0	CY	25.00	2.40	1.60	\$ -	\$ -	\$ -	\$ -
1.9	Blasting		EA				\$ -	\$ -	\$ -	\$ -
1.10	Install substation 8" pad base	0	SY	11.00	6.00	4.00	\$ -	\$ -	\$ -	\$ -
1.11	Site Surfacing - Aggregate 6" Thick	0	SY	16.50	4.50	3.00	\$ -	\$ -	\$ -	\$ -
1.12	7' Station Fence w/ Barbed Wire & Grounding		LF	13.85	13.85	6.92	\$ -	\$ -	\$ -	\$ -
1.13	20' Slide Gate & Grounding		EA	8,100.00	3,245.00	1,305.00	\$ -	\$ -	\$ -	\$ -
1.14	4' Pedestrian gate		EA	2,500.00	1,000.00	350.00	\$ -	\$ -	\$ -	\$ -
1.15	Storm drain-15" HDPE, INFILTRATION TRENCH, INLET and Hydrodynamic Separator		LS	446,976.00	-	-	\$ -	\$ -	\$ -	\$ -
1.16	Seeding		SF	1.50	1.50	1.00	\$ -	\$ -	\$ -	\$ -
1.17	Erosion Control-Silt fence install & remove		LF	2.41	3.16	0.72	\$ -	\$ -	\$ -	\$ -
1.18	Temporary fencing		LF	7.50	5.25	2.25	\$ -	\$ -	\$ -	\$ -

Item	Item Description	Estimated Quantity	Unit of Measure	Material Supply Rate	Labor Supply Rate	Const. Equipment Rate	Material Supply Cost	Labor Supply Cost	Const. Equipment Cost	TOTAL COST
1.19	Substation entrance with asphalt		SY	19.50	26.00	19.50	\$ -	\$ -	\$ -	\$ -
1.20	Concrete curb	0	LF	26.00	27.30	11.70	\$ -	\$ -	\$ -	\$ -
1.21	Retaining Wall	0	LF	156.00	117.00	117.00	\$ -	\$ -	\$ -	\$ -
TOTAL - SITE PREP/ GRADING/ FENCING / CIVIL							\$ -	\$ 180,000	\$ 120,000	\$ 300,000
2. SUBSTATION FOUNDATIONS										
2.1	345kV, Lightning mast	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.2	345kV, A Frame 70'	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.3	345kV, Bus support-3 Ph	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.4	345kV, Bus support-3 Ph, low	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.5	345kV, Bus support-1 Ph	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.6	345kV, GIS air terminal	40	CY	703.89	804.44	502.78	\$ 27,874	\$ 31,856	\$ 19,910	\$ 79,640
2.7	345kV, GIS support-1 Ph	12	CY	703.89	804.44	502.78	\$ 8,573	\$ 9,798	\$ 6,124	\$ 24,495
2.8	345kV, GIS support-3 Ph	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.9	345kV, GIS Cable sealing end	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.10	345kV, Cable sealing end	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.11	345kV, CCVT	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.12	345kV, Disconnect Switch	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.13	345/138KV, Power Transformer with oil containment	328	CY	703.89	804.44	502.78	\$ 230,874	\$ 263,856	\$ 164,910	\$ 659,641
2.14	345kV, Shunt Reactor with oil containment-25MVAR	200	CY	703.89	804.44	502.78	\$ 140,777	\$ 160,888	\$ 100,555	\$ 402,220
2.15	345kV, Shunt Reactor with oil containment-100MVAR	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.16	345kV, Phase Angle Regulator with oil containment	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.17	345kV, Circuit Breaker (PASS)	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.18	345kV, Circuit Breaker (GIS), outdoor rated	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.19	345Kv, GIS Enclosure-BLDG with generator pad	1,482	CY	703.89	804.44	502.78	\$ 1,043,158	\$ 1,192,180	\$ 745,113	\$ 2,980,450
2.20	345kV, Surge arrester	16	CY	-	-	-	\$ -	\$ -	\$ -	\$ -
2.21	138kV, Phase Angle Regulator with oil containment	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.22	138kV, Shunt Reactor with oil containment-80MVAR	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.23	138kV, Circuit Breaker, AIS breaker	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.24	138kV, Bus support-3 Ph, low	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.25	138kV, Bus support-1 Ph, low	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.26	138kV, Disconnect Switch	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.27	138kV, Cable sealing end	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.28	138kV, Surge arrester	-	CY	-	-	-	\$ -	\$ -	\$ -	\$ -
2.29	138kV, CCVT	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.30	138kV, A Frame 50'	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.31	Firewall Foundation	546	CY	703.89	804.44	502.78	\$ 384,659	\$ 439,610	\$ 274,756	\$ 1,099,026
2.32	Precast Firewall for transformer, PARs, reactors	8,220	SF	25.00	15.00	10.00	\$ 205,500	\$ 123,300	\$ 82,200	\$ 411,000
2.33	Precast Concrete Piles-12"X80'	-	EA	18,000.00	3,200.00	2,800.00	\$ -	\$ -	\$ -	\$ -
2.34	Local Control Cabinet foundation	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.35	138kV, GIS Enclosure-BLDG & control room	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
TOTAL - 345KV FOUNDATION							\$ 2,041,415	\$ 2,221,489	\$ 1,393,568	\$ 5,656,472
3. SUBSTATION #REF!										
3.1	345kV, Lightning mast	0	EA				\$ -	\$ -	\$ -	\$ -
3.2	345kV, A Frame 70'	0	EA	48,100.00	28,860.00	19,240.00	\$ -	\$ -	\$ -	\$ -
3.3	345kV, Bus support-3 Ph	0	EA	8,346.00	5,758.74	3,839.16	\$ -	\$ -	\$ -	\$ -
3.4	345kV, Bus support-3 Ph, low	0	EA	8,346.00	5,758.74	3,839.16	\$ -	\$ -	\$ -	\$ -
3.5	345kV, Bus support-1 Ph	0	EA	4,810.00	2,886.00	1,924.00	\$ -	\$ -	\$ -	\$ -
3.6	345kV, GIS air terminal	6	EA	8,346.00	5,758.74	3,839.16	\$ 50,076	\$ 34,552	\$ 23,035	\$ 107,663
3.7	345kV, GIS support-1 Ph	3	EA	8,346.00	5,758.74	3,839.16	\$ 25,038	\$ 17,276	\$ 11,517	\$ 53,832
3.8	345kV, GIS support-3 Ph	0	EA	4,810.00	2,886.00	1,924.00	\$ -	\$ -	\$ -	\$ -
3.9	345kV, GIS Cable sealing end	0	EA	8,346.00	5,758.74	3,839.16	\$ -	\$ -	\$ -	\$ -
3.10	345kV, Cable sealing end	0	EA	8,346.00	5,758.74	3,839.16	\$ -	\$ -	\$ -	\$ -
3.11	345kV, CCVT	0	EA	4,810.00	2,886.00	1,924.00	\$ -	\$ -	\$ -	\$ -
3.12	345kV, Disconnect Switch	0	EA	19,240.00	11,544.00	7,696.00	\$ -	\$ -	\$ -	\$ -
3.13	138kV, Bus support-3 Ph, low	0	EA	4,173.00	2,879.76	1,919.84	\$ -	\$ -	\$ -	\$ -
3.14	138kV, Bus support-1 Ph, low	0	EA	2,782.00	1,919.84	1,279.89	\$ -	\$ -	\$ -	\$ -
3.15	138kV, Disconnect Switch	0	EA				\$ -	\$ -	\$ -	\$ -
3.16	138kV, Cable sealing end	0	EA	4,810.00	2,886.00	1,924.00	\$ -	\$ -	\$ -	\$ -
3.18	138kV, Surge arrester	0	EA	4,810.00	2,886.00	1,924.00	\$ -	\$ -	\$ -	\$ -
3.17	138kV, CCVT	0	EA	3,206.67	1,924.00	1,282.67	\$ -	\$ -	\$ -	\$ -
3.18	138kV, A Frame 50'	0	EA	33,000.00	19,800.00	13,200.00	\$ -	\$ -	\$ -	\$ -
3.21	AL. Bus Tubing, 5" SCH 80	0	LF	25.00	184.94	123.29	\$ -	\$ -	\$ -	\$ -
3.22	AL. Bus fittings	0	LS	-	-	-	\$ -	\$ -	\$ -	\$ -
3.23	Steel grating and support beams-transformer moat	129,840	LB	2.73	1.17	0.50	\$ 354,699	\$ 151,783	\$ 65,050	\$ 571,532

Item	Item Description	Estimated Quantity	Unit of Measure	Material Supply Rate	Labor Supply Rate	Const. Equipment Rate	Material Supply Cost	Labor Supply Cost	Const. Equipment Cost	TOTAL COST
<b>TOTAL - SUBSTATION STRUCTURES &amp; GAS-INSULATED CONDUCTOR</b>							\$ 429,813	\$ 203,612	\$ 99,602	\$ 733,027
<b>4. MAJOR EQUIPMENT</b>										
4.1	345kV, GIS air terminal	6	EA							
4.2	345kV, GIS Cable sealing end	0	EA				\$ -	\$ -	\$ -	\$ -
4.3	345kV, Cable sealing end	0	EA		5,460.00	2,340.00	\$ -	\$ -	\$ -	\$ -
4.4	345kV, CCVT	0	EA		15,941.99	6,832.28	\$ -	\$ -	\$ -	\$ -
4.5	345kV, Disconnect Switch	0	EA	57,720.00	34,632.00	23,088.00	\$ -	\$ -	\$ -	\$ -
4.6	345/138KV, Power Transformer with oil containment	1	EA	4,420,000.00	3,520.00	880.00	\$ 4,420,000	\$ 3,520	\$ 880	\$ 4,424,400
4.7	Transport & Testing- Transformer	1	EA		717,400.00	474,600.00	\$ -	\$ 717,400	\$ 474,600	\$ 1,192,000
4.8	345kV, Shunt Reactor with oil containment-25MVAR	2	EA	1,900,130.50	3,520.00	880.00	\$ 3,800,261	\$ 7,040	\$ 1,760	\$ 3,809,061
4.9	345kV, Shunt Reactor with oil containment-100MVAR	0	EA		3,520.00	880.00	\$ -	\$ -	\$ -	\$ -
4.10	Transport & Testing- Shunt Reactor	2	EA		240,400.00	156,600.00	\$ -	\$ 480,800	\$ 313,200	\$ 794,000
4.11	345kV, Phase Angle Regulator with oil containment	0	EA		3,520.00	880.00	\$ -	\$ -	\$ -	\$ -
4.12	345kV, Gas Insulated Switchgear, BAAH Arrangement	12	BKR	847,083.33	508,250.00	338,833.33	\$ 10,165,000	\$ 6,099,000	\$ 4,066,000	\$ 20,330,000
4.13	345kV, Circuit Breaker (PASS)	0	EA		57,239.00	24,531.00	\$ -	\$ -	\$ -	\$ -
4.14	345kV, Circuit Breaker (GIS), outdoor rated	0	EA				\$ -	\$ -	\$ -	\$ -
4.15	345kV, Circuit Breaker (GIS), outdoor rated-Line surge Arrester ( 3phase)	0	EA				\$ -	\$ -	\$ -	\$ -
4.16	345kV, surge Arrester	0	EA		5,460.00	2,340.00	\$ -	\$ -	\$ -	\$ -
4.17	138kV, Phase Angle Regulator with oil containment	0	EA		3,520.00	880.00	\$ -	\$ -	\$ -	\$ -
4.18	Transport & Testing- Phase Angle Regulating Transformer, 138kV	0	EA		15,400.00	6,600.00	\$ -	\$ -	\$ -	\$ -
4.19	Transport & Testing- Transformer	0	EA		15,400.00	6,600.00	\$ -	\$ -	\$ -	\$ -
4.20	138kV, Shunt Reactor with oil containment-80MVAR	0	EA		3,520.00	880.00	\$ -	\$ -	\$ -	\$ -
4.21	Transport & Testing- Shunt Reactor	0	EA		15,400.00	6,600.00	\$ -	\$ -	\$ -	\$ -
4.22	138kV, Gas Insulated Switchgear, BAAH Arrangement	0	BKR		205,800.00	4,200.00	\$ -	\$ -	\$ -	\$ -
4.23	138kV, Circuit Breaker, AIS breaker	0	EA		13,559.00	5,811.00	\$ -	\$ -	\$ -	\$ -
4.24	138kV, Disconnect Switch	0	EA	37,700.00	11,875.50	5,089.50	\$ -	\$ -	\$ -	\$ -
4.25	138kV, Cable sealing end	0	EA	11,600.00	5,460.00	2,340.00	\$ -	\$ -	\$ -	\$ -
4.26	138kV, CCVT	0	EA		7,970.08	3,415.75	\$ -	\$ -	\$ -	\$ -
4.27	138kV, Surge arrester	0	EA		4,200.00	1,800.00	\$ -	\$ -	\$ -	\$ -
4.28	Station service transformers- 120/208v-250VA	0	EA		45,500.00	19,500.00	\$ -	\$ -	\$ -	\$ -
4.29	345kV Gas-Insulated Bus Conductor	30	LF	550.00	275.00	82.50	\$ 16,500	\$ 8,250	\$ 2,475	\$ 27,225.00
4.30	345kV Gas-Insulated Bus Conductor-elbow	0	EA	2,500.00	1,250.00	375.00	\$ -	\$ -	\$ -	\$ -
4.31	Transport & Testing- GIL	1	LS		2,970.00	1,980.00	\$ -	\$ 2,970	\$ 1,980	\$ 4,950.00
<b>TOTAL - MAJOR EQUIPMENT</b>							\$ 18,401,761	\$ 7,318,980	\$ 4,860,895	\$ 30,581,636
<b>5. LOW VOLTAGE &amp; CONTROL CABLE</b>										
5.1	Control Cables	6,000	LF	5.30	1.43	0.29	\$ 31,785	\$ 8,595	\$ 1,719	\$ 42,099
5.2			LF		-	-	\$ -	\$ -	\$ -	\$ -
<b>TOTAL - LOW VOLTAGE &amp; CONTROL CABLE</b>							\$ 31,785	\$ 8,595	\$ 1,719	\$ 42,099
<b>6. CONDUIT &amp; CABLE TRENCH</b>										
6.1	Conduit, PVC, 6", SCH 40		LF	20.70	13.28	6.64	\$ -	\$ -	\$ -	\$ -
6.2	Conduit, PVC, 4", SCH 40	1,200	LF	11.15	10.80	5.40	\$ 13,380	\$ 12,960	\$ 6,480	\$ 32,820
6.3	Conduit, PVC, 3", SCH 40		LF	8.10	10.80	5.40	\$ -	\$ -	\$ -	\$ -
6.4	Conduit, PVC, 2", SCH 40		LF	3.95	10.80	5.40	\$ -	\$ -	\$ -	\$ -
6.5	Conduit, PVC, 1", SCH 40		LF	1.90	10.80	5.40	\$ -	\$ -	\$ -	\$ -
6.6	Cable Trench		LF	266.50	53.04	13.26	\$ -	\$ -	\$ -	\$ -
6.7										
6.8	138kV UG- Conduit	1,287	LF	266.73	202.15	100.00	\$ 343,363	\$ 260,223	\$ 128,736	\$ 732,322
6.9	138kV UG- Cable	3,862	LF	145.00	87.00	58.00	\$ 559,976	\$ 335,985	\$ 223,990	\$ 1,119,951
6.10	138kV UG- Termination	24	EA	27,805.00	9,846.48	2,813.28	\$ 667,320	\$ 236,316	\$ 67,519	\$ 971,154
6.11	345kV UG- Conduit	2,267	LF	266.73	202.15	100.00	\$ 604,666	\$ 458,256	\$ 226,706	\$ 1,289,628
6.12	345kV UG- Cable	6,801	LF	167.00	100.20	66.80	\$ 1,135,742	\$ 681,445	\$ 454,297	\$ 2,271,484
6.13	345kV UG- Termination	24	EA	27,805.00	9,846.48	2,813.28	\$ 667,320	\$ 236,316	\$ 67,519	\$ 971,154
6.14	Fiber Optic Cable	3,554	LF	7.40	3.33	2.22	\$ 26,291	\$ 11,838	\$ 7,892	\$ 46,020
6.15	Ground Continuity Conductor	3,554	LF	13.04	7.53	5.02	\$ 46,344	\$ 26,753	\$ 17,835	\$ 90,932
<b>TOTAL - CONDUIT &amp; CABLE TRENCH</b>							\$ 4,064,400	\$ 2,260,091	\$ 1,200,974	\$ 7,525,466
<b>7. GROUND GRID</b>										
7.1	Cable, 4/0 AWG Bare Copper, 7 Strand Ground Conductor	5,100	LF	2.09	3.42	1.46	\$ 10,664	\$ 17,418	\$ 7,465	\$ 35,547
7.2	Caweld, DSA, 4/0 , T, CROSS	144	EA	165.00	75.00		\$ 23,760	\$ 10,800	\$ -	\$ 34,560
7.3	Ground Rod, 3/4" x 15'	120	EA	135.00	67.50	7.50	\$ 16,200	\$ 8,100	\$ 900	\$ 25,200
<b>TOTAL - GROUND GRID</b>							\$ 50,624	\$ 36,318	\$ 8,365	\$ 95,307
<b>8. CONTROL ENCLOSURE</b>										
8.1	345kv GIS Bldg	1	EA	2,926,829.03	2,048,780.32	878,048.71	\$ 2,926,829	\$ 2,048,780	\$ 878,049	\$ 5,853,658
8.2	138kv GIS/Control Bldg	0	EA	1,145,280.92	801,696.65	343,584.28	\$ -	\$ -	\$ -	\$ -



Item	Item Description	Estimated Quantity	Unit of Measure	Material Supply Rate	Labor Supply Rate	Const. Equipment Rate	Material Supply Cost	Labor Supply Cost	Const. Equipment Cost	TOTAL COST
8.3	Primary Line Relays (87L): SEL-411L	2	EA	21,328.12	17,062.49	4,265.62	\$ 42,656	\$ 34,125	\$ 8,531	\$ 85,312
8.4	Backup Line Relays (87L): GE L90	2	EA	21,328.12	17,062.49	4,265.62	\$ 42,656	\$ 34,125	\$ 8,531	\$ 85,312
8.5	Primary Bay Control: SEL-451	4	EA	21,328.12	17,062.49	4,265.62	\$ 85,312	\$ 68,250	\$ 17,062	\$ 170,625
8.6	Backup Bay Control: SEL-451	4	EA	21,328.12	17,062.49	4,265.62	\$ 85,312	\$ 68,250	\$ 17,062	\$ 170,625
8.7	Primary Transformer/Reactor/PAR Differential Relays: SEL-487E	3	EA	21,328.12	17,062.49	4,265.62	\$ 63,984	\$ 51,187	\$ 12,797	\$ 127,969
8.8	Backup Transformer/Reactor/PAR Differential Relays: GE T60	3	EA	21,328.12	17,062.49	4,265.62	\$ 63,984	\$ 51,187	\$ 12,797	\$ 127,969
8.9	Primary Bus Differential Relays: SEL-487B	4	EA	21,328.12	17,062.49	4,265.62	\$ 85,312	\$ 68,250	\$ 17,062	\$ 170,625
8.10	Backup Bus Differential Relays: GE B90	4	EA	21,328.12	17,062.49	4,265.62	\$ 85,312	\$ 68,250	\$ 17,062	\$ 170,625
8.11	RTU Panel A: SEL-2240 Axion, SEL-2730M ENET SW., SEL-2407 GPS, Modem, SEL-2523 Ann	1	EA	12,500.00	10,000.00	2,500.00	\$ 12,500	\$ 10,000	\$ 2,500	\$ 25,000
8.12	RTU Panel B: SEL-2730M Ethernet Switch, SEL-2407 GPS Clock, SEL-2523 Annunciator	1	EA	12,500.00	10,000.00	2,500.00	\$ 12,500	\$ 10,000	\$ 2,500	\$ 25,000
8.13	HMI Panel	1	EA	12,500.00	10,000.00	2,500.00	\$ 12,500	\$ 10,000	\$ 2,500	\$ 25,000
8.14	Primary Line Relays (87L): SEL-411L	4	EA	21,328.12	17,062.49	4,265.62	\$ 85,312	\$ 68,250	\$ 17,062	\$ 170,625
8.15	Backup Line Relays (87L): GE L90	4	EA	21,328.12	17,062.49	4,265.62	\$ 85,312	\$ 68,250	\$ 17,062	\$ 170,625
8.16	Primary Transformer/Reactor/PAR Differential Relays: SEL-487E	1	EA	21,328.12	17,062.49	4,265.62	\$ 21,328	\$ 17,062	\$ 4,266	\$ 42,656
8.17	Backup Transformer/Reactor/PAR Differential Relays: GE T60	1	EA	21,328.12	17,062.49	4,265.62	\$ 21,328	\$ 17,062	\$ 4,266	\$ 42,656
8.18	125VDC Battery System	2	LS	25,000.00	22,750.00	9,750.00	\$ 50,000	\$ 45,500	\$ 19,500	\$ 115,000
8.19	Control house AC Panel	2	EA	65,000.00	91,000.00	39,000.00	\$ 130,000	\$ 182,000	\$ 78,000	\$ 390,000
8.20	Control House DC Panel	2	EA	65,000.00	91,000.00	39,000.00	\$ 130,000	\$ 182,000	\$ 78,000	\$ 390,000
8.21	Generator	1	EA	130,000.00	72,800.00	31,200.00	\$ 130,000	\$ 72,800	\$ 31,200	\$ 234,000
TOTAL - CONTROL ENCLOSURE							\$ 4,172,141	\$ 3,175,330	\$ 1,245,811	\$ 8,593,282
8.Newbridge 345/138 kV GIS Substation Upgrades							\$ 29,191,940	\$ 15,404,415	\$ 8,930,934	\$ 53,527,289
9. MOB/DEMOB, ENGINEERING, PERMITTING, T&C, PM & INDIRECTS										
	Contractor Mobilization / Demobilization									
9.1	Mob / Demob	1.0	LS		495,962.21	212,555.23	\$ -	\$ 495,962	\$ 212,555	\$ 708,517
	Project Management, Material Handling & Amenities									
9.2	Preconstruction Supervision (Engineering, Permitting, Procurement)	1	LS		331,972.89		\$ -	\$ 331,973	\$ -	\$ 331,973
9.3	Project Management & Staffing (includes PM, Field Engineers / Supervision, Scheduler and Cost Manager, SHEQ Staff, and Admin Staff)	1	LS		1,327,891.55		\$ -	\$ 1,327,892	\$ -	\$ 1,327,892
9.4	Utility PM and Project Oversight	1	LS		331,972.89		\$ -	\$ 331,973	\$ -	\$ 331,973
9.5	Site Accommodation, Facilities, Storage	1	LS	331,972.89			\$ 331,973	\$ -	\$ -	\$ 331,973
	Engineering									
9.6	Design Engineering	1.00	LS		2,655,783.10		\$ -	\$ 2,655,783	\$ -	\$ 2,655,783
9.7	LIDAR /GPR	1.00	LS		-		\$ -	\$ -	\$ -	\$ -
9.8	Geotech		EA		2,730.00	1,820.00	\$ -	\$ -	\$ -	\$ -
9.9	Surveying/Staking	1.00	Site		232,381.02		\$ -	\$ 232,381	\$ -	\$ 232,381
	Testing & Commissioning									
9.10	Testing & Commissioning of SS and Equipment	1.00	LS		1,244,898.33		\$ -	\$ 1,244,898	\$ -	\$ 1,244,898
	Permitting and Additional Costs									
9.11	Physical Security	-	LS		62,196.12		\$ -	\$ -	\$ -	\$ -
9.12	Environmental Licensing & Permitting Costs & related legal cost	1.00	LS		331,972.89		\$ -	\$ 331,973	\$ -	\$ 331,973
9.13	Environmental-special studies/investigation	-	LS		-		\$ -	\$ -	\$ -	\$ -
9.14	Warranties / LOC's	1.00	LS		99,591.87		\$ -	\$ 99,592	\$ -	\$ 99,592
9.15	Laydown Lease	-	LS				\$ -	\$ -	\$ -	\$ -
9.16	Real Estate ( Acquisition)	-	LS			649,844.00	\$ -	\$ -	\$ -	\$ -
9.17	Legal Fees (Real estate)	-	LS		-	19,495.32	\$ -	\$ -	\$ -	\$ -
9.18	Insurance	-	LS		-	-	\$ -	\$ -	\$ -	\$ -
9.19	Bonds	1	LS		-	\$ 1,780,000	\$ -	\$ -	\$ 1,780,000	\$ 1,780,000
9.20	Sales Tax on Materials	8.80%	LS	29,191,939.93			\$ 2,568,891	\$ -	\$ -	\$ 2,568,891
9.21	Fees for permits, including roadway, railroad, building or other local permits	1.00	LS		53,527.29		\$ -	\$ 53,527	\$ -	\$ 53,527
TOTAL - MOB/DEMOB, ENGINEERING, PERMITTING, T&C, PM & INDIRECTS:							\$ 2,900,864	\$ 7,105,954	\$ 1,992,555	\$ 11,999,373



Item	Item Description	Estimated Quantity	Unit of Measure	Material Supply Rate	Labor Supply Rate	Const. Equipment Rate	Material Supply Cost	Labor Supply Cost	Const. Equipment Cost	TOTAL COST
1.19	Substation entrance with asphalt	0	SY	19.50	26.00	19.50	\$ -	\$ -	\$ -	\$ -
1.20	Concrete curb	0	LF	26.00	27.30	11.70	\$ -	\$ -	\$ -	\$ -
1.21	Retaining Wall	0	LF	156.00	117.00	117.00	\$ -	\$ -	\$ -	\$ -
<b>TOTAL - SITE PREP/ GRADING/ FENCING / CIVIL</b>							\$ 311,324	\$ 248,835	\$ 141,711	\$ 701,870
<b>2. SUBSTATION FOUNDATIONS</b>										
2.1	345kV, Lightning mast	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.2	345kV, A Frame 70'	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.3	345kV, Bus support-3 Ph	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.4	345kV, Bus support-3 Ph, low	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.5	345kV, Bus support-1 Ph	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.6	345kV, GIS air terminal	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.7	345kV, GIS support-1 Ph	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.8	345kV, GIS support-3 Ph	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.9	345kV, GIS Cable sealing end	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.10	345kV, Cable sealing end	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.11	345kV, CCVT	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.12	345kV, Disconnect Switch	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.13	345/138KV, Power Transformer with oil containment	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.14	345kV, Shunt Reactor with oil containment-150MVAR	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.15	345kV, Shunt Reactor with oil containment-100MVAR	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.16	345kV, Phase Angle Regulator with oil containment	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.17	345kV, Circuit Breaker (PASS)	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.18	345kV, Circuit Breaker (GIS), outdoor rated	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.19	345Kv, GIS Enclosure-BLDG with generator pad	1,140	CY	703.89	804.44	502.78	\$ 802,429	\$ 917,062	\$ 573,164	\$ 2,292,654
2.20	345kV, Surge arrester	-	CY	-	-	-	\$ -	\$ -	\$ -	\$ -
2.21	138kV, Phase Angle Regulator with oil containment	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.22	138kV, Shunt Reactor with oil containment-80MVAR	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.23	138kV, Circuit Breaker, AIS breaker	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.24	138kV, Bus support-3 Ph, low	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.25	138kV, Bus support-1 Ph, low	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.26	138kV, Disconnect Switch	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.27	138kV, Cable sealing end	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.28	138kV, Surge arrester	-	CY	-	-	-	\$ -	\$ -	\$ -	\$ -
2.29	138kV, CCVT	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.30	138kV, A Frame 50'	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.31	Firewall Foundation	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.32	Precast Firewall for transformer, PARs, reactors	-	SF	25.00	15.00	10.00	\$ -	\$ -	\$ -	\$ -
2.33	Precast Concrete Piles-12"X80'	-	EA	18,000.00	3,200.00	2,800.00	\$ -	\$ -	\$ -	\$ -
2.34	Local Control Cabinet foundation	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.35	138kV, GIS Enclosure-BLDG & control room	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
<b>TOTAL - 345KV FOUNDATION</b>							\$ 802,429	\$ 917,062	\$ 573,164	\$ 2,292,654
<b>3. SUBSTATION STRUCTURES</b>										
3.1	345kV, Lightning mast	0	EA				\$ -	\$ -	\$ -	\$ -
3.2	345kV, A Frame 70'	0	EA	48,100.00	28,860.00	19,240.00	\$ -	\$ -	\$ -	\$ -
3.3	345kV, Bus support-3 Ph	0	EA	8,346.00	5,758.74	3,839.16	\$ -	\$ -	\$ -	\$ -
3.4	345kV, Bus support-3 Ph, low	0	EA	8,346.00	5,758.74	3,839.16	\$ -	\$ -	\$ -	\$ -
3.5	345kV, Bus support-1 Ph	0	EA	4,810.00	2,886.00	1,924.00	\$ -	\$ -	\$ -	\$ -
3.6	345kV, GIS air terminal	0	EA	8,346.00	5,758.74	3,839.16	\$ -	\$ -	\$ -	\$ -
3.7	345kV, GIS support-1 Ph	0	EA	8,346.00	5,758.74	3,839.16	\$ -	\$ -	\$ -	\$ -
3.8	345kV, GIS support-3 Ph	0	EA	4,810.00	2,886.00	1,924.00	\$ -	\$ -	\$ -	\$ -
3.9	345kV, GIS Cable sealing end	0	EA	8,346.00	5,758.74	3,839.16	\$ -	\$ -	\$ -	\$ -
3.10	345kV, Cable sealing end	0	EA	8,346.00	5,758.74	3,839.16	\$ -	\$ -	\$ -	\$ -
3.11	345kV, CCVT	0	EA	4,810.00	2,886.00	1,924.00	\$ -	\$ -	\$ -	\$ -
3.12	345kV, Disconnect Switch	0	EA	19,240.00	11,544.00	7,696.00	\$ -	\$ -	\$ -	\$ -
3.13	138kV, Bus support-3 Ph, low	0	EA	4,173.00	2,879.76	1,919.84	\$ -	\$ -	\$ -	\$ -
3.14	138kV, Bus support-1 Ph, low	0	EA	2,782.00	1,919.84	1,279.89	\$ -	\$ -	\$ -	\$ -
3.15	138kV, Disconnect Switch	0	EA				\$ -	\$ -	\$ -	\$ -
3.16	138kV, Cable sealing end	0	EA	4,810.00	2,886.00	1,924.00	\$ -	\$ -	\$ -	\$ -
3.18	138kV, Surge arrester	0	EA	4,810.00	2,886.00	1,924.00	\$ -	\$ -	\$ -	\$ -
3.17	138kV, CCVT	0	EA	3,206.67	1,924.00	1,282.67	\$ -	\$ -	\$ -	\$ -
3.18	138kV, A Frame 50'	0	EA	33,000.00	19,800.00	13,200.00	\$ -	\$ -	\$ -	\$ -
3.19	345kV Gas-Insulated Bus Conductor	0	LF	550.00	275.00	82.50	\$ -	\$ -	\$ -	\$ -
3.20	345kV Gas-Insulated Bus Conductor-elbow	0	EA	2,500.00	1,250.00	375.00	\$ -	\$ -	\$ -	\$ -
3.21	AL. Bus Tubing, 5" SCH 80	0	LF	25.00	184.94	123.29	\$ -	\$ -	\$ -	\$ -
3.22	AL. Bus fittings	0	LS	-	-	-	\$ -	\$ -	\$ -	\$ -

Item	Item Description	Estimated Quantity	Unit of Measure	Material Supply Rate	Labor Supply Rate	Const. Equipment Rate	Material Supply Cost	Labor Supply Cost	Const. Equipment Cost	TOTAL COST
3.23	Steel grating and support beams-transformer moat	0	LB	2.73	1.17	0.50	\$ -	\$ -	\$ -	\$ -
TOTAL - SUBSTATION STRUCTURES & GAS-INSULATED CONDUCTOR							\$ -	\$ -	\$ -	\$ -
4. MAJOR EQUIPMENT										
4.1	345kV, GIS air terminal	0	EA				\$ -	\$ -	\$ -	\$ -
4.2	345kV, GIS Cable sealing end	0	EA				\$ -	\$ -	\$ -	\$ -
4.3	345kV, Cable sealing end	0	EA		5,460.00	2,340.00	\$ -	\$ -	\$ -	\$ -
4.4	345kV, CCVT	0	EA		15,941.99	6,832.28	\$ -	\$ -	\$ -	\$ -
4.5	345kV, Disconnect Switch	0	EA	57,720.00	34,632.00	23,088.00	\$ -	\$ -	\$ -	\$ -
4.6	345/138KV, Power Transformer with oil containment	0	EA		3,520.00	880.00	\$ -	\$ -	\$ -	\$ -
4.7	Transport & Testing- Transformer	0	EA		15,400.00	6,600.00	\$ -	\$ -	\$ -	\$ -
4.8	345kV, Shunt Reactor with oil containment-150MVAR	0	EA		3,520.00	880.00	\$ -	\$ -	\$ -	\$ -
4.9	345kV, Shunt Reactor with oil containment-100MVAR	0	EA		3,520.00	880.00	\$ -	\$ -	\$ -	\$ -
4.10	Transport & Testing- Shunt Reactor	0	EA		15,400.00	6,600.00	\$ -	\$ -	\$ -	\$ -
4.11	345kV, Phase Angle Regulator with oil containment	0	EA		3,520.00	880.00	\$ -	\$ -	\$ -	\$ -
4.12	345kV, Gas Insulated Switchgear, BAAH Arrangement	6	BKR	855,000.00	513,000.00	342,000.00	\$ 5,130,000	\$ 3,078,000	\$ 2,052,000	\$ 10,260,000
4.13	345kV, Circuit Breaker (PASS)	0	EA		57,239.00	24,531.00	\$ -	\$ -	\$ -	\$ -
4.14	345kV, Circuit Breaker (GIS), outdoor rated	0	EA				\$ -	\$ -	\$ -	\$ -
4.15	345kV, Circuit Breaker (GIS), outdoor rated-Line surge Arrester ( 3phase)	0	EA				\$ -	\$ -	\$ -	\$ -
4.16	345kV, surge Arrester	0	EA		5,460.00	2,340.00	\$ -	\$ -	\$ -	\$ -
4.17	138kV, Phase Angle Regulator with oil containment	0	EA		3,520.00	880.00	\$ -	\$ -	\$ -	\$ -
4.18	Transport & Testing- Phase Angle Regulating Transformer, 138kV	0	EA		15,400.00	6,600.00	\$ -	\$ -	\$ -	\$ -
4.19	Transport & Testing- Transformer	0	EA		15,400.00	6,600.00	\$ -	\$ -	\$ -	\$ -
4.20	138kV, Shunt Reactor with oil containment-80MVAR	0	EA		3,520.00	880.00	\$ -	\$ -	\$ -	\$ -
4.21	Transport & Testing- Shunt Reactor	0	EA		15,400.00	6,600.00	\$ -	\$ -	\$ -	\$ -
4.22	138kV, Gas Insulated Switchgear, BAAH Arrangement	0	BKR		205,800.00	4,200.00	\$ -	\$ -	\$ -	\$ -
4.23	138kV, Circuit Breaker, AIS breaker	0	EA		13,559.00	5,811.00	\$ -	\$ -	\$ -	\$ -
4.24	138kV, Disconnect Switch	0	EA	37,700.00	11,875.50	5,089.50	\$ -	\$ -	\$ -	\$ -
4.25	138kV, Cable sealing end	0	EA	11,600.00	5,460.00	2,340.00	\$ -	\$ -	\$ -	\$ -
4.26	138kV, CCVT	0	EA		7,970.08	3,415.75	\$ -	\$ -	\$ -	\$ -
4.27	138kV, Surge arrester	0	EA		4,200.00	1,800.00	\$ -	\$ -	\$ -	\$ -
4.28	Station service transformers- 120/208v-250VA	0	EA		45,500.00	19,500.00	\$ -	\$ -	\$ -	\$ -
TOTAL - MAJOR EQUIPMENT							\$ 5,130,000	\$ 3,078,000	\$ 2,052,000	\$ 10,260,000
5. LOW VOLTAGE & CONTROL CABLE										
5.1	Control Cables		LF	5.30	1.43	0.29	\$ -	\$ -	\$ -	\$ -
5.2			LF		-	-	\$ -	\$ -	\$ -	\$ -
TOTAL - LOW VOLTAGE & CONTROL CABLE							\$ -	\$ -	\$ -	\$ -
6. CONDUIT & CABLE TRENCH										
6.1	Conduit, PVC, 6", SCH 40		LF	20.70	13.28	6.64	\$ -	\$ -	\$ -	\$ -
6.2	Conduit, PVC, 4", SCH 40		LF	11.15	10.80	5.40	\$ -	\$ -	\$ -	\$ -
6.3	Conduit, PVC, 3", SCH 40		LF	8.10	10.80	5.40	\$ -	\$ -	\$ -	\$ -
6.4	Conduit, PVC, 2", SCH 40		LF	3.95	10.80	5.40	\$ -	\$ -	\$ -	\$ -
6.5	Conduit, PVC, 1", SCH 40		LF	1.90	10.80	5.40	\$ -	\$ -	\$ -	\$ -
6.6	Cable Trench		LF	266.50	53.04	13.26	\$ -	\$ -	\$ -	\$ -
6.7							\$ -	\$ -	\$ -	\$ -
6.8	138kV UG- Conduit	0	LF	266.73	202.15	100.00	\$ -	\$ -	\$ -	\$ -
6.9	138kV UG- Cable		LF	145.00	87.00	58.00	\$ -	\$ -	\$ -	\$ -
6.10	138kV UG- Termination	0	EA	27,805.00	9,846.48	2,813.28	\$ -	\$ -	\$ -	\$ -
6.11	345kV UG- Conduit	3,207	LF	266.73	202.15	100.00	\$ 855,326	\$ 648,223	\$ 320,686	\$ 1,824,235
6.12	345kV UG- Cable	9,620	LF	167.00	100.20	66.80	\$ 1,606,557	\$ 963,934	\$ 642,623	\$ 3,213,113
6.13	345kV UG- Termination	18	EA	27,805.00	9,846.48	2,813.28	\$ 500,490	\$ 177,237	\$ 50,639	\$ 728,366
6.14	Fiber Optic Cable	3,207	LF	7.40	3.33	2.22	\$ 23,720	\$ 10,680	\$ 7,120	\$ 41,520
6.15	Ground Continuity Conductor	3,207	LF	13.04	7.53	5.02	\$ 41,812	\$ 24,137	\$ 16,091	\$ 82,040
TOTAL - CONDUIT & CABLE TRENCH							\$ 3,027,905	\$ 1,824,211	\$ 1,037,159	\$ 5,889,274
7. GROUND GRID										
7.1	Cable, 4/0 AWG Bare Copper, 7 Strand Ground Conductor	3,280	LF	2.09	3.42	1.46	\$ 6,858	\$ 11,202	\$ 4,801	\$ 22,862
7.2	Caweld, DSA, 4/0 , T, CROSS	164	EA	165.00	75.00		\$ 27,060	\$ 12,300	\$ -	\$ 39,360
7.3	Ground Rod, 3/4" x 15'	53	EA	135.00	67.50	7.50	\$ 7,196	\$ 3,598	\$ 400	\$ 11,193
TOTAL - GROUND GRID							\$ 41,114	\$ 27,100	\$ 5,201	\$ 73,415
8. CONTROL ENCLOSURE										
8.1	345kv GIS Bldg	1	EA	2,226,935.13	1,558,854.59	668,080.54	\$ 2,226,935	\$ 1,558,855	\$ 668,081	\$ 4,453,870
8.2	138kv GIS/Control Bldg	0	EA	1,145,280.92	801,696.65	343,584.28	\$ -	\$ -	\$ -	\$ -
8.3	Primary Line Relays (87L): SEL-411L	4	EA	21,328.12	17,062.49	4,265.62	\$ 85,312	\$ 68,250	\$ 17,062	\$ 170,625

Item	Item Description	Estimated Quantity	Unit of Measure	Material Supply Rate	Labor Supply Rate	Const. Equipment Rate	Material Supply Cost	Labor Supply Cost	Const. Equipment Cost	TOTAL COST
8.4	Backup Line Relays (87L): GE L90	4	EA	21,328.12	17,062.49	4,265.62	\$ 85,312	\$ 68,250	\$ 17,062	\$ 170,625
8.5	Primary Bay Control: SEL-451	2	EA	21,328.12	17,062.49	4,265.62	\$ 42,656	\$ 34,125	\$ 8,531	\$ 85,312
8.6	Backup Bay Control: SEL-451	2	EA	21,328.12	17,062.49	4,265.62	\$ 42,656	\$ 34,125	\$ 8,531	\$ 85,312
8.7	Primary Bus Differential Relays: SEL-487B	2	EA	21,328.12	17,062.49	4,265.62	\$ 42,656	\$ 34,125	\$ 8,531	\$ 85,312
8.8	Backup Bus Differential Relays: GE B90	2	EA	21,328.12	17,062.49	4,265.62	\$ 42,656	\$ 34,125	\$ 8,531	\$ 85,312
8.9	RTU Panel A: SEL-2240 Axion, SEL-2730M ENET SW., SEL-2407 GPS, Modem, SEL-2523 Ann	1	EA	12,500.00	10,000.00	2,500.00	\$ 12,500	\$ 10,000	\$ 2,500	\$ 25,000
8.10	RTU Panel B: SEL-2730M Ethernet Switch, SEL-2407 GPS Clock, SEL-2523 Annunciator	1	EA	12,500.00	10,000.00	2,500.00	\$ 12,500	\$ 10,000	\$ 2,500	\$ 25,000
8.11	HMI Panel	1	EA	12,500.00	10,000.00	2,500.00	\$ 12,500	\$ 10,000	\$ 2,500	\$ 25,000
8.12	Primary Line Relays (87L): SEL-411L	3	EA	21,328.12	17,062.49	4,265.62	\$ 63,984	\$ 51,187	\$ 12,797	\$ 127,969
8.13	Backup Line Relays (87L): GE L90	3	EA	21,328.12	17,062.49	4,265.62	\$ 63,984	\$ 51,187	\$ 12,797	\$ 127,969
8.14	125VDC Battery System	2	LS	25,000.00	22,750.00	9,750.00	\$ 50,000	\$ 45,500	\$ 19,500	\$ 115,000
8.15	Control house AC Panel	2	EA	65,000.00	91,000.00	39,000.00	\$ 130,000	\$ 182,000	\$ 78,000	\$ 390,000
8.16	Control House DC Panel	2	EA	65,000.00	91,000.00	39,000.00	\$ 130,000	\$ 182,000	\$ 78,000	\$ 390,000
8.17	Generator	1	EA	130,000.00	72,800.00	31,200.00	\$ 130,000	\$ 72,800	\$ 31,200	\$ 234,000
TOTAL - CONTROL ENCLOSURE							\$ 3,173,654	\$ 2,446,529	\$ 976,124	\$ 6,596,307
9.Rainey 345kV GIS Substation Upgrades							\$ 12,486,425	\$ 8,541,737	\$ 4,785,358	\$ 25,813,520
9. MOB/DEMOB, ENGINEERING, PERMITTING, T&C, PM & INDIRECTS										
	Contractor Mobilization / Demobilization									
9.1	Mob / Demob	1.0	LS		286,898.32	122,956.42	\$ -	\$ 286,898	\$ 122,956	\$ 409,855
	Project Management, Material Handling & Amenities									
9.2	Preconstruction Supervision (Engineering, Permitting, Procurement)	1	LS		155,535.20		\$ -	\$ 155,535	\$ -	\$ 155,535
9.3	Project Management & Staffing (includes PM, Field Engineers / Supervision, Scheduler and Cost Manager, SHEQ Staff, and Admin Staff)	1	LS		622,140.82		\$ -	\$ 622,141	\$ -	\$ 622,141
9.4	Utility PM and Project Oversight	1	LS		155,535.20		\$ -	\$ 155,535	\$ -	\$ 155,535
9.5	Site Accommodation, Facilities, Storage	1	LS	155,535.20			\$ 155,535	\$ -	\$ -	\$ 155,535
	Engineering									
9.6	Design Engineering	1.00	LS		1,244,281.63		\$ -	\$ 1,244,282	\$ -	\$ 1,244,282
9.7	LIDAR /GPR	1.00	LS		-		\$ -	\$ -	\$ -	\$ -
9.8	Geotech	5.00	EA		2,730.00	1,820.00	\$ -	\$ 13,650	\$ 9,100	\$ 22,750
9.9	Surveying/Staking	1.00	Site		108,874.64		\$ -	\$ 108,875	\$ -	\$ 108,875
	Testing & Commissioning									
9.10	Testing & Commissioning of SS and Equipment	1.00	LS		583,257.02		\$ -	\$ 583,257	\$ -	\$ 583,257
	Permitting and Additional Costs									
9.11	Physical Security	1.00	LS		62,196.12		\$ -	\$ 62,196	\$ -	\$ 62,196
9.12	Environmental Licensing & Permitting Costs & related legal cost	1.00	LS		155,535.20		\$ -	\$ 155,535	\$ -	\$ 155,535
9.13	Environmental-special studies/investigation	-	LS		-		\$ -	\$ -	\$ -	\$ -
9.14	Warranties / LOC's	1.00	LS		46,660.56		\$ -	\$ 46,661	\$ -	\$ 46,661
9.15	Laydown Lease		LS				\$ -	\$ -	\$ -	\$ -
9.16	Real Estate ( Acquisition)	1.00	LS			1,874,704.00	\$ -	\$ -	\$ 1,874,704	\$ 1,874,704
9.17	Legal Fees (Real estate)	1.00	LS		-	56,241.12	\$ -	\$ -	\$ 56,241	\$ 56,241
9.18	Insurance	-	LS		-	-	\$ -	\$ -	\$ -	\$ -
9.19	Bonds	1	LS		-	\$ 900,000	\$ -	\$ -	\$ 900,000	\$ 900,000
9.20	Sales Tax on Materials	8.80%	LS	12,486,425.49			\$ 1,098,805	\$ -	\$ -	\$ 1,098,805
9.21	Fees for permits, including roadway, railroad, building or other local permits	1.00	LS		25,813.52		\$ -	\$ 25,814	\$ -	\$ 25,814
TOTAL - MOB/DEMOB, ENGINEERING, PERMITTING, T&C, PM & INDIRECTS:							\$ 1,254,341	\$ 3,460,378	\$ 2,963,002	\$ 7,677,720



<u>NEXTera Energy- TO36 Core 1</u>			
<u>10.Shore Road 138kV Substation Upgrades</u>			
Total:	Total:	\$	13,943,860

<u>NEXTera Energy- TO36 Core 1</u>			
<u>10.Shore Road 138kV Substation Upgrades</u>			
Total:	Total:	\$	13,943,860

<u>NEXTera Energy- TO36 Core 1</u>			
<u>10.Shore Road 138kV Substation Upgrades</u>			
Total:	Total:	\$	13,943,860

NEXtera Energy- TO36 Core 1				
	Material Supply	Labor Supply	Equip Supply	Total
10.Shore Road 138kV Substation Upgrades				
1. SITE PREP/ GRADING/ FENCING / CIVIL	\$ 9,922	\$ 10,764	\$ 6,052	\$ 26,738
2. SUBSTATION FOUNDATIONS	\$ 241,411	\$ 275,899	\$ 172,437	\$ 689,747
3. SUBSTATION STRUCTURES	\$ 135,326	\$ 72,142	\$ 35,749	\$ 243,217
4. MAJOR EQUIPMENT	\$ 5,681,973	\$ 251,002	\$ 153,318	\$ 6,086,293
5. LOW VOLTAGE & CONTROL CABLE	\$ 61,981	\$ 16,760	\$ 3,352	\$ 82,093
6. CONDUIT & CABLE TRENCH	\$ 93,385	\$ 39,180	\$ 16,275	\$ 148,840
7. GROUND GRID	\$ 2,925	\$ 2,335	\$ 610	\$ 5,871
8. CONTROL ENCLOSURE	\$ 85,312	\$ 68,250	\$ 17,062	\$ 170,625
9. MOB/DEMOB, ENGINEERING, PERMITTING, T&C, PM & INDIRECTS	\$ 630,011	\$ 1,483,167	\$ 280,758	\$ 2,393,936
SUBTOTAL (Costs):	\$ 6,942,247	\$ 2,219,499	\$ 685,612	\$ 9,847,359
CONTRACTOR MARK-UP (OH&P)	\$ 1,249,604	\$ 399,510	\$ 123,410	\$ 1,772,525
SUBTOTAL:	\$ 8,191,851	\$ 2,619,009	\$ 809,023	\$ 11,619,883
CONTINGENCY ON ENTIRE PROJECT	\$ 1,638,370	\$ 523,802	\$ 161,805	\$ 2,323,977
TOTAL:	\$ 9,830,222	\$ 3,142,811	\$ 970,827	\$ 13,943,860

Description of Work: Add a new 250 MVAR reactor at the existing Shore Road 138kV station (5 block of 50 MVAR)										
Item	Item Description	Estimated Quantity	Unit of Measure	Material Supply Rate	Labor Supply Rate	Const. Equipment Rate	Material Supply Cost	Labor Supply Cost	Const. Equipment Cost	TOTAL COST
10.Shore Road 138kV Substation Upgrades										
1. SITE PREP/ GRADING/ FENCING / CIVIL										
1.1	Site Clearing	0.1	ACRE	-	10,800.00	7,200.00	\$ -	\$ 540	\$ 360	\$ 900
1.2	Demolition	0	LS	-	-	-	\$ -	\$ -	\$ -	\$ -
1.3	New Access Road - 20'	0	SY	4.85	7.20	4.80	\$ -	\$ -	\$ -	\$ -
1.4	Strip and Dispose Top Soil	81	CY		24.50	10.50	\$ -	\$ 1,976	\$ 847	\$ 2,823
1.5	Site Grading- Excavation for Substation Pad	242	CY		9.00	6.00	\$ -	\$ 2,178	\$ 1,452	\$ 3,630
1.6	Site Grading- Excavation for Substation Pad-Rock excavation-Hauling and disposal	131	CY		21.00	9.00	\$ -	\$ 2,744.28	\$ 1,176.12	\$ 3,920.40
1.7	Site Grading- Fill for Substation Pad (site borrow, compacted in place)	196	CY		2.40	1.60	\$ -	\$ 470	\$ 314	\$ 784
1.8	Site Grading -Fill for Substation Pad (import, compacted in place)	131	CY	25.00	2.40	1.60	\$ 3,267	\$ 314	\$ 209	\$ 3,790
1.9	Blasting		EA				\$ -	\$ -	\$ -	\$ -
1.10	Install substation 8" pad base	242	SY	11.00	6.00	4.00	\$ 2,662	\$ 1,452	\$ 968	\$ 5,082
1.11	Site Surfacing - Aggregate 6" Thick	242	SY	16.50	4.50	3.00	\$ 3,993	\$ 1,089	\$ 726	\$ 5,808
1.12	7' Station Fence w/ Barbed Wire & Grounding	0	LF	13.85	13.85	6.92	\$ -	\$ -	\$ -	\$ -
1.13	20' Slide Gate & Grounding	0	EA	8,100.00	3,245.00	1,305.00	\$ -	\$ -	\$ -	\$ -
1.14	4' Pedestrian gate	0	EA	2,500.00	1,000.00	350.00	\$ -	\$ -	\$ -	\$ -
1.15	Storm drain-15" HDPE, INFILTRATION TRENCH, INLET and Hydrodynamic Separator	0	LS	109,761.60	-	-	\$ -	\$ -	\$ -	\$ -
1.16	Seeding	0	SF	1.50	1.50	1.00	\$ -	\$ -	\$ -	\$ -
1.17	Erosion Control-Silt fence install & remove	0	LF	2.41	3.16	0.72	\$ -	\$ -	\$ -	\$ -
1.18	Temporary fencing	0	LF	7.50	5.25	2.25	\$ -	\$ -	\$ -	\$ -
1.19	Substation entrance with asphalt	0	SY	19.50	26.00	19.50	\$ -	\$ -	\$ -	\$ -
1.20	Concrete curb	0	LF	26.00	27.30	11.70	\$ -	\$ -	\$ -	\$ -
1.21	Retaining Wall	0	LF	156.00	117.00	117.00	\$ -	\$ -	\$ -	\$ -

Item	Item Description	Estimated Quantity	Unit of Measure	Material Supply Rate	Labor Supply Rate	Const. Equipment Rate	Material Supply Cost	Labor Supply Cost	Const. Equipment Cost	TOTAL COST
TOTAL - SITE PREP/ GRADING/ FENCING / CIVIL							\$ 9,922	\$ 10,764	\$ 6,052	\$ 26,738
2. SUBSTATION FOUNDATIONS										
2.1	345kV, Lightning mast	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.2	345kV, A Frame 70'	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.3	345kV, Bus support-3 Ph	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.4	345kV, Bus support-3 Ph, low	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.5	345kV, Bus support-1 Ph	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.6	345kV, GIS air terminal	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.7	345kV, GIS support-1 Ph	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.8	345kV, GIS support-3 Ph	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.9	345kV, GIS Cable sealing end	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.10	345kV, Cable sealing end	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.11	345kV, CCVT	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.12	345kV, Disconnect Switch	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.13	345/138KV, Power Transformer with oil containment	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.14	345kV, Shunt Reactor with oil containment-250MVAR	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.15	345kV, Shunt Reactor with oil containment-100MVAR	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.16	345kV, Phase Angle Regulator with oil containment	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.17	345kV, Circuit Breaker	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.18	345kV, Circuit Breaker (GIS), outdoor rated	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.19	345Kv, GIS Enclosure-BLDG with generator pad	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.20	345kV, Surge arrester	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.21	138kV, Phase Angle Regulator with oil containment	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.22	138kV, Shunt Reactor with oil containment-250MVAR	305	CY	703.89	804.44	502.78	\$ 214,685	\$ 245,354	\$ 153,346	\$ 613,386
2.23	138kV, Circuit Breaker, AIS breaker	4	CY	703.89	804.44	502.78	\$ 3,132	\$ 3,580	\$ 2,237	\$ 8,949
2.24	138kV, Bus support-3 Ph, low	5	CY	703.89	804.44	502.78	\$ 3,766	\$ 4,304	\$ 2,690	\$ 10,759
2.25	138kV, Bus support-1 Ph, low	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.26	138kV, Disconnect Switch	12	CY	703.89	804.44	502.78	\$ 8,531	\$ 9,750	\$ 6,094	\$ 24,375
2.27	138kV, Cable sealing end	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.28	138kV, Surge arrester	-	CY	-	-	-	\$ -	\$ -	\$ -	\$ -
2.29	138kV, CCVT	16	CY	703.89	804.44	502.78	\$ 11,297	\$ 12,911	\$ 8,070	\$ 32,278
2.30	138kV, A Frame 50'	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.31	Firewall Foundation	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.32	Precast Firewall for transformer, PARs, reactors		SF	25.00	15.00	10.00	\$ -	\$ -	\$ -	\$ -
2.33	Precast Concrete Piles-12"X80'		EA	18,000.00	3,200.00	2,800.00	\$ -	\$ -	\$ -	\$ -
2.34	Local Control Cabinet foundation	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.35	138kV, GIS Enclosure-BLDG & control room	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
TOTAL - 345KV FOUNDATION							\$ 241,411	\$ 275,899	\$ 172,437	\$ 689,747
3. SUBSTATION STRUCTURES										
3.1	345kV, Lightning mast		EA				\$ -	\$ -	\$ -	\$ -
3.2	345kV, A Frame 70'		EA	48,100.00	28,860.00	19,240.00	\$ -	\$ -	\$ -	\$ -
3.3	345kV, Bus support-3 Ph		EA	8,346.00	5,758.74	3,839.16	\$ -	\$ -	\$ -	\$ -
3.4	345kV, Bus support-3 Ph, low		EA	8,346.00	5,758.74	3,839.16	\$ -	\$ -	\$ -	\$ -
3.5	345kV, Bus support-1 Ph		EA	4,810.00	2,886.00	1,924.00	\$ -	\$ -	\$ -	\$ -
3.6	345kV, GIS air terminal		EA	8,346.00	5,758.74	3,839.16	\$ -	\$ -	\$ -	\$ -
3.7	345kV, GIS support-1 Ph		EA	8,346.00	5,758.74	3,839.16	\$ -	\$ -	\$ -	\$ -
3.8	345kV, GIS support-3 Ph		EA	4,810.00	2,886.00	1,924.00	\$ -	\$ -	\$ -	\$ -
3.9	345kV, GIS Cable sealing end		EA	8,346.00	5,758.74	3,839.16	\$ -	\$ -	\$ -	\$ -
3.10	345kV, Cable sealing end		EA	8,346.00	5,758.74	3,839.16	\$ -	\$ -	\$ -	\$ -
3.11	345kV, CCVT		EA	4,810.00	2,886.00	1,924.00	\$ -	\$ -	\$ -	\$ -
3.12	345kV, Disconnect Switch		EA	19,240.00	11,544.00	7,696.00	\$ -	\$ -	\$ -	\$ -
3.13	138kV, Bus support-3 Ph, low	1	EA	4,173.00	2,879.76	1,919.84	\$ 4,173	\$ 2,880	\$ 1,920	\$ 8,973
3.14	138kV, Bus support-1 Ph, low		EA	2,782.00	1,919.84	1,279.89	\$ -	\$ -	\$ -	\$ -
3.15	138kV, Disconnect Switch	2	EA				\$ -	\$ -	\$ -	\$ -
3.16	138kV, Cable sealing end		EA	4,810.00	2,886.00	1,924.00	\$ -	\$ -	\$ -	\$ -
3.18	138kV, Surge arrester		EA	4,810.00	2,886.00	1,924.00	\$ -	\$ -	\$ -	\$ -
3.17	138kV, CCVT	3	EA	3,206.67	1,924.00	1,282.67	\$ 9,620	\$ 5,772	\$ 3,848	\$ 19,240
3.18	138kV, A Frame 50'		EA	33,000.00	19,800.00	13,200.00	\$ -	\$ -	\$ -	\$ -
3.19	345kV Gas-Insulated Bus Conductor		LF	550.00	275.00	82.50	\$ -	\$ -	\$ -	\$ -
3.20	345kV Gas-Insulated Bus Conductor-elbow		EA	2,500.00	1,250.00	375.00	\$ -	\$ -	\$ -	\$ -
3.21	AL. Bus Tubing, 5" SCH 80	60	LF	25.00	184.94	123.29	\$ 1,500	\$ 11,096	\$ 7,398	\$ 19,994
3.22	AL. Bus fittings	1	LS	1,800.00	1,800.00	900.00	\$ 1,800	\$ 1,800	\$ 900	\$ 4,500
3.23	Steel grating and support beams-transformer moat	43,280	LB	2.73	1.17	0.50	\$ 118,233	\$ 50,594	\$ 21,683	\$ 190,511

Item	Item Description	Estimated Quantity	Unit of Measure	Material Supply Rate	Labor Supply Rate	Const. Equipment Rate	Material Supply Cost	Labor Supply Cost	Const. Equipment Cost	TOTAL COST
TOTAL - SUBSTATION STRUCTURES & GAS-INSULATED CONDUCTOR							\$ 135,326	\$ 72,142	\$ 35,749	\$ 243,217
4. MAJOR EQUIPMENT										
4.1	345kV, GIS air terminal	0	EA				\$ -	\$ -	\$ -	\$ -
4.2	345kV, GIS Cable sealing end	0	EA				\$ -	\$ -	\$ -	\$ -
4.3	345kV, Cable sealing end	0	EA		5,460.00	2,340.00	\$ -	\$ -	\$ -	\$ -
4.4	345kV, CCVT		EA	4,810.00	2,886.00	1,924.00	\$ -	\$ -	\$ -	\$ -
4.5	345kV, Disconnect Switch		EA	57,720.00	34,632.00	23,088.00	\$ -	\$ -	\$ -	\$ -
4.6	345/138KV, Power Transformer with oil containment	0	EA		3,520.00	880.00	\$ -	\$ -	\$ -	\$ -
4.7	Transport & Testing- Transformer	0	EA		15,400.00	6,600.00	\$ -	\$ -	\$ -	\$ -
4.8	345kV, Shunt Reactor with oil containment-250MVAR		EA		3,520.00	880.00	\$ -	\$ -	\$ -	\$ -
4.9	345kV, Shunt Reactor with oil containment-100MVAR	0	EA		3,520.00	880.00	\$ -	\$ -	\$ -	\$ -
4.10	Transport & Testing- Shunt Reactor		EA		15,400.00	6,600.00	\$ -	\$ -	\$ -	\$ -
4.11	345kV, Phase Angle Regulator with oil containment	0	EA		3,520.00	880.00	\$ -	\$ -	\$ -	\$ -
4.12	345kV, Gas Insulated Switchgear, BAAH Arrangement	0	BKR		205,800.00	4,200.00	\$ -	\$ -	\$ -	\$ -
4.13	345kV, Circuit Breaker		EA		57,239.00	24,531.00	\$ -	\$ -	\$ -	\$ -
4.14	345kV, Circuit Breaker (GIS), outdoor rated	0	EA				\$ -	\$ -	\$ -	\$ -
4.15	345kV, Circuit Breaker (GIS), outdoor rated-Line surge Arrester ( 3phase)	0	EA				\$ -	\$ -	\$ -	\$ -
4.16	345kV, surge Arrester	0	EA		5,460.00	2,340.00	\$ -	\$ -	\$ -	\$ -
4.17	138kV, Phase Angle Regulator with oil containment	0	EA		3,520.00	880.00	\$ -	\$ -	\$ -	\$ -
4.18	Transport & Testing- Phase Angle Regulating Transformer, 138kV	0	EA		15,400.00	6,600.00	\$ -	\$ -	\$ -	\$ -
4.19	Transport & Testing- Transformer	0	EA		15,400.00	6,600.00	\$ -	\$ -	\$ -	\$ -
4.20	138kV, Shunt Reactor with oil containment-250MVAR	1	EA	5,484,953.00	3,520.00	880.00	\$ 5,484,953	\$ 3,520	\$ 880	\$ 5,489,353
4.21	Transport & Testing- Shunt Reactor	1	EA		204,400.00	132,600.00	\$ -	\$ 204,400	\$ 132,600	\$ 337,000
4.22	138kV, Gas Insulated Switchgear, BAAH Arrangement	0	BKR		205,800.00	4,200.00	\$ -	\$ -	\$ -	\$ -
4.23	138kV, Circuit Breaker,	1	EA	112,000.00	13,559.00	5,811.00	\$ 112,000	\$ 13,559	\$ 5,811	\$ 131,370
4.24	138kV, Disconnect Switch	2	EA	37,700.00	11,875.50	5,089.50	\$ 75,400	\$ 23,751	\$ 10,179	\$ 109,330
4.25	138kV, Cable sealing end	0	EA	11,600.00	5,460.00	2,340.00	\$ -	\$ -	\$ -	\$ -
4.26	138kV, CCVT	3	EA	3,206.67	1,924.00	1,282.67	\$ 9,620	\$ 5,772	\$ 3,848	\$ 19,240
4.27	138kV, Surge arrester	0	EA		4,200.00	1,800.00	\$ -	\$ -	\$ -	\$ -
4.28	Station service transformers- 120/208v-250VA	0	EA		45,500.00	19,500.00	\$ -	\$ -	\$ -	\$ -
TOTAL - MAJOR EQUIPMENT							\$ 5,681,973	\$ 251,002	\$ 153,318	\$ 6,086,293
5. LOW VOLTAGE & CONTROL CABLE										
5.1	Control Cables	11,700	LF	5.30	1.43	0.29	\$ 61,981	\$ 16,760	\$ 3,352	\$ 82,093
5.2			LF		-	-	\$ -	\$ -	\$ -	\$ -
TOTAL - LOW VOLTAGE & CONTROL CABLE							\$ 61,981	\$ 16,760	\$ 3,352	\$ 82,093
6. CONDUIT & CABLE TRENCH										
6.1	Conduit, PVC, 6", SCH 40		LF	20.70	13.28	6.64	\$ -	\$ -	\$ -	\$ -
6.2	Conduit, PVC, 4", SCH 40	2,400	LF	11.15	10.80	5.40	\$ 26,760	\$ 25,920	\$ 12,960	\$ 65,640
6.3	Conduit, PVC, 3", SCH 40		LF	8.10	10.80	5.40	\$ -	\$ -	\$ -	\$ -
6.4	Conduit, PVC, 2", SCH 40		LF	3.95	10.80	5.40	\$ -	\$ -	\$ -	\$ -
6.5	Conduit, PVC, 1", SCH 40		LF	1.90	10.80	5.40	\$ -	\$ -	\$ -	\$ -
6.6	Cable Trench	250	LF	266.50	53.04	13.26	\$ 66,625	\$ 13,260	\$ 3,315	\$ 83,200
6.7							\$ -	\$ -	\$ -	\$ -
6.8	138kV UG- Conduit	0	LF	266.73	202.15	100.00	\$ -	\$ -	\$ -	\$ -
6.9	138kV UG- Cable	0	LF	145.00	87.00	58.00	\$ -	\$ -	\$ -	\$ -
6.10	138kV UG- Termination	0	EA	27,805.00	9,846.48	2,813.28	\$ -	\$ -	\$ -	\$ -
6.11	345kV UG- Conduit	0	LF	266.73	202.15	100.00	\$ -	\$ -	\$ -	\$ -
6.12	345kV UG- Cable	0	LF	167.00	100.20	66.80	\$ -	\$ -	\$ -	\$ -
6.13	345kV UG- Termination	0	EA	27,805.00	9,846.48	2,813.28	\$ -	\$ -	\$ -	\$ -
6.14							\$ -	\$ -	\$ -	\$ -
6.15							\$ -	\$ -	\$ -	\$ -
TOTAL - CONDUIT & CABLE TRENCH							\$ 93,385	\$ 39,180	\$ 16,275	\$ 148,840
7. GROUND GRID										
7.1	Cable, 4/0 AWG Bare Copper, 7 Strand Ground Conductor	400	LF	2.09	3.42	1.46	\$ 836	\$ 1,366	\$ 585	\$ 2,788
7.2	Caweld, DSA, 4/0 , T, CROSS	10	EA	165.00	75.00		\$ 1,650	\$ 750	\$ -	\$ 2,400
7.3	Ground Rod, 3/4" x 15'	3	EA	135.00	67.50	7.50	\$ 439	\$ 219	\$ 24	\$ 683
TOTAL - GROUND GRID							\$ 2,925	\$ 2,335	\$ 610	\$ 5,871
8. CONTROL ENCLOSURE										
8.1	345kv GIS Bldg	0	EA	2,226,935.13	1,558,854.59	668,080.54	\$ -	\$ -	\$ -	\$ -
8.2	138kv GIS/Control Bldg	0	EA	1,145,280.92	801,696.65	343,584.28	\$ -	\$ -	\$ -	\$ -
8.3	Primary Bay Control: SEL-451	1	EA	21,328.12	17,062.49	4,265.62	\$ 21,328	\$ 17,062	\$ 4,266	\$ 42,656
8.4	Backup Bay Control: SEL-451	1	EA	21,328.12	17,062.49	4,265.62	\$ 21,328	\$ 17,062	\$ 4,266	\$ 42,656
8.5	Primary Transformer/Reactor/PAR Differential Relays: SEL-487E	1	EA	21,328.12	17,062.49	4,265.62	\$ 21,328	\$ 17,062	\$ 4,266	\$ 42,656
8.6	Backup Transformer/Reactor/PAR Differential Relays: GE T60	1	EA	21,328.12	17,062.49	4,265.62	\$ 21,328	\$ 17,062	\$ 4,266	\$ 42,656

Item	Item Description	Estimated Quantity	Unit of Measure	Material Supply Rate	Labor Supply Rate	Const. Equipment Rate	Material Supply Cost	Labor Supply Cost	Const. Equipment Cost	TOTAL COST
8.14	125VDC Battery System	0	LS	25,000.00	22,750.00	9,750.00	\$ -	\$ -	\$ -	\$ -
8.15	Control house AC Panel	0	EA	65,000.00	91,000.00	39,000.00	\$ -	\$ -	\$ -	\$ -
8.16	Control House DC Panel	0	EA	65,000.00	91,000.00	39,000.00	\$ -	\$ -	\$ -	\$ -
8.17	Generator	0	EA	130,000.00	72,800.00	31,200.00	\$ -	\$ -	\$ -	\$ -
TOTAL - CONTROL ENCLOSURE							\$ 85,312	\$ 68,250	\$ 17,062	\$ 170,625
10.Shore Road 138kV Substation Upgrades							\$ 6,312,236	\$ 736,333	\$ 404,855	\$ 7,453,423
9. MOB/DEMOB, ENGINEERING, PERMITTING, T&C, PM & INDIRECTS										
	Contractor Mobilization / Demobilization									
9.1	Mob / Demob	1.0	LS		39,941.55	17,117.81	\$ -	\$ 39,942	\$ 17,118	\$ 57,059
	Project Management, Material Handling & Amenities									
9.2	Preconstruction Supervision (Engineering, Permitting, Procurement)	1	LS		74,534.23		\$ -	\$ 74,534	\$ -	\$ 74,534
9.3	Project Management & Staffing (includes PM, Field Engineers / Supervision, Scheduler and Cost Manager, SHEQ Staff, and Admin Staff)	1	LS		298,136.92		\$ -	\$ 298,137	\$ -	\$ 298,137
9.4	Utility PM and Project Oversight	1	LS		74,534.23		\$ -	\$ 74,534	\$ -	\$ 74,534
9.5	Site Accommodation, Facilities, Storage	1	LS	74,534.23			\$ 74,534	\$ -	\$ -	\$ 74,534
	Engineering									
9.6	Design Engineering	1.00	LS		596,273.84		\$ -	\$ 596,274	\$ -	\$ 596,274
9.7	LIDAR /GPR	1.00	LS				\$ -	\$ -	\$ -	\$ -
9.8	Geotech	2.00	EA		2,730.00	1,820.00	\$ -	\$ 5,460	\$ 3,640	\$ 9,100
9.9	Surveying/Staking	0.20	Site		52,173.96		\$ -	\$ 10,435	\$ -	\$ 10,435
	Testing & Commissioning									
9.10	Testing & Commissioning of SS and Equipment	1.00	LS		279,503.36		\$ -	\$ 279,503	\$ -	\$ 279,503
	Permitting and Additional Costs									
9.11	Physical Security	-	LS		-		\$ -	\$ -	\$ -	\$ -
9.12	Environmental Licensing & Permitting Costs & related legal cost	1.00	LS		74,534.23		\$ -	\$ 74,534	\$ -	\$ 74,534
9.13	Environmental-special studies/investigation	-	LS		-		\$ -	\$ -	\$ -	\$ -
9.14	Warranties / LOC's	1.00	LS		22,360.27		\$ -	\$ 22,360	\$ -	\$ 22,360
9.15	Laydown Lease	-	LS		-		\$ -	\$ -	\$ -	\$ -
9.16	Real Estate ( Acquisition)	-	LS			704,727.00	\$ -	\$ -	\$ -	\$ -
9.17	Legal Fees (Real estate)	-	LS		-	21,141.81	\$ -	\$ -	\$ -	\$ -
9.18	Insurance	-	LS		-	-	\$ -	\$ -	\$ -	\$ -
9.19	Bonds	1	LS		-	\$ 260,000	\$ -	\$ -	\$ 260,000	\$ 260,000
9.20	Sales Tax on Materials	8.80%	LS	6,312,235.86			\$ 555,477	\$ -	\$ -	\$ 555,477
9.21	Fees for permits, including roadway, railroad, building or other local permits	1.00	LS		7,453.42		\$ -	\$ 7,453	\$ -	\$ 7,453
TOTAL - MOB/DEMOB, ENGINEERING, PERMITTING, T&C, PM & INDIRECTS:							\$ 630,011	\$ 1,483,167	\$ 280,758	\$ 2,393,936





Item	Item Description	Estimated Quantity	Unit of Measure	Material Supply Rate	Labor Supply Rate	Const. Equipment Rate	Material Supply Cost	Labor Supply Cost	Const. Equipment Cost	TOTAL COST
1.22	Concrete Retaining Wall- Soil excavation	99,073	CY		9.00	6.00	\$ -	\$ 891,661	\$ 594,440	\$ 1,486,101
1.23	Concrete Retaining Wall- Rock excavation	396,294	CY		120.00	180.00	\$ -	\$ 47,555,232	\$ 71,332,848	\$ 118,888,080
1.24	Concrete Retaining Wall-Rock excavation-Hauling and disposal	267,498	CY		21.00	9.00	\$ -	\$ 5,617,461.78	\$ 2,407,483.62	\$ 8,024,945
1.25	Concrete Retaining Wall- Backfill & compaction	668,745	CY	10.00	30.00	20.00	\$ 6,687,455	\$ 20,062,364	\$ 13,374,909	\$ 40,124,727
1.26	Concrete Retaining Walll- Foundaiton and Wall	68,967	CY	325.00	195.00	130.00	\$ 22,414,275	\$ 13,448,565	\$ 8,965,710	\$ 44,828,550
TOTAL - SITE PREP/ GRADING/ FENCING / CIVIL							\$ 29,886,197	\$ 124,478,741	\$ 142,056,673	\$ 296,421,611
2. SUBSTATION FOUNDATIONS										
2.1	345kV, Lightning mast	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.2	345kV, A Frame 70'	880	CY	703.89	804.44	502.78	\$ 619,306	\$ 707,778	\$ 442,362	\$ 1,769,446
2.3	345kV, Bus support-3 Ph	111	CY	703.89	804.44	502.78	\$ 78,047	\$ 89,196	\$ 55,748	\$ 222,991
2.4	345kV, Bus support-3 Ph, low	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.5	345kV, Bus support-1 Ph	48	CY	703.89	804.44	502.78	\$ 33,449	\$ 38,227	\$ 23,892	\$ 95,567
2.6	345kV, GIS air terminal	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.7	345kV, GIS support-1 Ph	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.8	345kV, GIS support-3 Ph	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.9	345kV, GIS Cable sealing end	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.10	345kV, Cable sealing end	32	CY	703.89	804.44	502.78	\$ 22,595	\$ 25,823	\$ 16,139	\$ 64,556
2.11	345kV, CCVT	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.12	345kV, Disconnect Switch	253	CY	703.89	804.44	502.78	\$ 178,393	\$ 203,877	\$ 127,423	\$ 509,693
2.13	345/138KV, Power Transformer with oil containment	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.14	345kV, Shunt Reactor with oil containment-275MVAR	350	CY	703.89	804.44	502.78	\$ 246,360	\$ 281,554	\$ 175,971	\$ 703,885
2.15	345kV, Shunt Reactor with oil containment-225MVAR	305	CY	703.89	804.44	502.78	\$ 214,685	\$ 245,354	\$ 153,346	\$ 613,386
2.16	345kV, Phase Angle Regulator with oil containment	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.17	345kV, Circuit Breaker	160	CY	703.89	804.44	502.78	\$ 112,622	\$ 128,710	\$ 80,444	\$ 321,776
2.18	345kV, Circuit Breaker (GIS), outdoor rated	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.19	345Kv, Control Enclosure-BLDG with generator pad	325	CY	703.89	804.44	502.78	\$ 228,763	\$ 261,443	\$ 163,402	\$ 653,608
2.20	345kV, Surge arrester	48	CY	703.89	804.44	502.78	\$ 33,892	\$ 38,734	\$ 24,209	\$ 96,834
2.21	138kV, Phase Angle Regulator with oil containment	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.22	138kV, Shunt Reactor with oil containment-80MVAR	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.23	138kV, Circuit Breaker, AIS breaker	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.24	138kV, Bus support-3 Ph, low	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.25	138kV, Bus support-1 Ph, low	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.26	138kV, Disconnect Switch	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.27	138kV, Cable sealing end	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.28	138kV, Surge arrester	-	CY	-	-	-	\$ -	\$ -	\$ -	\$ -
2.29	138kV, CCVT	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.30	138kV, A Frame 50'	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.31	Firewall Foundation	143	CY	703.89	804.44	502.78	\$ 100,346	\$ 114,681	\$ 71,676	\$ 286,702
2.32	Precast Firewall for transformer, PARs, reactors	2,100	SF	25.00	15.00	10.00	\$ 52,500	\$ 31,500	\$ 21,000	\$ 105,000
2.33	Precast Concrete Piles-12"X80'	-	EA	18,000.00	3,200.00	2,800.00	\$ -	\$ -	\$ -	\$ -
2.34	Local Control Cabinet foundation	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.35	138kV, GIS Enclosure-BLDG & control room	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
TOTAL - 345KV FOUNDATION							\$ 1,920,956	\$ 2,166,878	\$ 1,355,611	\$ 5,443,445
3. SUBSTATION STRUCTURES										
3.1	345kV, Lightning mast	0	EA				\$ -	\$ -	\$ -	\$ -
3.2	345kV, A Frame 70'	6	EA	48,100.00	28,860.00	19,240.00	\$ 288,600	\$ 173,160	\$ 115,440	\$ 577,200
3.3	345kV, Bus support-3 Ph	7	EA	8,346.00	5,758.74	3,839.16	\$ 58,422	\$ 40,311	\$ 26,874	\$ 125,607
3.4	345kV, Bus support-3 Ph, low	0	EA	8,346.00	5,758.74	3,839.16	\$ -	\$ -	\$ -	\$ -
3.5	345kV, Bus support-1 Ph	6	EA	4,810.00	2,886.00	1,924.00	\$ 28,860	\$ 17,316	\$ 11,544	\$ 57,720
3.6	345kV, GIS air terminal	0	EA	8,346.00	5,758.74	3,839.16	\$ -	\$ -	\$ -	\$ -
3.7	345kV, GIS support-1 Ph	0	EA	8,346.00	5,758.74	3,839.16	\$ -	\$ -	\$ -	\$ -
3.8	345kV, GIS support-3 Ph	0	EA	4,810.00	2,886.00	1,924.00	\$ -	\$ -	\$ -	\$ -
3.9	345kV, GIS Cable sealing end	0	EA	8,346.00	5,758.74	3,839.16	\$ -	\$ -	\$ -	\$ -
3.10	345kV, Cable sealing end	3	EA	8,346.00	5,758.74	3,839.16	\$ 25,038	\$ 17,276	\$ 11,517	\$ 53,832
3.11	345kV, CCVT	0	EA	4,810.00	2,886.00	1,924.00	\$ -	\$ -	\$ -	\$ -
3.12	345kV, Disconnect Switch	16	EA	19,240.00	11,544.00	7,696.00	\$ 307,840	\$ 184,704	\$ 123,136	\$ 615,680
3.13	345kV, Surge arrester	9	EA	4,810.00	2,886.00	1,924.00	\$ 43,290	\$ 25,974	\$ 17,316	\$ 86,580
3.14	138kV, Bus support-3 Ph, low	0	EA	4,173.00	2,879.76	1,919.84	\$ -	\$ -	\$ -	\$ -
3.15	138kV, Bus support-1 Ph, low	0	EA	2,782.00	1,919.84	1,279.89	\$ -	\$ -	\$ -	\$ -

Item	Item Description	Estimated Quantity	Unit of Measure	Material Supply Rate	Labor Supply Rate	Const. Equipment Rate	Material Supply Cost	Labor Supply Cost	Const. Equipment Cost	TOTAL COST
3.16	138kV, Disconnect Switch	0	EA				\$ -	\$ -	\$ -	\$ -
3.17	138kV, Cable sealing end	0	EA	4,810.00	2,886.00	1,924.00	\$ -	\$ -	\$ -	\$ -
3.18	138kV, Surge arrester	0	EA	4,810.00	2,886.00	1,924.00	\$ -	\$ -	\$ -	\$ -
3.19	138kV, CCVT	0	EA	3,206.67	1,924.00	1,282.67	\$ -	\$ -	\$ -	\$ -
3.20	138kV, A Frame 50'	0	EA	33,000.00	19,800.00	13,200.00	\$ -	\$ -	\$ -	\$ -
3.21	AL. Bus Tubing, 5" SCH 80	1,590	LF	25.00	184.94	123.29	\$ 39,750	\$ 294,051	\$ 196,034	\$ 529,836
3.22	AL. Bus fittings	1	LS	47,700.00	47,700.00	23,850.00	\$ 47,700	\$ 47,700	\$ 23,850	\$ 119,250
3.23	Steel grating and support beams-transformer moat	86,560	LB	2.73	1.17	0.50	\$ 236,466	\$ 101,189	\$ 43,367	\$ 381,021
TOTAL - SUBSTATION STRUCTURES & GAS-INSULATED CONDUCTOR							\$ 1,075,966	\$ 901,681	\$ 569,078	\$ 2,546,726
4. MAJOR EQUIPMENT										
4.1	345kV, GIS air terminal	0	EA				\$ -	\$ -	\$ -	\$ -
4.2	345kV, GIS Cable sealing end	0	EA				\$ -	\$ -	\$ -	\$ -
4.3	345kV, Cable sealing end	9	EA	27,144.00	5,460.00	2,340.00	\$ 244,296	\$ 49,140	\$ 21,060	\$ 314,496
4.4	345kV, CCVT	0	EA		15,941.99	6,832.28	\$ -	\$ -	\$ -	\$ -
4.5	345kV, Disconnect Switch	16	EA	57,720.00	34,632.00	23,088.00	\$ 923,520	\$ 554,112	\$ 369,408	\$ 1,847,040
4.6	345/138KV, Power Transformer with oil containment	0	EA		3,520.00	880.00	\$ -	\$ -	\$ -	\$ -
4.7	Transport & Testing- Transformer	0	EA		15,400.00	6,600.00	\$ -	\$ -	\$ -	\$ -
4.8	345kV, Shunt Reactor with oil containment-275MVAR	1	EA	3,332,487.50	3,520.00	880.00	\$ 3,332,488	\$ 3,520	\$ 880	\$ 3,336,888
4.9	345kV, Shunt Reactor with oil containment-225MVAR	1	EA	3,026,425.00	3,520.00	880.00	\$ 3,026,425	\$ 3,520	\$ 880	\$ 3,030,825
4.10	Transport & Testing- Shunt Reactor	2	EA		352,900.00	231,600.00	\$ -	\$ 705,800	\$ 463,200	\$ 1,169,000
4.11	345kV, Phase Angle Regulator with oil containment	0	EA		3,520.00	880.00	\$ -	\$ -	\$ -	\$ -
4.12	345kV, Gas Insulated Switchgear, BAAH Arrangement	0	BKR	641,250.00	384,750.00	256,500.00	\$ -	\$ -	\$ -	\$ -
4.13	345kV, Circuit Breaker	8	EA	350,000.00	57,239.00	24,531.00	\$ 2,800,000	\$ 457,912	\$ 196,248	\$ 3,454,160
4.14	345kV, Circuit Breaker (GIS), outdoor rated	0	EA	1,194,419.50	716,651.70	477,767.80	\$ -	\$ -	\$ -	\$ -
4.15	345kV, Circuit Breaker (GIS), outdoor rated-Line surge Arrester ( 3phase)	0	EA				\$ -	\$ -	\$ -	\$ -
4.16	345kV, surge Arrester	9	EA	8,450.00	5,460.00	2,340.00	\$ 76,050	\$ 49,140	\$ 21,060	\$ 146,250
4.17	138kV, Phase Angle Regulator with oil containment	0	EA		3,520.00	880.00	\$ -	\$ -	\$ -	\$ -
4.18	Transport & Testing- Phase Angle Regulating Transformer, 138kV	0	EA		15,400.00	6,600.00	\$ -	\$ -	\$ -	\$ -
4.19	Transport & Testing- Transformer	0	EA		15,400.00	6,600.00	\$ -	\$ -	\$ -	\$ -
4.20	138kV, Shunt Reactor with oil containment-80MVAR	0	EA		3,520.00	880.00	\$ -	\$ -	\$ -	\$ -
4.21	Transport & Testing- Shunt Reactor	0	EA		15,400.00	6,600.00	\$ -	\$ -	\$ -	\$ -
4.22	138kV, Gas Insulated Switchgear, BAAH Arrangement	0	BKR		205,800.00	4,200.00	\$ -	\$ -	\$ -	\$ -
4.23	138kV, Circuit Breaker, AIS breaker	0	EA		13,559.00	5,811.00	\$ -	\$ -	\$ -	\$ -
4.24	138kV, Disconnect Switch	0	EA	37,700.00	11,875.50	5,089.50	\$ -	\$ -	\$ -	\$ -
4.25	138kV, Cable sealing end	0	EA	11,600.00	2,340.00	2,340.00	\$ -	\$ -	\$ -	\$ -
4.26	138kV, CCVT	0	EA		7,970.08	3,415.75	\$ -	\$ -	\$ -	\$ -
4.27	138kV, Surge arrester	0	EA		4,200.00	1,800.00	\$ -	\$ -	\$ -	\$ -
4.28	Station service transformers- 120/208v-250VA	0	EA		45,500.00	19,500.00	\$ -	\$ -	\$ -	\$ -
4.29	345kV Gas-Insulated Bus Conductor	0	LF	550.00	275.00	82.50	\$ -	\$ -	\$ -	\$ -
4.30	345kV Gas-Insulated Bus Conductor-elbow	0	EA	2,500.00	1,250.00	375.00	\$ -	\$ -	\$ -	\$ -
TOTAL - MAJOR EQUIPMENT							\$ 10,402,779	\$ 1,823,144	\$ 1,072,736	\$ 13,298,659
5. LOW VOLTAGE & CONTROL CABLE										
5.1	Control Cables	43,800	LF	5.30	1.43	0.29	\$ 232,031	\$ 62,744	\$ 12,549	\$ 307,323
5.2			LF		-	-	\$ -	\$ -	\$ -	\$ -
TOTAL - LOW VOLTAGE & CONTROL CABLE							\$ 232,031	\$ 62,744	\$ 12,549	\$ 307,323
6. CONDUIT & CABLE TRENCH										
6.1	Conduit, PVC, 6", SCH 40		LF	20.70	13.28	6.64	\$ -	\$ -	\$ -	\$ -
6.2	Conduit, PVC, 4", SCH 40	8,100	LF	11.15	10.80	5.40	\$ 90,315	\$ 87,480	\$ 43,740	\$ 221,535
6.3	Conduit, PVC, 3", SCH 40		LF	8.10	10.80	5.40	\$ -	\$ -	\$ -	\$ -
6.4	Conduit, PVC, 2", SCH 40		LF	3.95	10.80	5.40	\$ -	\$ -	\$ -	\$ -
6.5	Conduit, PVC, 1", SCH 40		LF	1.90	10.80	5.40	\$ -	\$ -	\$ -	\$ -
6.6	Cable Trench	2,018	LF	266.50	53.04	13.26	\$ 537,664	\$ 107,008	\$ 26,752	\$ 671,424
6.7							\$ -	\$ -	\$ -	\$ -
6.8	138kV UG- Conduit	0	LF	266.73	202.15	100.00				\$ -
6.9	138kV UG- Cable		LF	145.00	87.00	58.00				\$ -
6.10	138kV UG- Termination	0	EA	27,805.00	9,846.48	2,813.28				\$ -
6.11	345kV UG- Conduit	466	LF	266.73	202.15	100.00				\$ -
6.12	345kV UG- Cable	1,398	LF	167.00	100.20	66.80				\$ -
6.13	345kV UG- Termination	6	EA	27,805.00	9,846.48	2,813.28				\$ -
6.14	Fiber Optic Cable	466	LF	7.40	3.33	2.22				\$ -
6.15	Ground Continuity Conductor	466	LF	13.04	7.53	5.02				\$ -
TOTAL - CONDUIT & CABLE TRENCH							\$ 627,979	\$ 194,488	\$ 70,492	\$ 892,959
7. GROUND GRID										
7.1	Cable, 4/0 AWG Bare Copper, 7 Strand Ground Conductor	17,277	LF	2.09	3.42	1.46	\$ 36,126	\$ 59,006	\$ 25,288	\$ 120,421

Item	Item Description	Estimated Quantity	Unit of Measure	Material Supply Rate	Labor Supply Rate	Const. Equipment Rate	Material Supply Cost	Labor Supply Cost	Const. Equipment Cost	TOTAL COST
7.2	Caweld, DSA, 4/0 , T, CROSS	462	EA	165.00	75.00		\$ 76,230	\$ 34,650	\$ -	\$ 110,880
7.3	Ground Rod, 3/4" x 15'	410	EA	135.00	67.50	7.50	\$ 55,350	\$ 27,675	\$ 3,075	\$ 86,100
TOTAL - GROUND GRID							\$ 167,706	\$ 121,331	\$ 28,363	\$ 317,401
8. CONTROL ENCLOSURE										
8.1	345kv GIS Bldg	1	EA	542,947.99	380,063.60	162,884.40	\$ 542,948	\$ 380,064	\$ 162,884	\$ 1,085,896
8.2	138kv GIS/Control Bldg	0	EA	1,145,280.92	801,696.65	343,584.28	\$ -	\$ -	\$ -	\$ -
8.3	Primary Line Relays (87L): SEL-411L	2	EA	21,328.12	17,062.49	4,265.62	\$ 42,656	\$ 34,125	\$ 8,531	\$ 85,312
8.4	Backup Line Relays (87L): GE L90	2	EA	21,328.12	17,062.49	4,265.62	\$ 42,656	\$ 34,125	\$ 8,531	\$ 85,312
8.5	Primary Bay Control: SEL-451	2	EA	21,328.12	17,062.49	4,265.62	\$ 42,656	\$ 34,125	\$ 8,531	\$ 85,312
8.6	Backup Bay Control: SEL-451	2	EA	21,328.12	17,062.49	4,265.62	\$ 42,656	\$ 34,125	\$ 8,531	\$ 85,312
8.7	Primary Transformer/Reactor/PAR Differential Relays: SEL-487E	2	EA	21,328.12	17,062.49	4,265.62	\$ 42,656	\$ 34,125	\$ 8,531	\$ 85,312
8.8	Backup Transformer/Reactor/PAR Differential Relays: GE T60	2	EA	21,328.12	17,062.49	4,265.62	\$ 42,656	\$ 34,125	\$ 8,531	\$ 85,312
8.9	Primary Bus Differential Relays: SEL-487B	6	EA	21,328.12	17,062.49	4,265.62	\$ 127,969	\$ 102,375	\$ 25,594	\$ 255,937
8.10	Backup Bus Differential Relays: GE B90	6	EA	21,328.12	17,062.49	4,265.62	\$ 127,969	\$ 102,375	\$ 25,594	\$ 255,937
8.14	125VDC Battery System	1	LS	25,000.00	22,750.00	9,750.00	\$ 25,000	\$ 22,750	\$ 9,750	\$ 57,500
8.15	Control house AC Panel	1	EA	65,000.00	91,000.00	39,000.00	\$ 65,000	\$ 91,000	\$ 39,000	\$ 195,000
8.16	Control House DC Panel	1	EA	65,000.00	91,000.00	39,000.00	\$ 65,000	\$ 91,000	\$ 39,000	\$ 195,000
8.17	Generator	1	EA	130,000.00	72,800.00	31,200.00	\$ 130,000	\$ 72,800	\$ 31,200	\$ 234,000
TOTAL - CONTROL ENCLOSURE							\$ 1,339,823	\$ 1,067,113	\$ 384,209	\$ 2,791,146
11.Sprain Brook 345kV Substation Expansion							\$ 45,653,436	\$ 130,816,120	\$ 145,549,713	\$ 322,019,268
9. MOB/DEMOB, ENGINEERING, PERMITTING, T&C, PM & INDIRECTS										
	Contractor Mobilization / Demobilization									
9.1	Mob / Demob	1.0	LS		9,672,804.15	4,145,487.49	\$ -	\$ 9,672,804	\$ 4,145,487	\$ 13,818,292
	Project Management, Material Handling & Amenities									
9.2	Preconstruction Supervision (Engineering, Permitting, Procurement)	1	LS		3,220,192.68		\$ -	\$ 3,220,193	\$ -	\$ 3,220,193
9.3	Project Management & Staffing (includes PM, Field Engineers / Supervision, Scheduler and Cost Manager, SHEQ Staff, and Admin Staff)	1	LS		12,880,770.74		\$ -	\$ 12,880,771	\$ -	\$ 12,880,771
9.4	Utility PM and Project Oversight	1	LS		3,220,192.68		\$ -	\$ 3,220,193	\$ -	\$ 3,220,193
9.5	Site Accommodation, Facilities, Storage	1	LS	3,220,192.68			\$ 3,220,193	\$ -	\$ -	\$ 3,220,193
	Engineering									
9.6	Design Engineering	1.00	LS		25,761,541.47		\$ -	\$ 25,761,541	\$ -	\$ 25,761,541
9.7	LiDAR /GPR	-	LS				\$ -	\$ -	\$ -	\$ -
9.8	Geotech	5.00	EA		2,730.00	1,820.00	\$ -	\$ 13,650	\$ 9,100	\$ 22,750
9.9	Surveying/Staking	1.00	Site		2,254,134.88		\$ -	\$ 2,254,135	\$ -	\$ 2,254,135
	Testing & Commissioning									
9.10	Testing & Commissioning of SS and Equipment	1.00	LS		12,075,722.57		\$ -	\$ 12,075,723	\$ -	\$ 12,075,723
	Permitting and Additional Costs									
9.11	Physical Security	1.00	LS		6,546.96		\$ -	\$ 6,547	\$ -	\$ 6,547
9.12	Environmental Licensing & Permitting Costs & related legal cost	1.00	LS		3,220,192.68		\$ -	\$ 3,220,193	\$ -	\$ 3,220,193
9.13	Environmental-special studies/investigation	-	LS		-		\$ -	\$ -	\$ -	\$ -
9.14	Warranties / LOC's	1.00	LS		966,057.81		\$ -	\$ 966,058	\$ -	\$ 966,058
9.15	Laydown Lease	-	LS				\$ -	\$ -	\$ -	\$ -
9.16	Real Estate ( Acquisition)	1.00	LS		-	2,124,464.00	\$ -	\$ -	\$ 2,124,464	\$ 2,124,464
9.17	Legal Fees (Real estate)	1.00	LS		-	63,733.92	\$ -	\$ -	\$ 63,734	\$ 63,734
9.18	Insurance	-	LS		-	-	\$ -	\$ -	\$ -	\$ -
9.19	Bonds	1	LS		-	\$ 11,920,000	\$ -	\$ -	\$ 11,920,000	\$ 11,920,000
9.20	Sales Tax on Materials	8.80%	LS	45,653,435.63			\$ 4,017,502	\$ -	\$ -	\$ 4,017,502
9.21	Fees for permits, including roadway, railroad, building or other local permits	1.00	LS		322,019.27		\$ -	\$ 322,019	\$ -	\$ 322,019
TOTAL - MOB/DEMOB, ENGINEERING, PERMITTING, T&C, PM & INDIRECTS:							\$ 7,237,695	\$ 73,613,826	\$ 18,262,785	\$ 99,114,306

NEXTera Energy- TO36 Core 1

12. Existing Ruland Road 138 kV Substation Upgrade

Total:     \$            2,030,035

NEXTera Energy- TO36 Core 1				
	Material Supply	Labor Supply	Equip Supply	Total
12. Existing Ruland Road 138 kV Substation Upgrade				
1. SITE PREP/ GRADING/ FENCING / CIVIL	\$ -	\$ -	\$ -	\$ -
2. SUBSTATION FOUNDATIONS	\$ 3,128	\$ 3,575	\$ 2,235	\$ 8,938.22
3. SUBSTATION STRUCTURES	\$ -	\$ -	\$ -	\$ -
4. MAJOR EQUIPTMENT	\$ 920,000	\$ 13,559	\$ 5,811	\$ 939,370.00
5. LOW VOLTAGE & CONTROL CABLE	\$ 20,660	\$ 5,587	\$ 1,117	\$ 27,364.35
6. CONDUIT & CABLE TRENCH	\$ 6,690	\$ 6,480	\$ 3,240	\$ 16,410.00
7. GROUND GRID	\$ -	\$ -	\$ -	\$ -
8. CONTROL ENCLOSURE	\$ 42,656	\$ 34,125	\$ 8,531	\$ 85,312.46
9. MOB/DEMOB, ENGINEERING, PERMITTING, T&C, PM & INDIRECTS	\$ 98,170	\$ 216,812	\$ 41,264	\$ 356,245.74
SUBTOTAL (Costs):	\$ 1,091,305	\$ 280,138	\$ 62,198	\$ 1,433,641
CONTRACTOR MARK-UP (OH&P)	\$ 196,435	\$ 50,425	\$ 11,196	\$ 258,055
SUBTOTAL:	\$ 1,287,740	\$ 330,563	\$ 73,394	\$ 1,691,696
CONTINGENCY ON ENTIRE PROJECT	\$ 257,548	\$ 66,113	\$ 14,679	\$ 338,339
TOTAL:	\$ 1,545,287	\$ 396,675	\$ 88,072	\$ 2,030,035

Description of Work: Modification at exisitng 138kv Ruland station ( replace with two hybrid circuit breaker)										
Item	Item Description	Estimated Quantity	Unit of Measure	Material Supply Rate	Labor Supply Rate	Const. Equipment Rate	Material Supply Cost	Labor Supply Cost	Const. Equipment Cost	TOTAL COST
12. Existing Ruland Road 138 kV Substation Upgrade										
1. SITE PREP/ GRADING/ FENCING / CIVIL										
1.1	Site Clearing		ACRE	-	10,800.00	7,200.00	\$ -	\$ -	\$ -	\$ -
1.2	Demolition		ACRE	-	-	-	\$ -	\$ -	\$ -	\$ -
1.3	New Access Road - 20'		SY	4.85	7.20	4.80	\$ -	\$ -	\$ -	\$ -
1.4	Strip and Dispose Top Soil		CY		24.50	10.50	\$ -	\$ -	\$ -	\$ -
1.5	Site Grading- Excavation for Substation Pad		CY		9.00	6.00	\$ -	\$ -	\$ -	\$ -
1.6	Site Grading- Excavation for Substation Pad-Rock excavation-Hauling and disposal		CY		21.00	9.00	\$ -	\$ -	\$ -	\$ -
1.7	Site Grading- Fill for Substation Pad (site borrow, compacted in place)		CY		2.40	1.60	\$ -	\$ -	\$ -	\$ -
1.8	Site Grading -Fill for Substation Pad (import, compacted in place)		CY	25.00	2.40	1.60	\$ -	\$ -	\$ -	\$ -
1.9	Blasting		EA				\$ -	\$ -	\$ -	\$ -
1.10	Install substation 8" pad base		SY	11.00	6.00	4.00	\$ -	\$ -	\$ -	\$ -
1.11	Site Surfacing - Aggregate 6" Thick		SY	16.50	4.50	3.00	\$ -	\$ -	\$ -	\$ -
1.12	7' Station Fence w/ Barbed Wire & Grounding		LF	13.85	13.85	6.92	\$ -	\$ -	\$ -	\$ -
1.13	20' Slide Gate & Grounding		EA	8,100.00	3,245.00	1,305.00	\$ -	\$ -	\$ -	\$ -
1.14	4' Pedestrian gate		EA	2,500.00	1,000.00	350.00	\$ -	\$ -	\$ -	\$ -
1.15	Storm drain-15" HDPE, INFILTRATION TRENCH, INLET and Hydrodynamic Separator		LS	446,976.00	115,200.00	76,104.00	\$ -	\$ -	\$ -	\$ -
1.16	Seeding		SF	1.50	1.50	1.00	\$ -	\$ -	\$ -	\$ -
1.17	Erosion Control-Silt fence install & remove		LF	2.41	3.16	0.72	\$ -	\$ -	\$ -	\$ -
1.18	Temporary fencing		LF	7.50	5.25	2.25	\$ -	\$ -	\$ -	\$ -
1.19	Substation entrance with asphalt		SY	19.50	26.00	19.50	\$ -	\$ -	\$ -	\$ -

Item	Item Description	Estimated Quantity	Unit of Measure	Material Supply Rate	Labor Supply Rate	Const. Equipment Rate	Material Supply Cost	Labor Supply Cost	Const. Equipment Cost	TOTAL COST
1.20	Concrete curb		LF	26.00	27.30	11.70	\$ -	\$ -	\$ -	\$ -
1.21	Retaining Wall		LF	156.00	117.00	117.00	\$ -	\$ -	\$ -	\$ -
TOTAL - SITE PREP/ GRADING/ FENCING / CIVIL							\$ -	\$ -	\$ -	\$ -
2. SUBSTATION FOUNDATIONS										
2.1	345kV, Lightning mast	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.2	345kV, A Frame 70'	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.3	345kV, Bus support-3 Ph	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.4	345kV, Bus support-3 Ph, low	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.5	345kV, Bus support-1 Ph	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.6	345kV, GIS air terminal	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.7	345kV, GIS support-1 Ph	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.8	345kV, GIS support-3 Ph	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.9	345kV, GIS Cable sealing end	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.10	345kV, Cable sealing end	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.11	345kV, CCVT	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.12	345kV, Disconnect Switch	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.13	345/138KV, Power Transformer with oil containment	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.14	345kV, Shunt Reactor with oil containment-275MVAR	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.15	345kV, Shunt Reactor with oil containment-100MVAR	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.16	345kV, Phase Angle Regulator with oil containment	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.17	345kV, Circuit Breaker	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.18	345kV, Circuit Breaker (GIS), outdoor rated	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.19	345Kv, Control Enclosure-BLDG with generator pad	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.20	345kV, Surge arrester	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.21	138kV, Phase Angle Regulator with oil containment	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.22	138kV, Circuit Breaker, Hybrid circuit breaker	4	CY	703.89	804.44	502.78	\$ 3,128	\$ 3,575	\$ 2,235	\$ 8,938
2.23	138kV, Bus support-3 Ph, low	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.24	138kV, Bus support-1 Ph, low	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.25	138kV, Disconnect Switch	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.26	138kV, Cable sealing end	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.27	138kV, Surge arrester	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.28	138kV, CCVT	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.29	138kV, A Frame 50'	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.30	Firewall Foundation	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.31	Precast Firewall for transformer, PARs, reactors	-	SF	25.00	15.00	10.00	\$ -	\$ -	\$ -	\$ -
2.32	Precast Concrete Piles-12"X80'	-	EA	18,000.00	3,200.00	2,800.00	\$ -	\$ -	\$ -	\$ -
2.33	Local Control Cabinet foundation	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.34	138kV, GIS Enclosure-BLDG & control room	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
TOTAL - 345KV FOUNDATION							\$ 3,128	\$ 3,575	\$ 2,235	\$ 8,938
3. SUBSTATION STRUCTURES										
3.1	345kV, Lightning mast	0	EA				\$ -	\$ -	\$ -	\$ -
3.2	345kV, A Frame 70'	0	EA	48,100.00	28,860.00	19,240.00	\$ -	\$ -	\$ -	\$ -
3.3	345kV, Bus support-3 Ph	0	EA	8,346.00	5,758.74	3,839.16	\$ -	\$ -	\$ -	\$ -
3.4	345kV, Bus support-3 Ph, low	0	EA	8,346.00	5,758.74	3,839.16	\$ -	\$ -	\$ -	\$ -
3.5	345kV, Bus support-1 Ph	0	EA	4,810.00	2,886.00	1,924.00	\$ -	\$ -	\$ -	\$ -
3.6	345kV, GIS air terminal	0	EA	8,346.00	5,758.74	3,839.16	\$ -	\$ -	\$ -	\$ -
3.7	345kV, GIS support-1 Ph	0	EA	8,346.00	5,758.74	3,839.16	\$ -	\$ -	\$ -	\$ -
3.8	345kV, GIS support-3 Ph	0	EA	4,810.00	2,886.00	1,924.00	\$ -	\$ -	\$ -	\$ -
3.9	345kV, GIS Cable sealing end	0	EA	8,346.00	5,758.74	3,839.16	\$ -	\$ -	\$ -	\$ -
3.10	345kV, Cable sealing end	0	EA	8,346.00	5,758.74	3,839.16	\$ -	\$ -	\$ -	\$ -
3.11	345kV, CCVT	0	EA	4,810.00	2,886.00	1,924.00	\$ -	\$ -	\$ -	\$ -
3.12	345kV, Disconnect Switch	0	EA	19,240.00	11,544.00	7,696.00	\$ -	\$ -	\$ -	\$ -
3.13	138kV, Bus support-3 Ph, low	0	EA	4,173.00	2,879.76	1,919.84	\$ -	\$ -	\$ -	\$ -
3.14	138kV, Bus support-1 Ph, low	0	EA	2,782.00	1,919.84	1,279.89	\$ -	\$ -	\$ -	\$ -
3.15	138kV, Disconnect Switch	0	EA				\$ -	\$ -	\$ -	
3.16	138kV, Cable sealing end	0	EA	4,810.00	2,886.00	1,924.00	\$ -	\$ -	\$ -	\$ -
3.17	138kV, Surge arrester	0	EA	4,810.00	2,886.00	1,924.00	\$ -	\$ -	\$ -	\$ -
3.17	138kV, CCVT	0	EA	3,206.67	1,924.00	1,282.67	\$ -	\$ -	\$ -	\$ -
3.18	138kV, A Frame 50'	0	EA	33,000.00	19,800.00	13,200.00	\$ -	\$ -	\$ -	\$ -
3.19	AL. Bus Tubing, 5" SCH 80		LF	25.00	184.94	123.29	\$ -	\$ -	\$ -	\$ -
3.20	AL. Bus fittings		LS	22,500.00	22,500.00	11,250.00	\$ -	\$ -	\$ -	\$ -
3.21	Steel grating and support beams-transformer moat	0	LB	2.73	1.17	0.50	\$ -	\$ -	\$ -	\$ -
TOTAL - SUBSTATION STRUCTURES & GAS-INSULATED CONDUCTOR							\$ -	\$ -	\$ -	\$ -



Item	Item Description	Estimated Quantity	Unit of Measure	Material Supply Rate	Labor Supply Rate	Const. Equipment Rate	Material Supply Cost	Labor Supply Cost	Const. Equipment Cost	TOTAL COST
<b>4. MAJOR EQUIPMENT</b>										
4.1	345kV, Cable sealing end	0	EA	17,400.00	5,460.00	2,340.00	\$ -	\$ -	\$ -	\$ -
4.2	345kV, CCVT	0	EA	4,810.00	2,886.00	1,924.00	\$ -	\$ -	\$ -	\$ -
4.3	345kV, Disconnect Switch	0	EA	57,720.00	34,632.00	23,088.00	\$ -	\$ -	\$ -	\$ -
4.4	345/138KV, Power Transformer with oil containment	0	EA	5,020,000.00	3,520.00	880.00	\$ -	\$ -	\$ -	\$ -
4.5	Transport & Testing- Transformer	0	EA		777,400.00	514,600.00	\$ -	\$ -	\$ -	\$ -
4.6	345kV, Shunt Reactor with oil containment-275MVAR	0	EA	3,332,488.00	3,520.00	880.00	\$ -	\$ -	\$ -	\$ -
4.7	345kV, Shunt Reactor with oil containment-100MVAR	0	EA		3,520.00	880.00	\$ -	\$ -	\$ -	\$ -
4.8	Transport & Testing- Shunt Reactor	0	EA		426,650.00	182,850.00	\$ -	\$ -	\$ -	\$ -
4.9	345kV, Phase Angle Regulator with oil containment	0	EA		3,520.00	880.00	\$ -	\$ -	\$ -	\$ -
4.10	345kV, Circuit Breaker	0	EA	350,000.00	57,239.00	24,531.00	\$ -	\$ -	\$ -	\$ -
4.11	345kV, Circuit Breaker (GIS), outdoor rated	0	EA				\$ -	\$ -	\$ -	\$ -
4.12	345kV, Circuit Breaker (GIS), outdoor rated-Line surge Arrester ( 3phase)	0	EA				\$ -	\$ -	\$ -	\$ -
4.13	345kV, surge Arrester	0	EA	6,669.00	5,460.00	2,340.00	\$ -	\$ -	\$ -	\$ -
4.14	138kV, Phase Angle Regulator with oil containment	0	EA		3,520.00	880.00	\$ -	\$ -	\$ -	\$ -
4.15	Transport & Testing- Phase Angle Regulating Transformer, 138kV	0	EA		15,400.00	6,600.00	\$ -	\$ -	\$ -	\$ -
4.16	138kV, Gas Insulated Switchgear, BAAH Arrangement	0	BKR	478,750.00	287,250.00	191,500.00	\$ -	\$ -	\$ -	\$ -
4.17	138kV, Circuit Breaker, Hybrid circuit breaker	1	EA	920,000.00	13,559.00	5,811.00	\$ 920,000	\$ 13,559	\$ 5,811	\$ 939,370
4.18	138kV, Disconnect Switch	0	EA		3,958.50	1,696.50	\$ -	\$ -	\$ -	\$ -
4.19	138kV, Cable sealing end	0	EA	11,600.00	5,460.00	2,340.00	\$ -	\$ -	\$ -	\$ -
4.20	138kV, CCVT	0	EA		7,970.08	3,415.75	\$ -	\$ -	\$ -	\$ -
4.21	138kV, Surge arrester	0	EA	4,446.00	4,200.00	1,800.00	\$ -	\$ -	\$ -	\$ -
4.22	Station service transformers- 120/208v-250VA	0	EA	260,000.00	45,500.00	19,500.00	\$ -	\$ -	\$ -	\$ -
4.23	345kV Gas-Insulated Bus Conductor	0	LF	550.00	275.00	82.50	\$ -	\$ -	\$ -	\$ -
4.24	345kV Gas-Insulated Bus Conductor-elbow	0	EA	2,500.00	1,250.00	375.00	\$ -	\$ -	\$ -	\$ -
4.25	Transport & Testing- GIL	0	LS		-	-	\$ -	\$ -	\$ -	\$ -
							\$ -	\$ -	\$ -	\$ -
<b>TOTAL - MAJOR EQUIPMENT</b>							\$ 920,000	\$ 13,559	\$ 5,811	\$ 939,370
<b>5. LOW VOLTAGE &amp; CONTROL CABLE</b>										
5.1	Control Cables	3,900	LF	5.30	1.43	0.29	\$ 20,660	\$ 5,587	\$ 1,117	\$ 27,364
5.2			LF		-	-	\$ -	\$ -	\$ -	\$ -
<b>TOTAL - LOW VOLTAGE &amp; CONTROL CABLE</b>							\$ 20,660	\$ 5,587	\$ 1,117	\$ 27,364
<b>6. CONDUIT &amp; CABLE TRENCH</b>										
6.1	Conduit, PVC, 6", SCH 40		LF	20.70	13.28	6.64	\$ -	\$ -	\$ -	\$ -
6.2	Conduit, PVC, 4", SCH 40	600	LF	11.15	10.80	5.40	\$ 6,690	\$ 6,480	\$ 3,240	\$ 16,410
6.3	Conduit, PVC, 3", SCH 40		LF	8.10	10.80	5.40	\$ -	\$ -	\$ -	\$ -
6.4	Conduit, PVC, 2", SCH 40		LF	3.95	10.80	5.40	\$ -	\$ -	\$ -	\$ -
6.5	Conduit, PVC, 1", SCH 40		LF	1.90	10.80	5.40	\$ -	\$ -	\$ -	\$ -
6.6	Cable Trench		LF	266.50	53.04	13.26	\$ -	\$ -	\$ -	\$ -
6.7										
6.8	138kV UG- Conduit		LF	266.73	202.15	100.00	\$ -	\$ -	\$ -	\$ -
6.9	138kV UG- Cable	0	LF	145.00	87.00	58.00	\$ -	\$ -	\$ -	\$ -
6.10	138kV UG- Termination		EA	27,805.00	9,846.48	2,813.28	\$ -	\$ -	\$ -	\$ -
6.13	Fiber Optic Cable	0	LF	7.40	3.33	2.22	\$ -	\$ -	\$ -	\$ -
6.14	Ground Continuity Conductor	0	LF	13.04	7.53	5.02	\$ -	\$ -	\$ -	\$ -
6.11							\$ -	\$ -	\$ -	\$ -
<b>TOTAL - CONDUIT &amp; CABLE TRENCH</b>							\$ 6,690	\$ 6,480	\$ 3,240	\$ 16,410
<b>7. GROUND GRID</b>										
7.1	Cable, 4/0 AWG Bare Copper, 7 Strand Ground Conductor	0	LF	2.09	3.42	1.46	\$ -	\$ -	\$ -	\$ -
7.2	Caweld, DSA, 4/0 , T, CROSS	0	EA	165.00	75.00		\$ -	\$ -	\$ -	\$ -
7.3	Ground Rod, 3/4" x 15'	0	EA	135.00	67.50	7.50	\$ -	\$ -	\$ -	\$ -
<b>TOTAL - GROUND GRID</b>							\$ -	\$ -	\$ -	\$ -
<b>8. CONTROL ENCLOSURE</b>										
8.1	345kv Control Bldg	0	EA	407,211.00	285,047.70	122,163.30	\$ -	\$ -	\$ -	\$ -
8.2	138kv GIS/Control Bldg	0	EA	1,145,280.92	801,696.65	343,584.28	\$ -	\$ -	\$ -	\$ -
8.3	Primary Line Relays (87L): SEL-411L	0	EA	21,328.12	17,062.49	4,265.62	\$ -	\$ -	\$ -	\$ -
8.4	Backup Line Relays (87L): GE L90	0	EA	21,328.12	17,062.49	4,265.62	\$ -	\$ -	\$ -	\$ -
8.5	Primary Bay Control: SEL-451	0	EA	21,328.12	17,062.49	4,265.62	\$ -	\$ -	\$ -	\$ -
8.6	Backup Bay Control: SEL-451	0	EA	21,328.12	17,062.49	4,265.62	\$ -	\$ -	\$ -	\$ -
8.7	Primary Transformer/Reactor/PAR Differential Relays: SEL-487E	0	EA	21,328.12	17,062.49	4,265.62	\$ -	\$ -	\$ -	\$ -
8.8	Backup Transformer/Reactor/PAR Differential Relays: GE T60	0	EA	21,328.12	17,062.49	4,265.62	\$ -	\$ -	\$ -	\$ -
8.9	Primary Bus Differential Relays: SEL-487B	0	EA	21,328.12	17,062.49	4,265.62	\$ -	\$ -	\$ -	\$ -
8.10	Backup Bus Differential Relays: GE B90	0	EA	21,328.12	17,062.49	4,265.62	\$ -	\$ -	\$ -	\$ -
8.11	RTU Panel A: SEL-2240 Axion, SEL-2730M ENET SW., SEL-2407 GPS, Modem, SEL-2523 Ann	0	EA	12,500.00	10,000.00	2,500.00	\$ -	\$ -	\$ -	\$ -
8.12	RTU Panel B: SEL-2730M Ethernet Switch, SEL-2407 GPS Clock, SEL-2523 Annunciator	0	EA	12,500.00	10,000.00	2,500.00	\$ -	\$ -	\$ -	\$ -
8.13	HMI Panel	0	EA	12,500.00	10,000.00	2,500.00	\$ -	\$ -	\$ -	\$ -
8.14	Primary Line Relays (87L): SEL-411L	1	EA	21,328.12	17,062.49	4,265.62	\$ 21,328	\$ 17,062	\$ 4,266	\$ 42,656

Item	Item Description	Estimated Quantity	Unit of Measure	Material Supply Rate	Labor Supply Rate	Const. Equipment Rate	Material Supply Cost	Labor Supply Cost	Const. Equipment Cost	TOTAL COST
8.15	Backup Line Relays (87L): GE L90	1	EA	21,328.12	17,062.49	4,265.62	\$ 21,328	\$ 17,062	\$ 4,266	\$ 42,656
8.16	Primary Bay Control: SEL-451	0	EA	21,328.12	17,062.49	4,265.62	\$ -	\$ -	\$ -	\$ -
8.17	Backup Bay Control: SEL-451	0	EA	21,328.12	17,062.49	4,265.62	\$ -	\$ -	\$ -	\$ -
8.18	Primary Bus Differential Relays: SEL-487B	0	EA	21,328.12	17,062.49	4,265.62	\$ -	\$ -	\$ -	\$ -
8.19	Backup Bus Differential Relays: GE B90	0	EA	21,328.12	17,062.49	4,265.62	\$ -	\$ -	\$ -	\$ -
8.20	125VDC Battery System	0	LS	25,000.00	22,750.00	9,750.00	\$ -	\$ -	\$ -	\$ -
8.21	Control house AC Panel	0	EA	65,000.00	91,000.00	39,000.00	\$ -	\$ -	\$ -	\$ -
8.22	Control House DC Panel	0	EA	65,000.00	91,000.00	39,000.00	\$ -	\$ -	\$ -	\$ -
8.23	Generator	0	EA	130,000.00	72,800.00	31,200.00	\$ -	\$ -	\$ -	\$ -
TOTAL - CONTROL ENCLOSURE							\$ 42,656	\$ 34,125	\$ 8,531	\$ 85,312
12. Existing Ruland Road 138 kV Substation Upgrade							\$ 993,135	\$ 63,326	\$ 20,934	\$ 1,077,395
9. MOB/DEMOB, ENGINEERING, PERMITTING, T&C, PM & INDIRECTS										
	Contractor Mobilization / Demobilization									
9.1	Mob / Demob	1.0	LS		2,949.11	1,263.90	\$ -	\$ 2,949	\$ 1,264	\$ 4,213
	Project Management, Material Handling & Amenities									
9.2	Preconstruction Supervision (Engineering, Permitting, Procurement)	1	LS		10,773.95		\$ -	\$ 10,774	\$ -	\$ 10,774
9.3	Project Management & Staffing (includes PM, Field Engineers / Supervision, Scheduler and Cost Manager, SHEQ Staff, and Admin Staff)	1	LS		43,095.80		\$ -	\$ 43,096	\$ -	\$ 43,096
9.4	Utility PM and Project Oversight	1	LS		10,773.95		\$ -	\$ 10,774	\$ -	\$ 10,774
9.5	Site Accommodation, Facilities, Storage	1	LS	10,773.95			\$ 10,774	\$ -	\$ -	\$ 10,774
	Engineering									
9.6	Design Engineering	1.00	LS		86,191.60		\$ -	\$ 86,192	\$ -	\$ 86,192
9.7	LIDAR /GPR	1.00	LS		-		\$ -	\$ -	\$ -	\$ -
9.8	Geotech	-	EA		2,730.00	1,820.00	\$ -	\$ -	\$ -	\$ -
9.9	Surveying/Staking	1.00	Site		7,541.77		\$ -	\$ 7,542	\$ -	\$ 7,542
	Testing & Commissioning									
9.10	Testing & Commissioning of SS and Equipment	1.00	LS		40,402.31		\$ -	\$ 40,402	\$ -	\$ 40,402
	Permitting and Additional Costs									
9.11	Physical Security	-	LS		6,546.96		\$ -	\$ -	\$ -	\$ -
9.12	Environmental Licensing & Permitting Costs & related legal cost	1.00	LS		10,773.95		\$ -	\$ 10,774	\$ -	\$ 10,774
9.13	Environmental-special studies/investigation	-	LS		-		\$ -	\$ -	\$ -	\$ -
9.14	Warranties / LOC's	1.00	LS		3,232.19		\$ -	\$ 3,232	\$ -	\$ 3,232
9.15	Laydown Lease	-	LS		-		\$ -	\$ -	\$ -	\$ -
9.16	Real Estate ( Acquisition)	-	LS		-	1,158,245.00	\$ -	\$ -	\$ -	\$ -
9.17	Legal Fees (Real estate)	-	LS		-	34,747.35	\$ -	\$ -	\$ -	\$ -
9.18	Insurance	-	LS		-	-	\$ -	\$ -	\$ -	\$ -
9.19	Bonds	1	LS		-	\$ 40,000	\$ -	\$ -	\$ 40,000	\$ 40,000
9.20	Sales Tax on Materials	8.80%	LS	993,134.86			\$ 87,396	\$ -	\$ -	\$ 87,396
9.21	Fees for permits, including roadway, railroad, building or other local permits	1.00	LS		1,077.40		\$ -	\$ 1,077	\$ -	\$ 1,077
TOTAL - MOB/DEMOB, ENGINEERING, PERMITTING, T&C, PM & INDIRECTS:							\$ 98,170	\$ 216,812	\$ 41,264	\$ 356,246

NEXtera Energy- TO36 Core 1

13.Exisitng East Garden City 138 kV Substation Upgrades

Total: \$ 28,298,464

NEXtera Energy- TO36 Core 1				
	Material Supply	Labor Supply	Equip Supply	Total
13.Exisitng East Garden City 138 kV Substation Upgrades				
1. SITE PREP/ GRADING/ FENCING / CIVIL	\$ -	\$ -	\$ -	\$ -
2. SUBSTATION FOUNDATIONS	\$ 249,640	\$ 285,303	\$ 178,314	\$ 713,257
3. SUBSTATION STRUCTURES	\$ 261,466	\$ 347,805	\$ 240,376	\$ 849,646
4. MAJOR EQUIPMENT	\$ 10,602,422	\$ 458,707	\$ 272,389	\$ 11,333,517
5. LOW VOLTAGE & CONTROL CABLE	\$ 25,428	\$ 6,876	\$ 1,375	\$ 33,679
6. CONDUIT & CABLE TRENCH	\$ 814,095	\$ 440,988	\$ 236,281	\$ 1,491,364
7. GROUND GRID	\$ 14,819	\$ 10,555	\$ 2,392	\$ 27,766
8. CONTROL ENCLOSURE	\$ 298,594	\$ 238,875	\$ 59,719	\$ 597,187
9. MOB/DEMOB, ENGINEERING, PERMITTING, T&C, PM & INDIRECTS	\$ 1,229,913	\$ 3,097,662	\$ 610,799	\$ 4,938,374
SUBTOTAL (Costs):	\$ 13,496,376	\$ 4,886,771	\$ 1,601,644	\$ 19,984,791
CONTRACTOR MARK-UP (OH&P)	\$ 2,429,348	\$ 879,619	\$ 288,296	\$ 3,597,262
SUBTOTAL:	\$ 15,925,724	\$ 5,766,390	\$ 1,889,940	\$ 23,582,053
CONTINGENCY ON ENTIRE PROJECT	\$ 3,185,145	\$ 1,153,278	\$ 377,988	\$ 4,716,411
TOTAL:	\$ 19,110,868	\$ 6,919,667	\$ 2,267,928	\$ 28,298,464

Description of Work: Modification at exisitng 138kv EGC station										
Item	Item Description	Estimated Quantity	Unit of Measure	Material Supply Rate	Labor Supply Rate	Const. Equipment Rate	Material Supply Cost	Labor Supply Cost	Const. Equipment Cost	TOTAL COST
13.Exisitng East Garden City 138 kV Substation Upgrades										
1. SITE PREP/ GRADING/ FENCING / CIVIL										
1.1	Site Clearing		ACRE	-	10,800.00	7,200.00	\$ -	\$ -	\$ -	\$ -
1.2	Demolition		LS	-	900,000.00	600,000.00	\$ -	\$ -	\$ -	\$ -
1.3	New Access Road - 20'		SY	4.85	7.20	4.80	\$ -	\$ -	\$ -	\$ -
1.4	Strip and Dispose Top Soil		CY		24.50	10.50	\$ -	\$ -	\$ -	\$ -
1.5	Site Grading- Excavation for Substation Pad		CY		9.00	6.00	\$ -	\$ -	\$ -	\$ -
1.6	Site Grading- Excavation for Substation Pad-Rock excavation-Hauling and disposal		CY		21.00	9.00	\$ -	\$ -	\$ -	\$ -
1.7	Site Grading- Fill for Substation Pad (site borrow, compacted in place)		CY		2.40	1.60	\$ -	\$ -	\$ -	\$ -
1.8	Site Grading -Fill for Substation Pad (import, compacted in place)		CY	25.00	2.40	1.60	\$ -	\$ -	\$ -	\$ -
1.9	Blasting		EA				\$ -	\$ -	\$ -	\$ -
1.10	Install substation 8" pad base		SY	11.00	6.00	4.00	\$ -	\$ -	\$ -	\$ -
1.11	Site Surfacing - Aggregate 6" Thick		SY	16.50	4.50	3.00	\$ -	\$ -	\$ -	\$ -
1.12	7' Station Fence w/ Barbed Wire & Grounding		LF	13.85	13.85	6.92	\$ -	\$ -	\$ -	\$ -
1.13	20' Slide Gate & Grounding		EA	8,100.00	3,245.00	1,305.00	\$ -	\$ -	\$ -	\$ -
1.14	4' Pedestrian gate		EA	2,500.00	1,000.00	350.00	\$ -	\$ -	\$ -	\$ -
1.15	Storm drain-15" HDPE, INFILTRATION TRENCH, INLET and Hydrodynamic Separator		LS	446,976.00	115,200.00	76,104.00	\$ -	\$ -	\$ -	\$ -
1.16	Seeding		SF	1.50	1.50	1.00	\$ -	\$ -	\$ -	\$ -
1.17	Erosion Control-Silt fence install & remove		LF	2.41	3.16	0.72	\$ -	\$ -	\$ -	\$ -
1.18	Temporary fencing		LF	7.50	5.25	2.25	\$ -	\$ -	\$ -	\$ -
1.19	Substation entrance with asphalt		SY	19.50	26.00	19.50	\$ -	\$ -	\$ -	\$ -
1.20	Concrete curb		LF	26.00	27.30	11.70	\$ -	\$ -	\$ -	\$ -
1.21	Retaining Wall		LF	156.00	117.00	117.00	\$ -	\$ -	\$ -	\$ -
TOTAL - SITE PREP/ GRADING/ FENCING / CIVIL							\$ -	\$ -	\$ -	\$ -

Item	Item Description	Estimated Quantity	Unit of Measure	Material Supply Rate	Labor Supply Rate	Const. Equipment Rate	Material Supply Cost	Labor Supply Cost	Const. Equipment Cost	TOTAL COST
<b>2. SUBSTATION FOUNDATIONS</b>										
2.1	345kV, Lightning mast	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.2	345kV, A Frame 70'	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.3	345kV, Bus support-3 Ph	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.4	345kV, Bus support-3 Ph, low	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.5	345kV, Bus support-1 Ph	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.6	345kV, GIS air terminal	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.7	345kV, GIS support-1 Ph	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.8	345kV, GIS support-3 Ph	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.9	345kV, GIS Cable sealing end	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.10	345kV, Cable sealing end	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.11	345kV, CCVT	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.12	345kV, Disconnect Switch	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.13	345/138KV, Power Transformer with oil containment	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.14	345kV, Shunt Reactor with oil containment-225MVAR	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.15	345kV, Shunt Reactor with oil containment-50MVAR	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.16	345kV, Shunt Reactor with oil containment-25MVAR	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.17	345kV, Phase Angle Regulator with oil containment	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.18	345kV, Circuit Breaker (PASS)	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.19	345kV, Circuit Breaker (GIS), outdoor rated	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.20	345Kv, GIS Enclosure-BLDG with generator pad	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.21	345kV, Surge arrester	-	CY	-	-	-	\$ -	\$ -	\$ -	\$ -
2.22	138kV, Phase Angle Regulator with oil containment	154	CY	703.89	804.44	502.78	\$ 108,398	\$ 123,884	\$ 77,427	\$ 309,709
2.23	138kV, Circuit Breaker, Hybrid circuit breaker	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.24	138kV, Bus support-3 Ph, low	43	CY	703.89	804.44	502.78	\$ 30,126	\$ 34,430	\$ 21,519	\$ 86,075
2.25	138kV, Bus support-1 Ph, low	61	CY	703.89	804.44	502.78	\$ 42,867	\$ 48,990	\$ 30,619	\$ 122,476
2.26	138kV, Disconnect Switch	73	CY	703.89	804.44	502.78	\$ 51,187	\$ 58,499	\$ 36,562	\$ 146,247
2.27	138kV, Cable sealing end	24	CY	703.89	804.44	502.78	\$ 17,062	\$ 19,500	\$ 12,187	\$ 48,749
2.28	138kV, CCVT	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.29	138kV, A Frame 50'	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.30	Firewall Foundation	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.31	Precast Firewall for transformer, PARs, reactors	25.00	SF	25.00	15.00	10.00	\$ -	\$ -	\$ -	\$ -
2.32	Precast Concrete Piles-12"X80'	-	EA	18,000.00	3,200.00	2,800.00	\$ -	\$ -	\$ -	\$ -
2.33	Local Control Cabinet foundation	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
2.34	138kV, GIS Enclosure-BLDG & control room	-	CY	703.89	804.44	502.78	\$ -	\$ -	\$ -	\$ -
<b>TOTAL - 345KV FOUNDATION</b>							\$ 249,640	\$ 285,303	\$ 178,314	\$ 713,257
<b>3. SUBSTATION STRUCTURES</b>										
3.1	345kV, Lightning mast	0	EA				\$ -	\$ -	\$ -	\$ -
3.2	345kV, A Frame 70'	0	EA	48,100.00	28,860.00	19,240.00	\$ -	\$ -	\$ -	\$ -
3.3	345kV, Bus support-3 Ph	0	EA	8,346.00	5,758.74	3,839.16	\$ -	\$ -	\$ -	\$ -
3.4	345kV, Bus support-3 Ph, low	0	EA	8,346.00	5,758.74	3,839.16	\$ -	\$ -	\$ -	\$ -
3.5	345kV, Bus support-1 Ph	0	EA	4,810.00	2,886.00	1,924.00	\$ -	\$ -	\$ -	\$ -
3.6	345kV, GIS air terminal	0	EA	8,346.00	5,758.74	3,839.16	\$ -	\$ -	\$ -	\$ -
3.7	345kV, GIS support-1 Ph	0	EA	8,346.00	5,758.74	3,839.16	\$ -	\$ -	\$ -	\$ -
3.8	345kV, GIS support-3 Ph	0	EA	4,810.00	2,886.00	1,924.00	\$ -	\$ -	\$ -	\$ -
3.9	345kV, GIS Cable sealing end	0	EA	8,346.00	5,758.74	3,839.16	\$ -	\$ -	\$ -	\$ -
3.10	345kV, Cable sealing end	0	EA	8,346.00	5,758.74	3,839.16	\$ -	\$ -	\$ -	\$ -
3.11	345kV, CCVT	0	EA	4,810.00	2,886.00	1,924.00	\$ -	\$ -	\$ -	\$ -
3.12	345kV, Disconnect Switch	0	EA	19,240.00	11,544.00	7,696.00	\$ -	\$ -	\$ -	\$ -
3.13	138kV, Bus support-3 Ph, low	4	EA	4,173.00	2,879.76	1,919.84	\$ 16,692	\$ 11,519	\$ 7,679	\$ 35,890
3.14	138kV, Bus support-1 Ph, low	15	EA	2,782.00	1,919.84	1,279.89	\$ 41,730	\$ 28,798	\$ 19,198	\$ 89,726
3.15	138kV, Disconnect Switch	3	EA	4,896.84	4,896.84	2,448.42	\$ 14,691	\$ 14,691	\$ 7,345	\$ 36,726
3.16	138kV, Cable sealing end	2	EA	4,810.00	2,886.00	1,924.00	\$ 9,620	\$ 5,772	\$ 3,848	\$ 19,240
3.17	138kV, CCVT	0	EA	3,206.67	1,924.00	1,282.67	\$ -	\$ -	\$ -	\$ -
3.18	138kV, A Frame 50'	0	EA	33,000.00	19,800.00	13,200.00	\$ -	\$ -	\$ -	\$ -
3.19	345kV Gas-Insulated Bus Conductor	0	LF	550.00	275.00	82.50	\$ -	\$ -	\$ -	\$ -
3.20	345kV Gas-Insulated Bus Conductor-elbow	0	EA	2,500.00	1,250.00	375.00	\$ -	\$ -	\$ -	\$ -
3.21	AL. Bus Tubing, 5" SCH 80	1,100	LF	25.00	184.94	123.29	\$ 27,500	\$ 203,432	\$ 135,621	\$ 366,553
3.22	AL. Bus fittings	1	LS	33,000.00	33,000.00	45,000.00	\$ 33,000	\$ 33,000	\$ 45,000	\$ 111,000
3.23	Steel grating and support beams-transformer moat	43,280	LB	2.73	1.17	0.50	\$ 118,233	\$ 50,594	\$ 21,683	\$ 190,511
<b>TOTAL - SUBSTATION STRUCTURES &amp; GAS-INSULATED CONDUCTOR</b>							\$ 261,466	\$ 347,805	\$ 240,376	\$ 849,646
<b>4. MAJOR EQUIPMENT</b>										
4.1	345kV, GIS air terminal	0	EA				\$ -	\$ -	\$ -	\$ -
4.2	345kV, GIS Cable sealing end	0	EA				\$ -	\$ -	\$ -	\$ -
4.3	345kV, Cable sealing end	0	EA	17,400.00	5,460.00	2,340.00	\$ -	\$ -	\$ -	\$ -

Item	Item Description	Estimated Quantity	Unit of Measure	Material Supply Rate	Labor Supply Rate	Const. Equipment Rate	Material Supply Cost	Labor Supply Cost	Const. Equipment Cost	TOTAL COST
4.4	345kV, CCVT	0	EA		15,941.99	6,832.28	\$ -	\$ -	\$ -	\$ -
4.5	345kV, Disconnect Switch	0	EA	57,720.00	34,632.00	23,088.00	\$ -	\$ -	\$ -	\$ -
4.6	345/138KV, Power Transformer with oil containment	0	EA		3,520.00	880.00	\$ -	\$ -	\$ -	\$ -
4.7	Transport & Testing- Transformer	0	EA		15,400.00	6,600.00	\$ -	\$ -	\$ -	\$ -
4.8	345kV, Shunt Reactor with oil containment-225MVAR	0	EA	3,026,425.00	3,520.00	880.00	\$ -	\$ -	\$ -	\$ -
4.9	345kV, Shunt Reactor with oil containment-50MVAR	0	EA	2,138,451.50	3,520.00	880.00	\$ -	\$ -	\$ -	\$ -
4.10	345kV, Shunt Reactor with oil containment-25MVAR	0	EA	1,900,130.50	3,520.00	880.00	\$ -	\$ -	\$ -	\$ -
4.11	Transport & Testing- Shunt Reactor	0	EA		457,900.00	301,600.00	\$ -	\$ -	\$ -	\$ -
4.12	345kV, Phase Angle Regulator with oil containment	0	EA	12,882,000.00	3,520.00	880.00	\$ -	\$ -	\$ -	\$ -
4.7	Transport & Testing- PAR	0	EA		615,400.00	406,600.00	\$ -	\$ -	\$ -	\$ -
4.13	345kV, Gas Insulated Switchgear, BAAH Arrangement		BKR	838,571.43	503,142.86	335,428.57	\$ -	\$ -	\$ -	\$ -
4.14	345kV, Circuit Breaker (PASS)	0	EA		57,239.00	24,531.00	\$ -	\$ -	\$ -	\$ -
4.15	345kV, Circuit Breaker (GIS), outdoor rated	0	EA				\$ -	\$ -	\$ -	\$ -
4.16	345kV, Circuit Breaker (GIS), outdoor rated-Line surge Arrester ( 3phase)	0	EA				\$ -	\$ -	\$ -	\$ -
4.17	345kV, surge Arrester		EA	6,669.00	5,460.00	2,340.00	\$ -	\$ -	\$ -	\$ -
4.18	138kV, Phase Angle Regulator with oil containment	1	EA	10,366,370.00	3,520.00	880.00	\$ 10,366,370	\$ 3,520	\$ 880	\$ 10,370,770
4.19	Transport & Testing- Phase Angle Regulating Transformer, 138kV	1	EA		336,400.00	220,600.00	\$ -	\$ 336,400	\$ 220,600	\$ 557,000
4.20	138kV, Gas Insulated Switchgear, BAAH Arrangement	0	BKR		205,800.00	4,200.00	\$ -	\$ -	\$ -	\$ -
4.21	138kV, Circuit Breaker, Hybrid circuit breaker	0	EA		13,559.00	5,811.00	\$ -	\$ -	\$ -	\$ -
4.22	138kV, Disconnect Switch	3	EA	37,700.00	11,875.50	5,089.50	\$ 113,100	\$ 35,627	\$ 15,269	\$ 163,995
4.23	138kV, Cable sealing end	6	EA	11,600.00	5,460.00	2,340.00	\$ 69,600	\$ 32,760	\$ 14,040	\$ 116,400
4.24	138kV, CCVT	0	EA		7,970.08	3,415.75	\$ -	\$ -	\$ -	\$ -
4.25	138kV, Surge arrester	12	EA	4,446.00	4,200.00	1,800.00	\$ 53,352	\$ 50,400	\$ 21,600	\$ 125,352
4.26	Station service transformers- 120/208v-250VA	0	EA	260,000.00	45,500.00	19,500.00	\$ -	\$ -	\$ -	\$ -
TOTAL - MAJOR EQUIPMENT							\$ 10,602,422	\$ 458,707	\$ 272,389	\$ 11,333,517
5. LOW VOLTAGE & CONTROL CABLE										
5.1	Control Cables	4,800	LF	5.30	1.43	0.29	\$ 25,428	\$ 6,876	\$ 1,375	\$ 33,679
5.2			LF		-	-	\$ -	\$ -	\$ -	\$ -
TOTAL - LOW VOLTAGE & CONTROL CABLE							\$ 25,428	\$ 6,876	\$ 1,375	\$ 33,679
6. CONDUIT & CABLE TRENCH										
6.1	Conduit, PVC, 6", SCH 40		LF	20.70	13.28	6.64	\$ -	\$ -	\$ -	\$ -
6.2	Conduit, PVC, 4", SCH 40	1,050	LF	11.15	10.80	5.40	\$ 11,708	\$ 11,340	\$ 5,670	\$ 28,718
6.3	Conduit, PVC, 3", SCH 40		LF	8.10	10.80	5.40	\$ -	\$ -	\$ -	\$ -
6.4	Conduit, PVC, 2", SCH 40		LF	3.95	10.80	5.40	\$ -	\$ -	\$ -	\$ -
6.5	Conduit, PVC, 1", SCH 40		LF	1.90	10.80	5.40	\$ -	\$ -	\$ -	\$ -
6.6	Cable Trench	375	LF	266.50	53.04	13.26	\$ 99,938	\$ 19,890	\$ 4,973	\$ 124,800
6.7										
6.8	138kV UG- Conduit	720	LF	266.73	202.15	100.00	\$ 192,046	\$ 145,545	\$ 72,004	\$ 409,595
6.9	138kV UG- Cable	2,268	LF	145.00	87.00	58.00	\$ 328,860	\$ 197,316	\$ 131,544	\$ 657,720
6.10	138kV UG- Termination	6	EA	27,805.00	9,846.48	2,813.28	\$ 166,830	\$ 59,079	\$ 16,880	\$ 242,789
6.11	345kV UG- Conduit		LF	266.73	202.15	100.00	\$ -	\$ -	\$ -	\$ -
6.12	345kV UG- Cable		LF	167.00	100.20	66.80	\$ -	\$ -	\$ -	\$ -
6.13	345kV UG- Termination		EA	27,805.00	9,846.48	2,813.28	\$ -	\$ -	\$ -	\$ -
6.14	Fiber Optic Cable	720	LF	7.40	3.33	2.22	\$ 5,326	\$ 2,398	\$ 1,599	\$ 9,323
6.15	Ground Continuity Conductor	720	LF	13.04	7.53	5.02	\$ 9,388	\$ 5,419	\$ 3,613	\$ 18,420
TOTAL - CONDUIT & CABLE TRENCH							\$ 814,095	\$ 440,988	\$ 236,281	\$ 1,491,364
7. GROUND GRID										
7.1	Cable, 4/0 AWG Bare Copper, 7 Strand Ground Conductor	1,470	LF	2.09	3.42	1.46	\$ 3,074	\$ 5,020	\$ 2,152	\$ 10,246
7.2	Caweld, DSA, 4/0 , T, CROSS	45	EA	165.00	75.00		\$ 7,425	\$ 3,375	\$ -	\$ 10,800
7.3	Ground Rod, 3/4" x 15'	32	EA	135.00	67.50	7.50	\$ 4,320	\$ 2,160	\$ 240	\$ 6,720
TOTAL - GROUND GRID							\$ 14,819	\$ 10,555	\$ 2,392	\$ 27,766
8. CONTROL ENCLOSURE										
8.1	345kv GIS Bldg	0	EA	3,817,603.08	2,672,322.16	1,145,280.92	\$ -	\$ -	\$ -	\$ -
8.2	138kv GIS/Control Bldg	0	EA	1,145,280.92	801,696.65	343,584.28	\$ -	\$ -	\$ -	\$ -
8.3	Primary Line Relays (87L): SEL-411L		EA	21,328.12	17,062.49	4,265.62	\$ -	\$ -	\$ -	\$ -
8.4	Backup Line Relays (87L): GE L90		EA	21,328.12	17,062.49	4,265.62	\$ -	\$ -	\$ -	\$ -
8.5	Primary Bay Control: SEL-451		EA	21,328.12	17,062.49	4,265.62	\$ -	\$ -	\$ -	\$ -
8.6	Backup Bay Control: SEL-451		EA	21,328.12	17,062.49	4,265.62	\$ -	\$ -	\$ -	\$ -
8.7	Primary Transformer/Reactor/PAR Differential Relays: SEL-487E		EA	21,328.12	17,062.49	4,265.62	\$ -	\$ -	\$ -	\$ -
8.8	Backup Transformer/Reactor/PAR Differential Relays: GE T60		EA	21,328.12	17,062.49	4,265.62	\$ -	\$ -	\$ -	\$ -
8.9	Primary Bus Differential Relays: SEL-487B		EA	21,328.12	17,062.49	4,265.62	\$ -	\$ -	\$ -	\$ -
8.10	Backup Bus Differential Relays: GE B90		EA	21,328.12	17,062.49	4,265.62	\$ -	\$ -	\$ -	\$ -



Item	Item Description	Estimated Quantity	Unit of Measure	Material Supply Rate	Labor Supply Rate	Const. Equipment Rate	Material Supply Cost	Labor Supply Cost	Const. Equipment Cost	TOTAL COST
8.11	RTU Panel A: SEL-2240 Axion, SEL-2730M ENET SW., SEL-2407 GPS, Modem, SEL-2523 Annunciator, JMUX		EA	12,500.00	10,000.00	2,500.00	\$ -	\$ -	\$ -	\$ -
8.12	RTU Panel B: SEL-2730M Ethernet Switch, SEL-2407 GPS Clock, SEL-2523 Annunciator		EA	12,500.00	10,000.00	2,500.00	\$ -	\$ -	\$ -	\$ -
8.13	HMI Panel		EA	12,500.00	10,000.00	2,500.00	\$ -	\$ -	\$ -	\$ -
8.14	Primary Line Relays (87L): SEL-411L		EA	21,328.12	17,062.49	4,265.62	\$ -	\$ -	\$ -	\$ -
8.15	Backup Line Relays (87L): GE L90		EA	21,328.12	17,062.49	4,265.62	\$ -	\$ -	\$ -	\$ -
8.16	Primary Line Relays (87L): SEL-411L	1	EA	21,328.12	17,062.49	4,265.62	\$ 21,328	\$ 17,062	\$ 4,266	\$ 42,656
8.17	Backup Line Relays (87L): GE L90	1	EA	21,328.12	17,062.49	4,265.62	\$ 21,328	\$ 17,062	\$ 4,266	\$ 42,656
8.18	Primary Transformer/Reactor/PAR Differential Relays: SEL-487E	1	EA	21,328.12	17,062.49	4,265.62	\$ 21,328	\$ 17,062	\$ 4,266	\$ 42,656
8.19	Backup Transformer/Reactor/PAR Differential Relays: GE T60	1	EA	21,328.12	17,062.49	4,265.62	\$ 21,328	\$ 17,062	\$ 4,266	\$ 42,656
8.20	Primary Bus Differential Relays: SEL-487B	5	EA	21,328.12	17,062.49	4,265.62	\$ 106,641	\$ 85,312	\$ 21,328	\$ 213,281
8.21	Backup Bus Differential Relays: GE B90	5	EA	21,328.12	17,062.49	4,265.62	\$ 106,641	\$ 85,312	\$ 21,328	\$ 213,281
8.22	125VDC Battery System		LS	25,000.00	22,750.00	9,750.00	\$ -	\$ -	\$ -	\$ -
8.23	Control house AC Panel		EA	65,000.00	91,000.00	39,000.00	\$ -	\$ -	\$ -	\$ -
8.24	Control House DC Panel		EA	65,000.00	91,000.00	39,000.00	\$ -	\$ -	\$ -	\$ -
8.25	Generator		EA	130,000.00	72,800.00	31,200.00	\$ -	\$ -	\$ -	\$ -
TOTAL - CONTROL ENCLOSURE							\$ 298,594	\$ 238,875	\$ 59,719	\$ 597,187
13.Exisitng East Garden City 138 kV Substation Upgrades							\$ 12,266,463	\$ 1,789,109	\$ 990,845	\$ 15,046,417
9. MOB/DEMOB, ENGINEERING, PERMITTING, T&C, PM & INDIRECTS										
	Contractor Mobilization / Demobilization									
9.1	Mob / Demob	1.0	LS		97,298.38	41,699.31	\$ -	\$ 97,298	\$ 41,699	\$ 138,998
	Project Management, Material Handling & Amenities									
9.2	Preconstruction Supervision (Engineering, Permitting, Procurement)	1	LS		150,464.17		\$ -	\$ 150,464	\$ -	\$ 150,464
9.3	Project Management & Staffing (includes PM, Field Engineers / Supervision, Scheduler and Cost Manager, SHEQ Staff, and Admin Staff)	1	LS		601,856.67		\$ -	\$ 601,857	\$ -	\$ 601,857
9.4	Utility PM and Project Oversight	1	LS		150,464.17		\$ -	\$ 150,464	\$ -	\$ 150,464
9.5	Site Accommodation, Facilities, Storage	1	LS	150,464.17			\$ 150,464	\$ -	\$ -	\$ 150,464
	Engineering									
9.6	Design Engineering	1.00	LS		1,203,713.34		\$ -	\$ 1,203,713	\$ -	\$ 1,203,713
9.7	LIDAR /GPR	-	LS				\$ -	\$ -	\$ -	\$ -
9.8	Geotech	5.00	EA		2,730.00	1,820.00	\$ -	\$ 13,650	\$ 9,100	\$ 22,750
9.9	Surveying/Staking	1.00	Site		105,324.92		\$ -	\$ 105,325	\$ -	\$ 105,325
	Testing & Commissioning									
9.10	Testing & Commissioning of SS and Equipment	1.00	LS		564,240.63		\$ -	\$ 564,241	\$ -	\$ 564,241
	Permitting and Additional Costs									
9.11	Physical Security	-	LS		6,546.96		\$ -	\$ -	\$ -	\$ -
9.12	Environmental Licensing & Permitting Costs & related legal cost	1.00	LS		150,464.17		\$ -	\$ 150,464	\$ -	\$ 150,464
9.13	Environmental-special studies/investigation	-	LS		-		\$ -	\$ -	\$ -	\$ -
9.14	Warranties / LOC's	1.00	LS		45,139.25		\$ -	\$ 45,139	\$ -	\$ 45,139
9.15	Laydown Lease	-	LS				\$ -	\$ -	\$ -	\$ -
9.16	Real Estate ( Acquisition)	-	LS		-	31,050,000.00	\$ -	\$ -	\$ -	\$ -
9.17	Legal Fees (Real estate)	-	LS		-	931,500.00	\$ -	\$ -	\$ -	\$ -
9.18	Insurance	-	LS		-	-	\$ -	\$ -	\$ -	\$ -
9.19	Bonds	1	LS		-	\$ 560,000	\$ -	\$ -	\$ 560,000	\$ 560,000
9.20	Sales Tax on Materials	8.80%	LS	12,266,462.98			\$ 1,079,449	\$ -	\$ -	\$ 1,079,449
9.21	Fees for permits, including roadway, railroad, building or other local permits	1.00	LS		15,046.42		\$ -	\$ 15,046	\$ -	\$ 15,046
TOTAL - MOB/DEMOB, ENGINEERING, PERMITTING, T&C, PM & INDIRECTS:							\$ 1,229,913	\$ 3,097,662	\$ 610,799	\$ 4,938,374

<p align="center"> <u>NEXTera Energy- TO36 Core 1</u>  <u>Comp 4 - Dunwoodie To New Rochelle Landing 345kV Onshore UG Cables -single circuit</u>  <u>(EGC To Dunwoodie 345 kV)</u> </p>	
Total:	\$ 188,625,656

	NEXTera Energy- TO36 Core 1
--	-----------------------------

NEXtera Energy- TO36 Core 1				
	Material Supply	Labor Supply	Equip Supply	Total
Comp 4 - Dunwoodie To New Rochelle Landing 345kV Onshore UG Cables -single circuit(EGC To Dunwoodie 345 kV)				
1. SITE PREP/ACCESS/TRAFFIC MANAGEMENT	\$ 2,044,864	\$ 10,048,478	\$ 4,020,386	\$ 16,113,728
2. ONSHORE CABLE CONDUITS & VAULTS INSTALLATION	\$ 14,363,368	\$ 14,404,930	\$ 9,713,465	\$ 38,481,763
3. ONSHORE CABLE PROCUREMENT AND INSTALLATION	\$ 25,812,070	\$ 15,635,513	\$ 10,063,576	\$ 51,511,158
4. MOB/DEMOB, ENGINEERING, PERMITTING, T&C, PM & INDIRECTS	\$ 4,810,229	\$ 16,648,918	\$ 5,644,412	\$ 27,103,560
SUBTOTAL (Costs):	\$ 47,030,531	\$ 56,737,840	\$ 29,441,838	\$ 133,210,209
CONTRACTOR MARK-UP (OH&P)	\$ 8,465,496	\$ 10,212,811	\$ 5,299,531	\$ 23,977,838
SUBTOTAL:	\$ 55,496,027	\$ 66,950,651	\$ 34,741,369	\$ 157,188,047
CONTINGENCY ON ENTIRE PROJECT	\$ 11,099,205	\$ 13,390,130	\$ 6,948,274	\$ 31,437,609
TOTAL:	\$ 66,595,232	\$ 80,340,781	\$ 41,689,643	\$ 188,625,656

Description of Work: Dunwoodie - New Rochelle Landing (single cable duct). 5000 kcmil copper XLPE, single cable per phase.										
Item	Item Description	Estimated Quantity	Unit of Measure	Material Supply Rate	Labor Supply Rate	Const. Equipment Rate	Material Supply Cost	Labor Supply Cost	Const. Equipment Cost	TOTAL
Comp 4 - Dunwoodie To New Rochelle Landing 345kV Onshore UG Cables -single circuit(EGC To Dunwoodie 345 kV)										
1. SITE PREP/ACCESS/TRAFFIC MANAGEMENT										
1.1	Environmental BMPs / SWPPP Installation, Maintenance & Repairs	0	LF	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
1.2	Existing Utility Conflict and Relocation	8.21	Mile		\$ 700,000	\$ 300,000	\$ -	\$ 5,747,000	\$ 2,463,000	\$ 8,210,000
1.3	Flaggers	260	DAY	\$ 1,600	\$ 4,800	\$ 1,600	\$ 416,000	\$ 1,248,000	\$ 416,000	\$ 2,080,000
1.4	K Rail / Lane Control / Metal Plates	43,349	LF	\$ 30	\$ 18	\$ 12	\$ 1,300,464	\$ 780,278	\$ 520,186	\$ 2,600,928
1.5	Police Support	10,400.0	HR		\$ 120	\$ 27	\$ -	\$ 1,248,000	\$ 280,800	\$ 1,528,800
1.6	Additional Traffic Management		LS				\$ -	\$ -	\$ -	\$ -
1.7	Access / Clearing Costs		LS				\$ -	\$ -	\$ -	\$ -
1.8	Snow Removal	40.0	DAY		\$ 1,000	\$ 300	\$ -	\$ 40,000	\$ 12,000	\$ 52,000
1.9	Existing Utility Protection	8.21	Mile	\$ 40,000	\$ 120,000	\$ 40,000	\$ 328,400	\$ 985,200	\$ 328,400	\$ 1,642,000
TOTAL - SITE PREP/ACCESS/TRAFFIC MANAGEMENT/ ACCESS:							\$ 2,044,864	\$ 10,048,478	\$ 4,020,386	\$ 16,113,728
2. ONSHORE CABLE CONDUITS & VAULTS INSTALLATION										
2.1	Trench Box Shoring & Trench Box Install Crew	8	Miles		\$ 139,800	\$ 93,200	\$ -	\$ 1,147,758	\$ 765,172	\$ 1,912,930
2.2	Formwork in Trench	335,070	SF	\$ 2	\$ 1.5	\$ 0.5	\$ 670,141	\$ 502,606	\$ 167,535	\$ 1,340,282
2.3	Trench Excavation	16,754	CY		\$ 17.5	\$ 7.5	\$ -	\$ 293,187	\$ 125,651	\$ 418,838
2.4	Supply & Install 6" Sand Bedding for direct bury conduits	1,745	SF	\$ 50	\$ 25	\$ 14	\$ 87,258	\$ 42,756	\$ 24,432	\$ 154,447
2.5	Supply & Install Thermal Backfill	14,659	CY	\$ 350	\$ 245	\$ 105	\$ 5,130,766	\$ 3,591,536	\$ 1,539,230	\$ 10,261,531
2.6	Supply & Install Concrete Cap (6")	0	CY	\$ 200	\$ 125	\$ 50	\$ -	\$ -	\$ -	\$ -
2.7	Native Backfill -direct bury conduits sys Trench	0	CY		\$ 14.0	\$ 6.0	\$ -	\$ -	\$ -	\$ -
2.8	Supply & Install Ductbank Concrete	6,825	CY	\$ 200	\$ 125	\$ 50	\$ 1,364,947	\$ 853,092	\$ 341,237	\$ 2,559,275
2.9	Conduit 8" SCH 40PVC	173,395	LF	\$ 28.6	\$ 5.7	\$ 2.4	\$ 4,959,103	\$ 983,151	\$ 421,350	\$ 6,363,604
2.10	Conduit 4" SCH 40PVC	0	LF	\$ 9.8	\$ 4.20	\$ 1.8	\$ -	\$ -	\$ -	\$ -
2.11	Conduit 2" SCH 40PVC	86,698	LF	\$ 3.5	\$ 3.15	\$ 1.4	\$ 305,176	\$ 273,097	\$ 117,042	\$ 695,315
2.12	Warning Tape	86,698	LF	\$ 0.15	\$ 0.25	\$ 0.10	\$ 13,005	\$ 21,674	\$ 8,670	\$ 43,349
2.13	Trench Box Shoring (Vault)	30	EA	\$ -	\$ 18,079	\$ 27,119	\$ -	\$ 542,373	\$ 813,559	\$ 1,355,932
2.14	Splice Vault Excavation	2,992	CY		\$ 17.5	\$ 7.5	\$ -	\$ 52,360	\$ 22,440	\$ 74,800

Item	Item Description	Estimated Quantity	Unit of Measure	Material Supply Rate	Labor Supply Rate	Const. Equipment Rate	Material Supply Cost	Labor Supply Cost	Const. Equipment Cost	TOTAL
2.15	Splice Vault Supply & Installation	30	EA	\$ 35,000	\$ 16,500	\$ 38,500	\$ 1,050,000	\$ 495,000	\$ 1,155,000	\$ 2,700,000
2.16	Splice Vault Backfill	898	CY		\$ 14.0	\$ 6.0	\$ -	\$ 12,566	\$ 5,386	\$ 17,952
2.17	Jack and Bore along Route	565	LF	\$ 800	\$ 1,600	\$ 1,600	\$ 452,000	\$ 904,000	\$ 904,000	\$ 2,260,000
2.18	HDD along Route		LF	\$ 800	\$ 1,600	\$ 1,600	\$ -	\$ -	\$ -	\$ -
2.19	Air Test Ducts	260,093	LF			\$ 0.25	\$ -	\$ -	\$ 65,023	\$ 65,023
2.20	PVMT, ASPHALT, 2" SURFACE COURSE	16,371	SY	\$ 14.00	\$ 14.00	\$ 7.00	\$ 229,199	\$ 229,199	\$ 114,600	\$ 572,998
2.21	PVMT, AGGREGATE, 10", BASE COURSE	4,548	CY	\$ 22.38	\$ 23.50	\$ 10.07	\$ 101,775	\$ 106,864	\$ 45,799	\$ 254,438
2.22	Concrete Ductbank Thermal Resistivity Testing (every 100CY of concrete poured)	68	EA		\$ 400	\$ 1,200	\$ -	\$ 27,299	\$ 81,897	\$ 109,196
2.23	Concrete Ductbank Compressive Strength Testing (every 100CY of concrete poured)	68	EA		\$ 10	\$ 15	\$ -	\$ 682	\$ 1,024	\$ 1,706
2.24	Backfill Thermal Resistivity Testing (every 100CY of backfill placed)	147	EA		\$ 400	\$ 1,200	\$ -	\$ 58,637	\$ 175,912	\$ 234,549
2.25	Additional misc. testing allowance (Native Backfill, Asphalt Density, Concrete Curb etc.)	1	LS		\$ 448,266	\$ 298,844	\$ -	\$ 448,266	\$ 298,844	\$ 747,110
2.26	Excess Materials Disposal to Certified Backfill	24,502	CY		\$ 24.5	\$ 10.5	\$ -	\$ 600,306	\$ 257,274	\$ 857,580
2.27	Rock Excavation and Removal	13,164	CY		\$ 243	\$ 162	\$ -	\$ 3,198,774	\$ 2,132,516	\$ 5,331,290
2.28	Dewatering	30	EA			\$ 4,000	\$ -	\$ -	\$ 120,000	\$ 120,000
2.29	Contaminated Water Treatment and Disposal	1	LS				\$ -	\$ -	\$ -	\$ -
2.30	Contaminated Spoils Disposal	1	LS				\$ -	\$ -	\$ -	\$ -
2.31	Excavated material - stockpile management	19,746	CF		\$ 1.0	\$ 0.5	\$ -	\$ 19,746	\$ 9,873	\$ 29,618
TOTAL - ONSHORE CABLE CONDUITS & VAULTS INSTALLATION:							\$ 14,363,368	\$ 14,404,930	\$ 9,713,465	\$ 38,481,763
3. ONSHORE CABLE PROCUREMENT AND INSTALLATION										
3.1	Circuit #1- Procurement & Installation- 345kV 5000 kcmil copper XLPE	136,549	FT	\$ 167	\$ 100	\$ 67	\$ 22,803,636	\$ 13,682,182	\$ 9,121,454	\$ 45,607,272
3.2	Circuit #1- Cable Splicing- 345kV 5000 kcmil copper XLPE	90	EA	\$ 11,722	\$ 9,846	\$ 2,813	\$ 1,054,980	\$ 886,183	\$ 253,195	\$ 2,194,358
3.3	Circuit #1- Cable Termination- 345kV 5000 kcmil copper XLPE	6	EA	\$ 27,805	\$ 9,846	\$ 2,813	\$ 166,830	\$ 59,079	\$ 16,880	\$ 242,789
3.4	Circuit #2- Procurement & Installation- 345kV 5000 kcmil copper XLPE		FT	\$ 167	\$ 100	\$ 67	\$ -	\$ -	\$ -	\$ -
3.5	Circuit #2- Cable Splicing- 345kV 5000 kcmil copper XLPE		EA	\$ 11,722	\$ 9,846	\$ 2,813	\$ -	\$ -	\$ -	\$ -
3.6	Circuit #2- Cable Termination- 345kV 5000 kcmil copper XLPE		EA	\$ 27,805	\$ 9,846	\$ 2,813	\$ -	\$ -	\$ -	\$ -
3.7	Circuit #3- Procurement & Installation- 345kV 5000 kcmil copper XLPE		FT	\$ 167	\$ 100	\$ 67	\$ -	\$ -	\$ -	\$ -
3.8	Circuit #3- Cable Splicing- 345kV 5000 kcmil copper XLPE		EA	\$ 11,722	\$ 9,846	\$ 2,813	\$ -	\$ -	\$ -	\$ -
3.9	Circuit #3- Cable Termination- 345kV 5000 kcmil copper XLPE		EA	\$ 27,805	\$ 9,846	\$ 2,813	\$ -	\$ -	\$ -	\$ -
3.10	Link Box & MH racking	30	EA	\$ 28,548	\$ 17,129	\$ 11,419	\$ 856,454	\$ 513,872	\$ 342,581	\$ 1,712,907
3.11	Fiber Optic Cable	45,516	FT	\$ 7	\$ 3	\$ 2	\$ 336,684	\$ 151,596	\$ 101,064	\$ 589,344
3.12	Ground Continuity Conductor	45,516	FT	\$ 13	\$ 8	\$ 5	\$ 593,486	\$ 342,601	\$ 228,400	\$ 1,164,487
TOTAL - ONSHORE CABLE PROCUREMENT AND INSTALLATION							\$ 25,812,070	\$ 15,635,513	\$ 10,063,576	\$ 51,511,158
Comp 4 - Dunwoodie To New Rochelle Landing 345kV Onshore UG Cables -single circuit(EGC To Dunwoodie 345 kV)							\$ 42,220,302	\$ 40,088,921	\$ 23,797,426	\$ 106,106,649
4. MOB/DEMOB, ENGINEERING, PERMITTING, T&C, PM & INDIRECTS										
	Contractor Mobilization / Demobilization									
4.1	Mob / Demob	1	LS		\$ 1,916,590	\$ 1,277,727	\$ -	\$ 1,916,590	\$ 1,277,727	\$ 3,194,317
	Project Management, Material Handling & Amenities									
4.2	Preconstruction Supervision (Engineering, Permitting, Procurement)	1	LS		1,061,066.49		\$ -	\$ 1,061,066	\$ -	\$ 1,061,066
4.3	Project Management & Staffing (includes PM, Field Engineers / Supervision, Scheduler and Cost Manager, SHEQ Staff, and Admin Staff)	1	LS		4,244,265.98		\$ -	\$ 4,244,266	\$ -	\$ 4,244,266
4.4	Utility PM and Project Oversight	1	LS		1,061,066.49		\$ -	\$ 1,061,066	\$ -	\$ 1,061,066
4.5	Site Accommodation, Facilities, Storage	1	LS	1,061,066.49			\$ 1,061,066	\$ -	\$ -	\$ 1,061,066
	Engineering									
4.6	Design Engineering	1.0	LS		\$ 5,305,332	\$ -	\$ -	\$ 5,305,332	\$ -	\$ 5,305,332
4.7	LiDAR /GPR	1.0	LS		\$ 190,992	\$ 127,328	\$ -	\$ 190,992	\$ 127,328	\$ 318,320
4.8	Geotech	9.00	EA		2,730.00	1,820.00	\$ -	\$ 24,570	\$ 16,380	\$ 40,950
4.9	Surveying/Staking	1	LS		\$ 445,648	\$ 297,099	\$ -	\$ 445,648	\$ 297,099	\$ 742,747
	Testing & Commissioning									
4.10	Testing & Commissioning of T-Line and Equipment	1	EA		\$ 20,000		\$ -	\$ 20,000	\$ -	\$ 20,000
	Permitting, Indirects and Additional Costs									
4.11	Environmental Licensing & Permitting Costs & related legal cost	1	LS		\$ 1,061,066		\$ -	\$ 1,061,066	\$ -	\$ 1,061,066
4.12	Environmental-special studies/investigation		LS		\$ -		\$ -	\$ -	\$ -	\$ -
4.13	Warranties / LOC's	1	LS		\$ 318,320		\$ -	\$ 318,320	\$ -	\$ 318,320
4.14	Laydown Lease & temporary easement	1	LS		\$ 1,000,000		\$ -	\$ 1,000,000	\$ -	\$ 1,000,000
4.15	Real Estate ( Acquisition)	1	LS			\$ 58,031	\$ -	\$ -	\$ 58,031	\$ 58,031
4.16	Legal Fees (Real estate)	1.00	LS		-	1,740.93	\$ -	\$ -	\$ 1,741	\$ 1,741
4.17	Insurance	-	LS		-	-	\$ -	\$ -	\$ -	\$ -
4.18	Insurance (specialty, e.g. railroad)		Crossing			\$ 1,000	\$ -	\$ -	\$ -	\$ -
4.19	Bonds	1	LS			\$ 3,760,000	\$ -	\$ -	\$ 3,760,000	\$ 3,760,000
4.20	Sales Tax on Materials	8.88%	% of material cost	\$ 42,220,301.83			\$ 3,749,163	\$ -	\$ -	\$ 3,749,163
4.21	Fees for permits, including roadway, railroad, building or other local permits	1	LS			\$ 106,107	\$ -	\$ -	\$ 106,107	\$ 106,107
TOTAL - MOB/DEMOB, ENGINEERING, PERMITTING, T&C, PM & INDIRECTS:							\$ 4,810,229	\$ 16,648,918	\$ 5,644,412	\$ 27,103,560

NEXtera Energy- TO36 Core 1

Comp 4C - Sprain Brook To New Rochelle Landing Onshore 345kV UG Cables -Dobule circuits

(EGC To Sprain Brook 345 kV / Ruland To Sprain Brook 345 kV)

Total:   \$   346,473,248

NEXtera Energy- TO36 Core 1				
	Material Supply	Labor Supply	Equip Supply	Total
=A18				
1. SITE PREP/ACCESS/TRAFFIC MANAGEMENT	\$ 2,512,448	\$ 12,822,389	\$ 4,834,059	\$ 20,168,896
2. ONSHORE CABLE CONDUITS & VAULTS INSTALLATION	\$ 27,540,967	\$ 25,088,214	\$ 16,490,743	\$ 69,119,924
3. ONSHORE CABLE PROCUREMENT AND INSTALLATION	\$ 53,127,377	\$ 32,168,921	\$ 20,725,748	\$ 106,022,045
4. MOB/DEMOB, ENGINEERING, PERMITTING, T&C, PM & INDIRECTS	\$ 9,339,563	\$ 29,623,574	\$ 10,410,495	\$ 49,373,632
SUBTOTAL (Costs):	\$ 92,520,355	\$ 99,703,098	\$ 52,461,045	\$ 244,684,497
CONTRACTOR MARK-UP (OH&P)	\$ 16,653,664	\$ 17,946,558	\$ 9,442,988	\$ 44,043,210
SUBTOTAL:	\$ 109,174,018	\$ 117,649,655	\$ 61,904,033	\$ 288,727,707
CONTINGENCY ON ENTIRE PROJECT	\$ 21,834,804	\$ 23,529,931	\$ 12,380,807	\$ 57,745,541
TOTAL:	\$ 131,008,822	\$ 141,179,587	\$ 74,284,840	\$ 346,473,248

Description of Work: Dunwoodie - New Rochelle Landing (double circuit duct). 5000 kcmil copper XLPE, single cable per phase.										
Item	Item Description	Estimated Quantity	Unit of Measure	Material Supply Rate	Labor Supply Rate	Const. Equipment Rate	Material Supply Cost	Labor Supply Cost	Const. Equipment Cost	TOTAL
Comp 4C - Sprain Brook To New Rochelle Landing Onshore 345kV UG Cables -Dobule circuits(EGC To Sprain Brook 345 kV / Ruland To Sprain Brook 345 kV)										
1. SITE PREP/ACCESS/TRAFFIC MANAGEMENT										
1.1	Environmental BMPs / SWPPP Installation, Maintenance & Repairs	0	LF	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
1.2	Existing Utility Conflict and Relocation	8.47	Mile		\$ 700,000	\$ 300,000	\$ -	\$ 5,929,000	\$ 2,541,000	\$ 8,470,000
1.3	Flaggers	520	DAY	\$ 1,600	\$ 4,800	\$ 1,600	\$ 832,000	\$ 2,496,000	\$ 832,000	\$ 4,160,000
1.4	K Rail / Lane Control / Metal Plates	44,722	LF	\$ 30	\$ 18	\$ 12	\$ 1,341,648	\$ 804,989	\$ 536,659	\$ 2,683,296
1.5	Police Support	20,800.0	HR		\$ 120	\$ 27	\$ -	\$ 2,496,000	\$ 561,600	\$ 3,057,600
1.6	Additional Traffic Management		LS				\$ -	\$ -	\$ -	\$ -
1.7	Access / Clearing Costs		LS				\$ -	\$ -	\$ -	\$ -
1.8	Snow Removal	80.0	DAY		\$ 1,000	\$ 300	\$ -	\$ 80,000	\$ 24,000	\$ 104,000
1.9	Existing Utility Protection	8.47	Mile	\$ 40,000	\$ 120,000	\$ 40,000	\$ 338,800	\$ 1,016,400	\$ 338,800	\$ 1,694,000
TOTAL - SITE PREP/ACCESS/TRAFFIC MANAGEMENT/ ACCESS:							\$ 2,512,448	\$ 12,822,389	\$ 4,834,059	\$ 20,168,896
2. ONSHORE CABLE CONDUITS & VAULTS INSTALLATION										
EGC-SP & RL-SP -Double CIRCUITS										
2.1	Trench Box Shoring & Trench Box Install Crew	8.47	Miles		\$ 139,800	\$ 93,200	\$ -	\$ 1,184,106	\$ 789,404	\$ 1,973,510
2.2	Formwork in Trench	357,773	SF	\$ 2	\$ 1.5	\$ 0.5	\$ 715,546	\$ 536,659	\$ 178,886	\$ 1,431,091
2.3	Trench Excavation	33,790	CY		\$ 17.5	\$ 7.5	\$ -	\$ 591,319	\$ 253,422	\$ 844,741
2.4	Supply & Install 6" Sand Bedding for direct bury conduits	3,520	CY	\$ 50	\$ 25	\$ 14	\$ 175,988	\$ 86,234	\$ 49,277	\$ 311,498
2.5	Supply & Install Thermal Backfill -conduit level	29,566	CY	\$ 350	\$ 245	\$ 105	\$ 10,348,081	\$ 7,243,657	\$ 3,104,424	\$ 20,696,163
2.6	Supply & Install Concrete Cap (6")	0	CY	\$ 200	\$ 125	\$ 50	\$ -	\$ -	\$ -	\$ -
2.7	Supply & Install Native Backfill -direct bury conduits sys	0	CY	\$ 350	\$ 245.0	\$ 105.0	\$ -	\$ -	\$ -	\$ -
2.8	Supply & Install Ductbank Concrete	13,774	CY	\$ 200	\$ 125.0	\$ 50.0	\$ 2,754,851	\$ 1,721,782	\$ 688,713	\$ 5,165,345
2.8	Conduit 8" SCH 40PVC	357,773	LF	\$ 28.6	\$ 5.7	\$ 2.4	\$ 10,232,302	\$ 2,028,572	\$ 869,388	\$ 13,130,262
2.9	Conduit 4" SCH 40PVC	0	LF	\$ 9.8	\$ 4.20	\$ 1.8	\$ -	\$ -	\$ -	\$ -
2.10	Conduit 2" SCH 40PVC	178,886	LF	\$ 3.5	\$ 3.15	\$ 1.4	\$ 629,680	\$ 563,492	\$ 241,497	\$ 1,434,669
2.11	Warning Tape	44,722	LF	\$ 0.15	\$ 0.25	\$ 0.10	\$ 6,708	\$ 11,180	\$ 4,472	\$ 22,361
2.12	Trench Box Shoring (Vault)	60	EA	\$ -	\$ 18,079	\$ 27,119	\$ -	\$ 1,084,746	\$ 1,627,119	\$ 2,711,864
2.13	Splice Vault Excavation	5,984	CY		\$ 17.5	\$ 7.5	\$ -	\$ 104,720	\$ 44,880	\$ 149,600
2.14	Splice Vault Supply & Installation	60	EA	\$ 35,000	\$ 16,500	\$ 38,500	\$ 2,100,000	\$ 990,000	\$ 2,310,000	\$ 5,400,000
2.15	Splice Vault Backfill	1,795	CY		\$ 14.0	\$ 6.0	\$ -	\$ 25,133	\$ 10,771	\$ 35,904

Item	Item Description	Estimated Quantity	Unit of Measure	Material Supply Rate	Labor Supply Rate	Const. Equipment Rate	Material Supply Cost	Labor Supply Cost	Const. Equipment Cost	TOTAL
2.16	Jack and Bore along Route	0	LF	\$ 800	\$ 1,600	\$ 1,600	\$ -	\$ -	\$ -	\$ -
2.17	HDD along Route	0	LF	\$ 800	\$ 1,600	\$ 1,600	\$ -	\$ -	\$ -	\$ -
2.18	Air Test Ducts	536,659	LF			\$ 0.25	\$ -	\$ -	\$ 134,165	\$ 134,165
2.20	PVMT, ASPHALT, 2" SURFACE COURSE	28,581	SY	\$ 14.00	\$ 14.00	\$ 7.00	\$ 400,133	\$ 400,133	\$ 200,067	\$ 1,000,333
2.21	PVMT, AGGREGATE, 10", BASE COURSE	7,939	CY	\$ 22.38	\$ 23.50	\$ 10.07	\$ 177,678	\$ 186,562	\$ 79,955	\$ 444,195
2.20	Concrete Ductbank Thermal Resistivity Testing (every 100CY of concrete poured)	138	EA		\$ 400	\$ 1,200	\$ -	\$ 55,097	\$ 165,291	\$ 220,388
2.21	Concrete Ductbank Compressive Strength Testing (every 100CY of concrete poured)	138	EA		\$ 10	\$ 15	\$ -	\$ 1,377	\$ 2,066	\$ 3,444
2.22	Backfill Thermal Resistivity Testing (every 100CY of backfill placed)	296	EA		\$ 400	\$ 1,200	\$ -	\$ 118,264	\$ 354,791	\$ 473,055
2.25	Additional misc. testing allowance (Native Backfill, Asphalt Density, Concrete Curb etc.)	1	LS		\$ 462,462	\$ 308,308	\$ -	\$ 462,462	\$ 308,308	\$ 770,770
2.24	Excess Materials Disposal to Certified Backfill	49,372	CY		\$ 24.5	\$ 10.5	\$ -	\$ 1,209,614	\$ 518,406	\$ 1,728,020
2.25	Rock Excavation and Removal	26,516	CY		\$ 243	\$ 162	\$ -	\$ 6,443,332	\$ 4,295,555	\$ 10,738,886
2.26	Dewatering	60	EA			\$ 4,000	\$ -	\$ -	\$ 240,000	\$ 240,000
2.27	Contaminated Water Treatment and Disposal	1	LS				\$ -	\$ -	\$ -	\$ -
2.28	Contaminated Spoils Disposal	1	LS				\$ -	\$ -	\$ -	\$ -
2.29	Excavated material - stockpile management	39,774	CF		\$ 1.0	\$ 0.5	\$ -	\$ 39,774	\$ 19,887	\$ 59,660
TOTAL - ONSHORE CABLE CONDUITS & VAULTS INSTALLATION:							\$ 27,540,967	\$ 25,088,214	\$ 16,490,743	\$ 69,119,924
3. ONSHORE CABLE PROCUREMENT AND INSTALLATION										
3.1	Circuit #1- Procurement & Installation- 345kV 5000 kcmil copper XLPE	140,873	FT	\$ 167	\$ 100	\$ 67	\$ 23,525,798	\$ 14,115,479	\$ 9,410,319	\$ 47,051,595
3.2	Circuit #1- Cable Splicing- 345kV 5000 kcmil copper XLPE	90	EA	\$ 11,722	\$ 9,846	\$ 2,813	\$ 1,054,980	\$ 886,183	\$ 253,195	\$ 2,194,358
3.3	Circuit #1- Cable Termination- 345kV 5000 kcmil copper XLPE	6	EA	\$ 27,805	\$ 9,846	\$ 2,813	\$ 166,830	\$ 59,079	\$ 16,880	\$ 242,789
3.4	Circuit #2- Procurement & Installation- 345kV 5000 kcmil copper XLPE	140,873	FT	\$ 167	\$ 100	\$ 67	\$ 23,525,798	\$ 14,115,479	\$ 9,410,319	\$ 47,051,595
3.5	Circuit #2- Cable Splicing- 345kV 5000 kcmil copper XLPE	90	EA	\$ 11,722	\$ 9,846	\$ 2,813	\$ 1,054,980	\$ 886,183	\$ 253,195	\$ 2,194,358
3.6	Circuit #2- Cable Termination- 345kV 5000 kcmil copper XLPE	6	EA	\$ 27,805	\$ 9,846	\$ 2,813	\$ 166,830	\$ 59,079	\$ 16,880	\$ 242,789
3.7	Circuit #3- Procurement & Installation- 345kV 5000 kcmil copper XLPE		FT	\$ 167	\$ 100	\$ 67	\$ -	\$ -	\$ -	\$ -
3.8	Circuit #3- Cable Splicing- 345kV 5000 kcmil copper XLPE		EA	\$ 11,722	\$ 9,846	\$ 2,813	\$ -	\$ -	\$ -	\$ -
3.9	Circuit #3- Cable Termination- 345kV 5000 kcmil copper XLPE		EA	\$ 27,805	\$ 9,846	\$ 2,813	\$ -	\$ -	\$ -	\$ -
3.10	Link Box & MH racking	60	EA	\$ 28,548	\$ 17,129	\$ 11,419	\$ 1,712,907	\$ 1,027,744	\$ 685,163	\$ 3,425,814
3.11	Fiber Optic Cable	93,915	FT	\$ 7	\$ 3	\$ 2	\$ 694,692	\$ 312,794	\$ 208,530	\$ 1,216,016
3.12	Ground Continuity Conductor	93,915	FT	\$ 13	\$ 8	\$ 5	\$ 1,224,562	\$ 706,901	\$ 471,267	\$ 2,402,731
TOTAL - ONSHORE CABLE PROCUREMENT AND INSTALLATION							\$ 53,127,377	\$ 32,168,921	\$ 20,725,748	\$ 106,022,045
Comp 4C - Sprain Brook To New Rochelle Landing Onshore 345kV UG Cables -Dobule circuits(EGC To Sprain Brook 345 kV / Ruland To Sprain Broo							\$ 83,180,792	\$ 70,079,524	\$ 42,050,550	\$ 195,310,866
4. MOB/DEMOB, ENGINEERING, PERMITTING, T&C, PM & INDIRECTS										
	Contractor Mobilization / Demobilization									
4.1	Mob / Demob	1	LS		\$ 3,363,902	\$ 2,242,601	\$ -	\$ 3,363,902	\$ 2,242,601	\$ 5,606,504
	Project Management, Material Handling & Amenities									
4.2	Preconstruction Supervision (Engineering, Permitting, Procurement)	1	LS		1,953,108.66		\$ -	\$ 1,953,109	\$ -	\$ 1,953,109
4.3	Project Management & Staffing (includes PM, Field Engineers / Supervision, Scheduler and Cost Manager, SHEQ Staff, and Admin Staff)	1	LS		7,812,434.62		\$ -	\$ 7,812,435	\$ -	\$ 7,812,435
4.4	Utility PM and Project Oversight	1	LS		1,953,108.66		\$ -	\$ 1,953,109	\$ -	\$ 1,953,109
4.5	Site Accommodation, Facilities, Storage	1	LS	1,953,108.66			\$ 1,953,109	\$ -	\$ -	\$ 1,953,109
	Engineering									
4.6	Design Engineering	1.0	LS		\$ 9,765,543	\$ -	\$ -	\$ 9,765,543	\$ -	\$ 9,765,543
4.7	LiDAR /GPR	1.0	LS		\$ 351,560	\$ 234,373	\$ -	\$ 351,560	\$ 234,373	\$ 585,933
4.8	Geotech	9.00	EA		2,730.00	1,820.00	\$ -	\$ 24,570	\$ 16,380	\$ 40,950
4.9	Surveying/Staking	1	LS		\$ 820,306	\$ 546,870	\$ -	\$ 820,306	\$ 546,870	\$ 1,367,176
	Testing & Commissioning									
4.10	Testing & Commissioning of T-Line and Equipment	1	EA		\$ 40,000		\$ -	\$ 40,000	\$ -	\$ 40,000
	Permitting, Indirects and Additional Costs									
4.11	Environmental Licensing & Permitting Costs & related legal cost	1	LS		\$ 1,953,109		\$ -	\$ 1,953,109	\$ -	\$ 1,953,109
4.12	Environmental-special studies/investigation		LS		\$ -		\$ -	\$ -	\$ -	\$ -
4.13	Warranties / LOC's	1	LS		\$ 585,933		\$ -	\$ 585,933	\$ -	\$ 585,933
4.14	Laydown Lease & temporary easement	1	LS		\$ 1,000,000		\$ -	\$ 1,000,000	\$ -	\$ 1,000,000
4.15	Real Estate ( Acquisition)	1	LS			\$ 247,533	\$ -	\$ -	\$ 247,533	\$ 247,533
4.16	Legal Fees (Real estate)	1.00	LS		-	7,425.99	\$ -	\$ -	\$ 7,426	\$ 7,426
4.17	Insurance	-	LS		-	-	\$ -	\$ -	\$ -	\$ -
4.18	Insurance (specialty, e.g. railroad)		Crossing			\$ 1,000	\$ -	\$ -	\$ -	\$ -
4.19	Bonds	1	LS			\$ 6,920,000	\$ -	\$ -	\$ 6,920,000	\$ 6,920,000
4.20	Sales Tax on Materials	8.88%	% of material cost	\$ 83,180,791.58			\$ 7,386,454	\$ -	\$ -	\$ 7,386,454
4.21	Fees for permits, including roadway, railroad, building or other local permits	1	LS			\$ 195,311	\$ -	\$ -	\$ 195,311	\$ 195,311
TOTAL - MOB/DEMOB, ENGINEERING, PERMITTING, T&C, PM & INDIRECTS:							\$ 9,339,563	\$ 29,623,574	\$ 10,410,495	\$ 49,373,632



**EGC-Dunwoodie 345KV / EGC-SprainBrook 345KV/ Ruland-SprainBrook 345KV**

	Material Supply	Labor Supply	Equip Supply	Total
<b>Comp 17. New Rochelle Landing to Hempstead Harbor Landing (Shore Road) 345kV Offshore Submarine Cables - Three circuits (three lines, single circuit each)</b> <b>EGC-Dunwoodie 345KV / EGC-SprainBrook 345KV/ Ruland-SprainBrook 345KV</b>				
1. SUBMARINE CABLE	\$ 170,749,328	\$ 149,849,551	\$ 99,574,291	\$ 420,173,170
2. TRANSITION STATION	\$ 1,367,680	\$ 1,706,372	\$ 1,640,135	\$ 4,714,187
3. MOB/DEMOB, ENGINEERING, PERMITTING, T&C, PM & INDIRECTS:	\$ 19,395,170	\$ 62,117,544	\$ 20,312,816	\$ 101,825,530
SUBTOTAL (Costs):	\$ 191,512,178	\$ 213,673,467	\$ 121,527,241	\$ 526,712,886
CONTRACTOR MARK-UP (OH&P)	\$ 34,472,192	\$ 38,461,224	\$ 21,874,903	\$ 94,808,320
SUBTOTAL:	\$ 225,984,370	\$ 252,134,691	\$ 143,402,144	\$ 621,521,206
CONTINGENCY ON ENTIRE PROJECT	\$ -	\$ -	\$ -	\$ 124,304,241
TOTAL:	\$ 225,984,370	\$ 252,134,691	\$ 143,402,144	\$ 745,825,447

Description of Work: New Rochelle landing - Hempstead Harbor Landing. Part of any Dunwoodie to Shore/Ruland/EGC 345 kV project segment (Include HDD's to get onshore at both ends of route) 1600 mm2 Tri-Core										
Item	Item Description	Estimated Quantity	Unit of Measure	Material Supply Rate	Labor Supply Rate	Const. Equipment Rate	Material Supply Cost	Labor Supply Cost	Const. Equipment Cost	TOTAL
Comp 17. New Rochelle Landing to Hempstead Harbor Landing (Shore Road) 345kV Offshore Submarine Cables - Three circuits (three lines, single circuit each)EGC-Dunwoodie 345KV / EGC-SprainBrook 345KV/ Rula										
1. SUBMARINE CABLE										
1.1	Submarine Cable - 1600 mm2 Tri-Core + Vessel Install	300,390	FT	\$ 537	\$ 400	\$ 250	\$ 161,309,301	\$ 120,155,904	\$ 75,097,440	\$ 356,562,645
1.2	Submarine Cable- transportation from manufacture location to site	1	LS		\$ 15,203,818	\$ 10,135,879	\$ -	\$ 15,203,818	\$ 10,135,879	\$ 25,339,697
1.3	Submarine Cable Splicing if Required 1600 mm2 Tri-Core	-	EA				\$ -	\$ -	\$ -	\$ -
1.5	Cable Transition Splice	8	EA	\$ 27,911	\$ 37,214	\$ 27,911	\$ 223,286	\$ 297,715	\$ 223,286	\$ 744,286
1.6	Outdoor Termination	8	EA	\$ 27,911	\$ 37,214	\$ 27,911	\$ 223,286	\$ 297,715	\$ 223,286	\$ 744,286
1.7	"Shore End" (shallow) Diver Cable Install						\$ -	\$ -	\$ -	\$ -
1.8	Fiber Optic Cable	100,130	FT	\$ 7			\$ 740,661	\$ -	\$ -	\$ 740,661
1.9	Ground Continuity Conductor	100,130	FT	\$ 13			\$ 1,305,594	\$ -	\$ -	\$ 1,305,594
1.10							\$ -	\$ -	\$ -	\$ -
1.11	Jack and Bore along Route	0	LF	\$ 1,600	\$ 3,200	\$ 3,200	\$ -	\$ -	\$ -	\$ -
1.12	HDD along Route	4,342	LF	\$ 1,600	\$ 3,200	\$ 3,200	\$ 6,947,200	\$ 13,894,400	\$ 13,894,400	\$ 34,736,000
TOTAL - Submarine cable:							\$ 170,749,328	\$ 149,849,551	\$ 99,574,291	\$ 420,173,170
2. TRANSITION STATION										
2.1	Site Clearing	1.5	ACRE	-	10,800.00	7,200.00	\$ -	\$ 16,200	\$ 10,800	\$ 27,000
2.2	Demolition	0	LS	-	60,000.00	40,000.00	\$ -	\$ -	\$ -	\$ -
2.3	Strip and Dispose Top Soil	2,420	CY		24.50	10.50	\$ -	\$ 59,290	\$ 25,410	\$ 84,700
2.4	Site Grading- Excavation for Substation Pad	7,260	CY		9.00	6.00	\$ -	\$ 65,340	\$ 43,560	\$ 108,900
2.5	Site Grading- Excavation for Substation Pad-Rock excavation-Hauling and disposal	3,920	CY		21.00	9.00	\$ -	\$ 82,328.40	\$ 35,283.60	\$ 117,612.00
2.6	Site Grading- Fill for Substation Pad (site borrow, compacted in place)	5,881	CY		2.40	1.60	\$ -	\$ 14,113	\$ 9,409	\$ 23,522
2.7	Site Grading -Fill for Substation Pad (import, compacted in place)	3,920	CY	25.00	2.40	1.60	\$ 98,010	\$ 9,409	\$ 6,273	\$ 113,692
2.8	Install substation 8" pad base	7,260	SY	11.00	6.00	4.00	\$ 79,860	\$ 43,560	\$ 29,040	\$ 152,460
2.9	Site Surfacing - Aggregate 6" Thick	7,260	SY	16.50	4.50	3.00	\$ 119,790	\$ 32,670	\$ 21,780	\$ 174,240
2.10	7' Station Fence w/ Barbed Wire & Grounding	1,350	LF	13.85	13.85	6.92	\$ 18,695	\$ 18,695	\$ 9,347	\$ 46,737
2.11	20' Slide Gate & Grounding	3	EA	8,100.00	3,245.00	1,305.00	\$ 24,300	\$ 9,735	\$ 3,915	\$ 37,950
2.12	4' Pedestrian gate	3	EA	2,500.00	1,000.00	350.00	\$ 7,500	\$ 3,000	\$ 1,050	\$ 11,550
2.13	Erosion Control-Silt fence install & remove	2,250	LF	2.41	3.16	0.72	\$ 5,423	\$ 7,110	\$ 1,620	\$ 14,153
2.14	Temporary fencing	1,500	LF	7.50	5.25	2.25	\$ 11,250	\$ 7,875	\$ 3,375	\$ 22,500
2.15	345kV, Cable sealing end - 3 Ph	96	CY	703.89	804.44	502.78	\$ 67,784	\$ 77,468	\$ 48,417	\$ 193,669
2.16	345kV, lighting arrester	96	CY	703.89	804.44	502.78	\$ 67,784	\$ 77,468	\$ 48,417	\$ 193,669
2.17	345kV, Cable sealing end - 3 Ph	18	EA	8,346.00	5,758.74	3,839.16	\$ 150,228	\$ 103,657	\$ 69,105	\$ 322,990
2.18	345kV, lighting arrester	18	EA	4,810.00	2,886.00	1,924.00	\$ 86,580	\$ 51,948	\$ 34,632	\$ 173,160
2.19	AL. Bus Tubing, 5" SCH 80	630	LF	25.00	184.94	123.29	\$ 15,750	\$ 116,511	\$ 77,674	\$ 209,935
2.20	AL. Bus fittings	1	LS	12,600.00	12,600.00	6,300.00	\$ 12,600	\$ 12,600	\$ 6,300	\$ 31,500
2.21	Cable, 4/0 AWG Bare Copper, 7 Strand Ground Conductor	400	LF	2.09	-	-	\$ 836	\$ -	\$ -	\$ 836

Item	Item Description	Estimated Quantity	Unit of Measure	Material Supply Rate	Labor Supply Rate	Const. Equipment Rate	Material Supply Cost	Labor Supply Cost	Const. Equipment Cost	TOTAL
2.22	Caweld, DSA, 4/0 , T, CROSS	200	EA	165.00	75.00		\$ 33,000	\$ 15,000	\$ -	\$ 48,000
2.23	Ground Rod, 3/4" x 15'	54	EA	135.00	67.50	7.50	\$ 7,290	\$ 3,645	\$ 405	\$ 11,340
2.24	Trench Box Shoring (Vault)	12	EA	\$ -	\$ 18,079	\$ 27,119	\$ -	\$ 216,949	\$ 325,424	\$ 542,373
2.25	Splice Vault Excavation	7,765	CY		\$ 17.5	\$ 7.5	\$ -	\$ 135,893	\$ 58,240	\$ 194,133
2.26	Splice Vault Supply & Installation	12	EA	\$ 45,500	\$ 21,450	\$ 50,050	\$ 546,000	\$ 257,400	\$ 600,600	\$ 1,404,000
2.27	Splice Vault Backfill	2,330	CY		\$ 14.0	\$ 6.0	\$ -	\$ 32,614	\$ 13,978	\$ 46,592
2.28	Restoration (incl. Paving)	1	LS	\$ 15,000.00	\$ 20,000.00	\$ 15,000.00	\$ 15,000	\$ 20,000	\$ 15,000	\$ 50,000
2.29	Additional misc. testing allowance (Native Backfill, Asphalt Density, Concrete Curb etc.)	1	LS		\$ 35,000	\$ 15,000	\$ -	\$ 35,000	\$ 15,000	\$ 50,000
2.30	Excess Materials Disposal to Certified Backfill	7,066	CY		\$ 24.5	\$ 10.5	\$ -	\$ 173,128	\$ 74,198	\$ 247,326
2.31	Rock Excavation and Removal	1	LS				\$ -	\$ -	\$ -	\$ -
2.32	Dewatering	12	EA			\$ 4,000	\$ -	\$ -	\$ 48,000	\$ 48,000
2.33	Contaminated Water Treatment and Disposal	1	LS				\$ -	\$ -	\$ -	\$ -
2.34	Contaminated Spoils Disposal	1	LS				\$ -	\$ -	\$ -	\$ -
2.35	Excavated material - stockpile management	7,765	CF		\$ 1.0	\$ 0.5	\$ -	\$ 7,765	\$ 3,883	\$ 11,648
2.36							\$ -	\$ -	\$ -	\$ -
TOTAL - Transition station :							\$ 1,367,680	\$ 1,706,372	\$ 1,640,135	\$ 4,714,187
Comp 17. New Rochelle Landing to Hempstead Harbor Landing (Shore Road) 345kV Offshore Submarine Cables							\$ 172,117,008	\$ 151,555,924	\$ 101,214,425	\$ 424,887,357
3. MOB/DEMOB, ENGINEERING, PERMITTING, T&C, PM & INDIRECTS:										
	Contractor Mobilization / Demobilization									
3.1	Mob / Demob	1	LS		\$ 6,000,000	\$ 4,000,000	\$ -	\$ 6,000,000	\$ 4,000,000	\$ 10,000,000
	Project Management, Material Handling & Amenities									
3.2	Preconstruction Supervision (Engineering, Permitting, Procurement)	1	LS		4,248,873.57		\$ -	\$ 4,248,874	\$ -	\$ 4,248,874
3.3	Project Management & Staffing (includes PM, Field Engineers / Supervision, Scheduler and Cost Manager, SHEQ Staff, and Admin Staff)	1	LS		16,995,494.27		\$ -	\$ 16,995,494	\$ -	\$ 16,995,494
3.4	Utility PM and Project Oversight	1	LS		4,248,873.57		\$ -	\$ 4,248,874	\$ -	\$ 4,248,874
3.5	Site Accommodation, Facilities, Storage	1	LS	4,248,873.57			\$ 4,248,874	\$ -	\$ -	\$ 4,248,874
	Engineering									
3.6	Design Engineering	1	LS		\$ 21,244,368		\$ -	\$ 21,244,368	\$ -	\$ 21,244,368
3.7	Surveying/Staking	1	LS		\$ 2,974,211		\$ -	\$ 2,974,211	\$ -	\$ 2,974,211
3.8	Geotech	10.00	EA		2,730.00	1,820.00	\$ -	\$ 27,300	\$ 18,200	\$ 45,500
	Testing & Commissioning / Inspection									
3.9	Testing & Commissioning / End to End Testing of Subsea Cable	1	EA		\$ 60,000		\$ -	\$ 60,000	\$ -	\$ 60,000
3.10	Post Cable-Lay Inspection		EA				\$ -	\$ -	\$ -	\$ -
	Permitting and Additional Costs									
3.10	Environmental Licensing & Permitting Costs & related legal cost	1	LS		\$ 4,248,874		\$ -	\$ 4,248,874	\$ -	\$ 4,248,874
3.11	Environmental-special studies/investigation	1	LS		\$ 370,000		\$ -	\$ 370,000	\$ -	\$ 370,000
3.12	Warranties / LOC's	1	LS		\$ 1,274,662		\$ -	\$ 1,274,662	\$ -	\$ 1,274,662
3.13	Laydown Lease	1	LS		\$ -	\$ 500,000	\$ -	\$ -	\$ 500,000	\$ 500,000
3.14	Real Estate ( Acquisition)	1	LS		\$ -	\$ 868,559	\$ -	\$ -	\$ 868,559	\$ 868,559
3.15	Legal Fees (Real estate)	1.00	LS		-	26,056.77	\$ -	\$ -	\$ 26,057	\$ 26,057
3.16	Insurance	-	LS		-	-	\$ -	\$ -	\$ -	\$ -
3.17	Insurance (specialty, e.g. railroad)		Crossing				\$ -	\$ -	\$ -	\$ -
3.18	Allowance for Funds Used During Construction (AFUDC)		LS				\$ -	\$ -	\$ -	\$ -
3.19	Sales Tax on Materials	8.8%	LS	\$ 172,117,008			\$ 15,146,297	\$ -	\$ -	\$ 15,146,297
3.20	Contractor Permits	1	LS		\$ 424,887		\$ -	\$ 424,887	\$ -	\$ 424,887
3.21	Payment & Performance Bond	1	LS			\$ 14,900,000	\$ -	\$ -	\$ 14,900,000	\$ 14,900,000
3.22	Marine / Specialty Insurance		LS				\$ -	\$ -	\$ -	\$ -
TOTAL - MOB/DEMOB, ENGINEERING, PERMITTING, T&C, PM & INDIRECTS:							\$ 19,395,170	\$ 62,117,544	\$ 20,312,816	\$ 101,825,530

<p align="center"><b><u>NEXtera Energy- TO36 Core 1</u></b></p> <p align="center"><b><u>Comp 3A - East Garden City To Hempstead Harbor Landing 345kV Onshore UG Cables -Double circuits</u></b></p> <p align="center"><b><u>(EGC To Sprain Brook 345 kV / EGC To Dunwoodie 345 kV)</u></b></p>	
Total:	\$ 385,634,343

NEXtera Energy- TO36 Core 1				
	Material Supply	Labor Supply	Equip Supply	Total
<b>Comp 3A - East Garden City To Hempstead Harbor Landing 345kV Onshore UG Cables -Double circuits (EGC To Sprain Brook 345 kV / EGC To Dunwoodie 345 kV)</b>				
1. SITE PREP/ACCESS/TRAFFIC MANAGEMENT	\$ 2,553,664	\$ 12,590,558	\$ 5,026,706	\$ 20,170,928
2. ONSHORE CABLE CONDUITS & VAULTS INSTALLATION	\$ 32,756,973	\$ 23,529,781	\$ 14,478,636	\$ 70,765,391
3. ONSHORE CABLE PROCUREMENT AND INSTALLATION	\$ 63,187,504	\$ 38,177,910	\$ 24,731,740	\$ 126,097,154
4. MOB/DEMOB, ENGINEERING, PERMITTING, T&C, PM & INDIRECTS	\$ 10,916,970	\$ 33,123,408	\$ 11,266,787	\$ 55,307,165
SUBTOTAL (Costs):	\$ 109,415,111	\$ 107,421,657	\$ 55,503,869	\$ 272,340,638
CONTRACTOR MARK-UP (OH&P)	\$ 19,694,720	\$ 19,335,898	\$ 9,990,696	\$ 49,021,315
SUBTOTAL:	\$ 129,109,831	\$ 126,757,556	\$ 65,494,565	\$ 321,361,952
CONTINGENCY ON ENTIRE PROJECT	\$ 25,821,966	\$ 25,351,511	\$ 13,098,913	\$ 64,272,390
TOTAL:	\$ 154,931,797	\$ 152,109,067	\$ 78,593,479	\$ 385,634,343

Description of Work: East Garden City - Hempstead Harbor Landing (Shore Road, double circuits). 5000 kcmil copper XLPE, single cable per phase.										
Item	Item Description	Estimated Quantity	Unit of Measure	Material Supply Rate	Labor Supply Rate	Const. Equipment Rate	Material Supply Cost	Labor Supply Cost	Const. Equipment Cost	TOTAL
Comp 3A - East Garden City To Hempstead Harbor Landing 345kV Onshore UG Cables -Double circuits(EGC To Sprain Brook 345 kV / EGC To Dunwoodie 345 kV)										
1. SITE PREP/ACCESS/TRAFFIC MANAGEMENT										
1.1	Environmental BMPs / SWPPP Installation, Maintenance & Repairs	0	LF	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
1.2	Existing Utility Conflict and Relocation	10.21	Mile		\$ 700,000	\$ 300,000	\$ -	\$ 7,147,000	\$ 3,063,000	\$ 10,210,000
1.3	Flaggers	330	DAY	\$ 1,600	\$ 4,800	\$ 1,600	\$ 528,000	\$ 1,584,000	\$ 528,000	\$ 2,640,000
1.4	K Rail / Lane Control / Metal Plates	53,909	LF	\$ 30	\$ 18	\$ 12	\$ 1,617,264	\$ 970,358	\$ 646,906	\$ 3,234,528
1.5	Police Support	13,200.0	HR		\$ 120	\$ 27	\$ -	\$ 1,584,000	\$ 356,400	\$ 1,940,400
1.6	Additional Traffic Management		LS				\$ -	\$ -	\$ -	\$ -
1.7	Access / Clearing Costs		LS				\$ -	\$ -	\$ -	\$ -
1.8	Snow Removal	80.0	DAY		\$ 1,000	\$ 300	\$ -	\$ 80,000	\$ 24,000	\$ 104,000
1.9	Existing Utility Protection	10.21	Mile	\$ 40,000	\$ 120,000	\$ 40,000	\$ 408,400	\$ 1,225,200	\$ 408,400	\$ 2,042,000
TOTAL - SITE PREP/ACCESS/TRAFFIC MANAGEMENT/ ACCESS:							\$ 2,553,664	\$ 12,590,558	\$ 5,026,706	\$ 20,170,928
2. ONSHORE CABLE CONDUITS & VAULTS INSTALLATION										
EGC-SP & RL-DW -Double CIRCUITS										
2.1	Trench Box Shoring & Trench Box Install Crew	10.21	Miles		\$ 139,800	\$ 93,200	\$ -	\$ 1,427,358	\$ 951,572	\$ 2,378,930
2.2	Formwork in Trench	431,270	SF	\$ 2	\$ 1.5	\$ 0.5	\$ 862,541	\$ 646,906	\$ 215,635	\$ 1,725,082
2.3	Trench Excavation	67,885	CY		\$ 17.5	\$ 7.5	\$ -	\$ 1,187,990	\$ 509,139	\$ 1,697,129
2.4	Supply & Install 6" Sand Bedding for direct bury conduits	4,243	CY	\$ 50	\$ 25	\$ 14	\$ 212,141	\$ 103,949	\$ 59,400	\$ 375,490
2.5	Supply & Install Thermal Backfill -conduit level	35,640	CY	\$ 350	\$ 245	\$ 105	\$ 12,473,897	\$ 8,731,728	\$ 3,742,169	\$ 24,947,795
2.6	Supply & Install Concrete Cap (6")	0	CY	\$ 200	\$ 125	\$ 50	\$ -	\$ -	\$ -	\$ -
2.7	Supply & Install Native Backfill -direct bury conduits sys	0	CY	\$ 350	\$ 245.0	\$ 105.0	\$ -	\$ -	\$ -	\$ -
2.8	Supply & Install Ductbank Concrete	16,604	CY	\$ 200	\$ 125.0	\$ 50.0	\$ 3,320,782	\$ 2,075,489	\$ 830,196	\$ 6,226,466
2.8	Conduit 8" SCH 40PVC	431,270	LF	\$ 28.6	\$ 5.7	\$ 2.4	\$ 12,334,333	\$ 2,445,303	\$ 1,047,987	\$ 15,827,624
2.9	Conduit 4" SCH 40PVC	0	LF	\$ 9.8	\$ 4.20	\$ 1.8	\$ -	\$ -	\$ -	\$ -
2.10	Conduit 2" SCH 40PVC	215,635	LF	\$ 3.5	\$ 3.15	\$ 1.4	\$ 759,036	\$ 679,251	\$ 291,108	\$ 1,729,394
2.11	Warning Tape	53,909	LF	\$ 0.15	\$ 0.25	\$ 0.10	\$ 8,086	\$ 5,391	\$ 5,391	\$ 26,954
2.12	Trench Box Shoring (Vault)	60	EA	\$ -	\$ 18,079	\$ 27,119	\$ -	\$ 1,084,746	\$ 1,627,119	\$ 2,711,864

Item	Item Description	Estimated Quantity	Unit of Measure	Material Supply Rate	Labor Supply Rate	Const. Equipment Rate	Material Supply Cost	Labor Supply Cost	Const. Equipment Cost	TOTAL
2.13	Splice Vault Excavation	9,973	CY		\$ 17.5	\$ 7.5	\$ -	\$ 174,533	\$ 74,800	\$ 249,333
2.14	Splice Vault Supply & Installation	60	EA	\$ 35,000	\$ 16,500	\$ 38,500	\$ 2,100,000	\$ 990,000	\$ 2,310,000	\$ 5,400,000
2.15	Splice Vault Backfill	2,992	CY		\$ 14.0	\$ 6.0	\$ -	\$ 41,888	\$ 17,952	\$ 59,840
2.16	Jack and Bore along Route	0	LF	\$ 800	\$ 1,600	\$ 1,600	\$ -	\$ -	\$ -	\$ -
2.17	HDD along Route	0	LF	\$ 800	\$ 1,600	\$ 1,600	\$ -	\$ -	\$ -	\$ -
2.18	Air Test Ducts	646,906	LF			\$ 0.25	\$ -	\$ -	\$ 161,726	\$ 161,726
2.20	PVMT, ASPHALT, 2" SURFACE COURSE	33,940	SY	\$ 14.00	\$ 14.00	\$ 7.00	\$ 475,162	\$ 475,162	\$ 237,581	\$ 1,187,905
2.21	PVMT, AGGREGATE, 10", BASE COURSE	9,428	CY	\$ 22.38	\$ 23.50	\$ 10.07	\$ 210,994	\$ 221,544	\$ 94,948	\$ 527,486
2.20	Concrete Ductbank Thermal Resistivity Testing (every 100CY of concrete poured)	166	EA		\$ 400	\$ 1,200	\$ -	\$ 66,416	\$ 199,247	\$ 265,663
2.21	Concrete Ductbank Compressive Strength Testing (every 100CY of concrete poured)	166	EA		\$ 10	\$ 15	\$ -	\$ 1,660	\$ 2,491	\$ 4,151
2.22	Backfill Thermal Resistivity Testing (every 100CY of backfill placed)	356	EA		\$ 400	\$ 1,200	\$ -	\$ 142,559	\$ 427,676	\$ 570,235
2.25	Additional misc. testing allowance (Native Backfill, Asphalt Density, Concrete Curb etc.)	1	LS		\$ 557,466	\$ 371,644	\$ -	\$ 557,466	\$ 371,644	\$ 929,110
2.24	Excess Materials Disposal to Certified Backfill	97,326	CY		\$ 24.5	\$ 10.5	\$ -	\$ 2,384,498	\$ 1,021,928	\$ 3,406,425
2.25	Rock Excavation and Removal	1	LS				\$ -	\$ -	\$ -	\$ -
2.26	Dewatering	60	EA			\$ 4,000	\$ -	\$ -	\$ 240,000	\$ 240,000
2.27	Contaminated Water Treatment and Disposal	1	LS				\$ -	\$ -	\$ -	\$ -
2.28	Contaminated Spoils Disposal	1	LS				\$ -	\$ -	\$ -	\$ -
2.29	Excavated material - stockpile management	77,858	CF		\$ 1.0	\$ 0.5	\$ -	\$ 77,858	\$ 38,929	\$ 116,788
TOTAL - ONSHORE CABLE CONDUITS & VAULTS INSTALLATION:							\$ 32,756,973	\$ 23,529,781	\$ 14,478,636	\$ 70,765,391
3. ONSHORE CABLE PROCUREMENT AND INSTALLATION										
3.1	Circuit #1- Procurement & Installation- 345kV 5000 kcmil copper XLPE	169,813	FT	\$ 167	\$ 100	\$ 67	\$ 28,358,724	\$ 17,015,235	\$ 11,343,490	\$ 56,717,448
3.2	Circuit #1- Cable Splicing- 345kV 5000 kcmil copper XLPE	90	EA	\$ 11,722	\$ 9,846	\$ 2,813	\$ 1,054,980	\$ 886,183	\$ 253,195	\$ 2,194,358
3.3	Circuit #1- Cable Termination- 345kV 5000 kcmil copper XLPE	6	EA	\$ 27,805	\$ 9,846	\$ 2,813	\$ 166,830	\$ 59,079	\$ 16,880	\$ 242,789
3.4	Circuit #2- Procurement & Installation- 345kV 5000 kcmil copper XLPE	169,813	FT	\$ 167	\$ 100	\$ 67	\$ 28,358,724	\$ 17,015,235	\$ 11,343,490	\$ 56,717,448
3.5	Circuit #2- Cable Splicing- 345kV 5000 kcmil copper XLPE	90	EA	\$ 11,722	\$ 9,846	\$ 2,813	\$ 1,054,980	\$ 886,183	\$ 253,195	\$ 2,194,358
3.6	Circuit #2- Cable Termination- 345kV 5000 kcmil copper XLPE	6	EA	\$ 27,805	\$ 9,846	\$ 2,813	\$ 166,830	\$ 59,079	\$ 16,880	\$ 242,789
3.7	Circuit #3- Procurement & Installation- 345kV 5000 kcmil copper XLPE		FT	\$ 167	\$ 100	\$ 67	\$ -	\$ -	\$ -	\$ -
3.8	Circuit #3- Cable Splicing- 345kV 5000 kcmil copper XLPE		EA	\$ 11,722	\$ 9,846	\$ 2,813	\$ -	\$ -	\$ -	\$ -
3.9	Circuit #3- Cable Termination- 345kV 5000 kcmil copper XLPE		EA	\$ 27,805	\$ 9,846	\$ 2,813	\$ -	\$ -	\$ -	\$ -
3.10	Link Box & MH racking	60	EA	\$ 28,548	\$ 17,129	\$ 11,419	\$ 1,712,907	\$ 1,027,744	\$ 685,163	\$ 3,425,814
3.11	Fiber Optic Cable	113,208	FT	\$ 7	\$ 3	\$ 2	\$ 837,403	\$ 377,052	\$ 251,368	\$ 1,465,823
3.12	Ground Continuity Conductor	113,208	FT	\$ 13	\$ 8	\$ 5	\$ 1,476,125	\$ 852,120	\$ 568,080	\$ 2,896,326
TOTAL - ONSHORE CABLE PROCUREMENT AND INSTALLATION							\$ 63,187,504	\$ 38,177,910	\$ 24,731,740	\$ 126,097,154
Comp 3A - East Garden City To Hempstead Harbor Landing 345kV Onshore UG Cables -Double circuits(EGC To Sprain Brook 345 kV / EGC To Dunwoodie 345kV)							\$ 98,498,141	\$ 74,298,250	\$ 44,237,082	\$ 217,033,473
4. MOB/DEMOB, ENGINEERING, PERMITTING, T&C, PM & INDIRECTS										
	Contractor Mobilization / Demobilization									
4.1	Mob / Demob	1	LS		\$ 3,556,060	\$ 2,370,707	\$ -	\$ 3,556,060	\$ 2,370,707	\$ 5,926,767
	Project Management, Material Handling & Amenities									
4.2	Preconstruction Supervision (Engineering, Permitting, Procurement)	1	LS		2,170,334.73		\$ -	\$ 2,170,335	\$ -	\$ 2,170,335
4.3	Project Management & Staffing (includes PM, Field Engineers / Supervision, Scheduler and Cost Manager, SHEQ Staff, and Admin Staff)	1	LS		8,681,338.90		\$ -	\$ 8,681,339	\$ -	\$ 8,681,339
4.4	Utility PM and Project Oversight	1	LS		2,170,334.73		\$ -	\$ 2,170,335	\$ -	\$ 2,170,335
4.5	Site Accommodation, Facilities, Storage	1	LS	2,170,334.73			\$ 2,170,335	\$ -	\$ -	\$ 2,170,335
	Engineering									
4.6	Design Engineering	1.0	LS		\$ 10,851,674	\$ -	\$ -	\$ 10,851,674	\$ -	\$ 10,851,674
4.7	LiDAR /GPR	1.0	LS		\$ 390,660	\$ 260,440	\$ -	\$ 390,660	\$ 260,440	\$ 651,100
4.8	Geotech	11.00	EA		2,730.00	1,820.00	\$ -	\$ 30,030	\$ 20,020	\$ 50,050
4.9	Surveying/Staking	1	LS		\$ 911,541	\$ 607,694	\$ -	\$ 911,541	\$ 607,694	\$ 1,519,234
	Testing & Commissioning									
4.10	Testing & Commissioning of T-Line and Equipment	1	EA		\$ 40,000		\$ -	\$ 40,000	\$ -	\$ 40,000
	Permitting, Indirects and Additional Costs									
4.11	Environmental Licensing & Permitting Costs & related legal cost	1	LS		\$ 2,170,335		\$ -	\$ 2,170,335	\$ -	\$ 2,170,335
4.12	Environmental-special studies/investigation		LS		\$ -		\$ -	\$ -	\$ -	\$ -
4.13	Warranties / LOC's	1	LS		\$ 651,100		\$ -	\$ 651,100	\$ -	\$ 651,100
4.14	Laydown Lease & temporary easement	1	LS		\$ 1,500,000		\$ -	\$ 1,500,000	\$ -	\$ 1,500,000
4.15	Real Estate ( Acquisition)	1	LS			\$ 88,246	\$ -	\$ -	\$ 88,246	\$ 88,246
4.16	Legal Fees (Real estate)	1.00	LS		-	2,647.38	\$ -	\$ -	\$ 2,647	\$ 2,647
4.17	Insurance	-	LS		-	-	\$ -	\$ -	\$ -	\$ -
4.18	Insurance (specialty, e.g. railroad)		Crossing			\$ 1,000	\$ -	\$ -	\$ -	\$ -
4.19	Bonds	1	LS			\$ 7,700,000	\$ -	\$ -	\$ 7,700,000	\$ 7,700,000
4.20	Sales Tax on Materials	8.88%	% of material cost	\$ 98,498,141.33			\$ 8,746,635	\$ -	\$ -	\$ 8,746,635

Item	Item Description	Estimated Quantity	Unit of Measure	Material Supply Rate	Labor Supply Rate	Const. Equipment Rate	Material Supply Cost	Labor Supply Cost	Const. Equipment Cost	TOTAL
4.21	Fees for permits, including roadway, railroad, building or other local permits	1	LS			\$ 217,033	\$ -	\$ -	\$ 217,033	\$ 217,033
TOTAL - MOB/DEMOB, ENGINEERING, PERMITTING, T&C, PM & INDIRECTS:							\$ 10,916,970	\$ 33,123,408	\$ 11,266,787	\$ 55,307,165



<p align="center"><b><u>NEXtera Energy- TO36 Core 1</u></b></p> <p align="center"><b><u>Comp 5 - Ruland To Hempstead Harbor Landing (Shore Road) 345kV Onshore UG Cables -Single circuit</u></b></p> <p align="center"><b><u>(Ruland To Sprain Brook 345 kV)</u></b></p>	
Total:	\$ 349,868,481

	<b>Total:</b> \$    349,868,481
--	---------------------------------

NEXtera Energy- TO36 Core 1				
	Material Supply	Labor Supply	Equip Supply	Total
Comp 5 - Ruland To Hempstead Harbor Landing (Shore Road) 345kV Onshore UG Cables -Single circuit(Ruland To Sprain Brook 345 kV)				
1. SITE PREP/ACCESS/TRAFFIC MANAGEMENT	\$ 3,951,782	\$ 19,416,325	\$ 7,771,777	\$ 31,139,885
2. ONSHORE CABLE CONDUITS & VAULTS INSTALLATION	\$ 28,082,043	\$ 23,492,789	\$ 15,680,897	\$ 67,255,729
3. ONSHORE CABLE PROCUREMENT AND INSTALLATION	\$ 49,212,741	\$ 29,776,525	\$ 19,277,107	\$ 98,266,373
4. MOB/DEMOB, ENGINEERING, PERMITTING, T&C, PM & INDIRECTS	\$ 9,181,315	\$ 30,875,539	\$ 10,363,420	\$ 50,420,274
SUBTOTAL (Costs):	\$ 90,427,881	\$ 103,561,178	\$ 53,093,201	\$ 247,082,261
CONTRACTOR MARK-UP (OH&P)	\$ 16,277,019	\$ 18,641,012	\$ 9,556,776	\$ 44,474,807
SUBTOTAL:	\$ 106,704,900	\$ 122,202,190	\$ 62,649,977	\$ 291,557,067
CONTINGENCY ON ENTIRE PROJECT	\$ 21,340,980	\$ 24,440,438	\$ 12,529,995	\$ 58,311,413
TOTAL:	\$ 128,045,880	\$ 146,642,628	\$ 75,179,973	\$ 349,868,481

Description of Work: Ruland - Hempstead Harbor Landing (Shore Road, single circuit). 5000 kcmil copper XLPE, single cable per phase..										
Item	Item Description	Estimated Quantity	Unit of Measure	Material Supply Rate	Labor Supply Rate	Const. Equipment Rate	Material Supply Cost	Labor Supply Cost	Const. Equipment Cost	TOTAL
Comp 5 - Ruland To Hempstead Harbor Landing (Shore Road) 345kV Onshore UG Cables -Single circuit(Ruland To Sprain Brook 345 kV)										
1. SITE PREP/ACCESS/TRAFFIC MANAGEMENT										
1.1	Environmental BMPs / SWPPP Installation, Maintenance & Repairs	0	LF	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
1.2	Existing Utility Conflict and Relocation	15.89	Mile		\$ 700,000	\$ 300,000	\$ -	\$ 11,120,200	\$ 4,765,800	\$ 15,886,000
1.3	Flaggers	500	DAY	\$ 1,600	\$ 4,800	\$ 1,600	\$ 800,000	\$ 2,400,000	\$ 800,000	\$ 4,000,000
1.4	K Rail / Lane Control / Metal Plates	83,878	LF	\$ 30	\$ 18	\$ 12	\$ 2,516,342	\$ 1,509,805	\$ 1,006,537	\$ 5,032,685
1.5	Police Support	20,000.0	HR		\$ 120	\$ 27	\$ -	\$ 2,400,000	\$ 540,000	\$ 2,940,000
1.6	Additional Traffic Management		LS				\$ -	\$ -	\$ -	\$ -
1.7	Access / Clearing Costs		LS				\$ -	\$ -	\$ -	\$ -
1.8	Snow Removal	80.0	DAY		\$ 1,000	\$ 300	\$ -	\$ 80,000	\$ 24,000	\$ 104,000
1.9	Existing Utility Protection	15.89	Mile	\$ 40,000	\$ 120,000	\$ 40,000	\$ 635,440	\$ 1,906,320	\$ 635,440	\$ 3,177,200
TOTAL - SITE PREP/ACCESS/TRAFFIC MANAGEMENT/ ACCESS:							\$ 3,951,782	\$ 19,416,325	\$ 7,771,777	\$ 31,139,885
2. ONSHORE CABLE CONDUITS & VAULTS INSTALLATION										
2.1	Trench Box Shoring & Trench Box Install Crew	15.89	Miles		\$ 139,800	\$ 93,200	\$ -	\$ 2,220,863	\$ 1,480,575	\$ 3,701,438
2.2	Formwork in Trench	643,225	SF	\$ 2	\$ 1.5	\$ 0.5	\$ 1,286,449	\$ 964,837	\$ 321,612	\$ 2,572,899
2.3	Trench Excavation	53,602	CY		\$ 17.5	\$ 7.5	\$ -	\$ 938,036	\$ 402,015	\$ 1,340,051
2.4	Supply & Install 6" Sand Bedding for direct bury conduits	3,350	SF	\$ 50	\$ 25	\$ 14	\$ 167,506	\$ 82,078	\$ 46,902	\$ 296,486
2.5	Supply & Install Thermal Backfill	28,141	CY	\$ 350	\$ 245	\$ 105	\$ 9,849,377	\$ 6,894,564	\$ 2,954,813	\$ 19,698,755
2.6	Supply & Install Concrete Cap (6")	0	CY	\$ 200	\$ 125	\$ 50	\$ -	\$ -	\$ -	\$ -
2.7	Native Backfill -direct bury conduits sys Trench	0	CY		\$ 14.0	\$ 6.0	\$ -	\$ -	\$ -	\$ -
2.8	Supply & Install Ductbank Concrete	13,101	CY	\$ 200	\$ 125	\$ 50	\$ 2,620,247	\$ 1,637,654	\$ 655,062	\$ 4,912,963
2.9	Conduit 8" SCH 40PVC	335,512	LF	\$ 28.6	\$ 5.7	\$ 2.4	\$ 9,595,652	\$ 1,902,355	\$ 815,295	\$ 12,313,302
2.10	Conduit 4" SCH 40PVC	0	LF	\$ 9.8	\$ 4.20	\$ 1.8	\$ -	\$ -	\$ -	\$ -
2.11	Conduit 2" SCH 40PVC	167,756	LF	\$ 3.5	\$ 3.15	\$ 1.4	\$ 590,502	\$ 528,432	\$ 226,471	\$ 1,345,404
2.12	Warning Tape	167,756	LF	\$ 0.15	\$ 0.25	\$ 0.10	\$ 25,163	\$ 41,939	\$ 16,776	\$ 83,878
2.13	Trench Box Shoring (Vault)	49	EA	\$ -	\$ 18,079	\$ 27,119	\$ -	\$ 885,876	\$ 1,328,814	\$ 2,214,689
2.14	Splice Vault Excavation	8,145	CY		\$ 17.5	\$ 7.5	\$ -	\$ 142,536	\$ 61,087	\$ 203,622
2.15	Splice Vault Supply & Installation	49	EA	\$ 35,000	\$ 16,500	\$ 38,500	\$ 1,715,000	\$ 808,500	\$ 1,886,500	\$ 4,410,000
2.16	Splice Vault Backfill	2,443	CY		\$ 14.0	\$ 6.0	\$ -	\$ 34,209	\$ 14,661	\$ 48,869
2.17	Jack and Bore along Route	805	LF	\$ 800	\$ 1,600	\$ 1,600	\$ 644,000	\$ 1,288,000	\$ 1,288,000	\$ 3,220,000
2.18	HDD along Route	1,200	LF	\$ 800	\$ 1,600	\$ 1,600	\$ 960,000	\$ 1,920,000	\$ 1,920,000	\$ 4,800,000

Item	Item Description	Estimated Quantity	Unit of Measure	Material Supply Rate	Labor Supply Rate	Const. Equipment Rate	Material Supply Cost	Labor Supply Cost	Const. Equipment Cost	TOTAL
2.19	Air Test Ducts	503,268	LF			\$ 0.25	\$ -	\$ -	\$ 125,817	\$ 125,817
2.20	PVMT, ASPHALT, 2" SURFACE COURSE	31,071	SY	\$ 14.00	\$ 14.00	\$ 7.00	\$ 434,989	\$ 434,989	\$ 217,495	\$ 1,087,473
2.21	PVMT, AGGREGATE, 10", BASE COURSE	8,631	CY	\$ 22.38	\$ 23.50	\$ 10.07	\$ 193,156	\$ 202,814	\$ 86,920	\$ 482,890
2.22	Concrete Ductbank Thermal Resistivity Testing (every 100CY of concrete poured)	131	EA		\$ 400	\$ 1,200	\$ -	\$ 52,405	\$ 157,215	\$ 209,620
2.23	Concrete Ductbank Compressive Strength Testing (every 100CY of concrete poured)	131	EA		\$ 10	\$ 15	\$ -	\$ 1,310	\$ 1,965	\$ 3,275
2.24	Backfill Thermal Resistivity Testing (every 100CY of backfill placed)	281	EA		\$ 400	\$ 1,200	\$ -	\$ 112,564	\$ 337,693	\$ 450,257
2.25	Additional misc. testing allowance (Native Backfill, Asphalt Density, Concrete Curb etc.)	1	LS		\$ 448,266	\$ 298,844	\$ -	\$ 448,266	\$ 298,844	\$ 747,110
2.26	Excess Materials Disposal to Certified Backfill	77,095	CY		\$ 24.5	\$ 10.5	\$ -	\$ 1,888,816	\$ 809,492	\$ 2,698,308
2.27	Rock Excavation and Removal	1	LS				\$ -	\$ -	\$ -	\$ -
2.28	Dewatering	49	EA			\$ 4,000	\$ -	\$ -	\$ 196,000	\$ 196,000
2.29	Contaminated Water Treatment and Disposal	1	LS				\$ -	\$ -	\$ -	\$ -
2.30	Contaminated Spoils Disposal	1	LS				\$ -	\$ -	\$ -	\$ -
2.31	Excavated material - stockpile management	61,747	CF		\$ 1.0	\$ 0.5	\$ -	\$ 61,747	\$ 30,873	\$ 92,620
TOTAL - ONSHORE CABLE CONDUITS & VAULTS INSTALLATION:							\$ 28,082,043	\$ 23,492,789	\$ 15,680,897	\$ 67,255,729
3. ONSHORE CABLE PROCUREMENT AND INSTALLATION										
3.1	Circuit #1- Procurement & Installation- 345kV 5000 kcmil copper XLPE	264,216	FT	\$ 167	\$ 100	\$ 67	\$ 44,124,064	\$ 26,474,438	\$ 17,649,626	\$ 88,248,128
3.2	Circuit #1- Cable Splicing- 345kV 5000 kcmil copper XLPE	147	EA	\$ 11,722	\$ 9,846	\$ 2,813	\$ 1,723,134	\$ 1,447,433	\$ 413,552	\$ 3,584,119
3.3	Circuit #1- Cable Termination- 345kV 5000 kcmil copper XLPE	6	EA	\$ 27,805	\$ 9,846	\$ 2,813	\$ 166,830	\$ 59,079	\$ 16,880	\$ 242,789
3.4	Circuit #2- Procurement & Installation- 345kV 5000 kcmil copper XLPE		FT	\$ 167	\$ 100	\$ 67	\$ -	\$ -	\$ -	\$ -
3.5	Circuit #2- Cable Splicing- 345kV 5000 kcmil copper XLPE		EA	\$ 11,722	\$ 9,846	\$ 2,813	\$ -	\$ -	\$ -	\$ -
3.6	Circuit #2- Cable Termination- 345kV 5000 kcmil copper XLPE		EA	\$ 27,805	\$ 9,846	\$ 2,813	\$ -	\$ -	\$ -	\$ -
3.7	Circuit #3- Procurement & Installation- 345kV 5000 kcmil copper XLPE		FT	\$ 167	\$ 100	\$ 67	\$ -	\$ -	\$ -	\$ -
3.8	Circuit #3- Cable Splicing- 345kV 5000 kcmil copper XLPE		EA	\$ 11,722	\$ 9,846	\$ 2,813	\$ -	\$ -	\$ -	\$ -
3.9	Circuit #3- Cable Termination- 345kV 5000 kcmil copper XLPE		EA	\$ 27,805	\$ 9,846	\$ 2,813	\$ -	\$ -	\$ -	\$ -
3.10	Link Box & MH racking	49	EA	\$ 28,548	\$ 17,129	\$ 11,419	\$ 1,398,874	\$ 839,324	\$ 559,550	\$ 2,797,748
3.11	Fiber Optic Cable	88,072	FT	\$ 7	\$ 3	\$ 2	\$ 651,468	\$ 293,333	\$ 195,555	\$ 1,140,356
3.12	Ground Continuity Conductor	88,072	FT	\$ 13	\$ 8	\$ 5	\$ 1,148,371	\$ 662,918	\$ 441,945	\$ 2,253,234
TOTAL - INSULATORS, FITTINGS, HARDWARE:							\$ 49,212,741	\$ 29,776,525	\$ 19,277,107	\$ 98,266,373
Comp 4 - Dunwoodie To New Rochelle Landing 345kV Onshore UG Cables -single circuit(EGC To Dunwoodie 345 kV)							\$ 81,246,566	\$ 72,685,639	\$ 42,729,781	\$ 196,661,987
4. MOB/DEMOB, ENGINEERING, PERMITTING, T&C, PM & INDIRECTS										
	Contractor Mobilization / Demobilization									
4.1	Mob / Demob	1	LS		\$ 3,462,463	\$ 2,308,308	\$ -	\$ 3,462,463	\$ 2,308,308	\$ 5,770,771
	Project Management, Material Handling & Amenities									
4.2	Preconstruction Supervision (Engineering, Permitting, Procurement)	1	LS		1,966,619.87		\$ -	\$ 1,966,620	\$ -	\$ 1,966,620
4.3	Construction Project Management / Supervision	1	LS		7,866,479.47		\$ -	\$ 7,866,479	\$ -	\$ 7,866,479
4.4	Utility PM and Project Oversight	1	LS		1,966,619.87		\$ -	\$ 1,966,620	\$ -	\$ 1,966,620
4.5	Site Accommodation, Facilities, Storage	1	LS	1,966,619.87			\$ 1,966,620	\$ -	\$ -	\$ 1,966,620
	Engineering									
4.6	Design Engineering	1.0	LS		\$ 9,833,099	\$ -	\$ -	\$ 9,833,099	\$ -	\$ 9,833,099
4.7	LiDAR /GPR	1.0	LS		\$ 353,992	\$ 235,994	\$ -	\$ 353,992	\$ 235,994	\$ 589,986
4.8	Geotech	16.00	EA		2,730.00	1,820.00	\$ -	\$ 43,680	\$ 29,120	\$ 72,800
4.9	Surveying/Staking	1	LS		\$ 825,980	\$ 550,654	\$ -	\$ 825,980	\$ 550,654	\$ 1,376,634
	Testing & Commissioning									
4.10	Testing & Commissioning of T-Line and Equipment	1	EA		\$ -		\$ -	\$ -	\$ -	\$ -
	Permitting, Indirects and Additional Costs									
4.11	Environmental Licensing & Permitting Costs & related legal cost	1	LS		\$ 1,966,620		\$ -	\$ 1,966,620	\$ -	\$ 1,966,620
4.12	Environmental-special studies/investigation		LS		\$ -		\$ -	\$ -	\$ -	\$ -
4.13	Warranties / LOC's	1	LS		\$ 589,986		\$ -	\$ 589,986	\$ -	\$ 589,986
4.14	Laydown Lease & temporary easement	1	LS		\$ 2,000,000		\$ -	\$ 2,000,000	\$ -	\$ 2,000,000
4.15	Real Estate ( Acquisition)	1	LS			\$ 60,856	\$ -	\$ -	\$ 60,856	\$ 60,856
4.16	Legal Fees (Real estate)	1.00	LS		-	1,825.68	\$ -	\$ -	\$ 1,826	\$ 1,826
4.17	Insurance	-	LS		-	-	\$ -	\$ -	\$ -	\$ -
4.18	Insurance (specialty, e.g. railroad)		Crossing			\$ 1,000	\$ -	\$ -	\$ -	\$ -
4.19	Bonds	1	LS			\$ 6,980,000	\$ -	\$ -	\$ 6,980,000	\$ 6,980,000
4.20	Sales Tax on Materials	8.88%	% of material cost	\$ 81,246,566.33			\$ 7,214,695	\$ -	\$ -	\$ 7,214,695
4.21	Fees for permits, including roadway, railroad, building or other local permits	1	LS			\$ 196,662	\$ -	\$ -	\$ 196,662	\$ 196,662
TOTAL - MOB/DEMOB, ENGINEERING, PERMITTING, T&C, PM & INDIRECTS:							\$ 9,181,315	\$ 30,875,539	\$ 10,363,420	\$ 50,420,274

**NEXtera Energy- TO36 Core 1**

**Comp 8C - Rebuild: East Garden City - Newbridge 345kV Onshore UG Cables -Double circuits**

Total:   \$   133,317,472

**NEXtera Energy- TO36 Core 1**

**Comp 8C - Rebuild: East Garden City - Newbridge 345kV Onshore UG Cables -Double circuits**

Total:   \$   133,317,472

**NEXtera Energy- TO36 Core 1**

**Comp 8C - Rebuild: East Garden City - Newbridge 345kV Onshore UG Cables -Double circuits**

Total:   \$   133,317,472

NEXtera Energy- TO36 Core 1				
	Material Supply	Labor Supply	Equip Supply	Total
Comp 8C - Rebuild: East Garden City - Newbridge 345kV Onshore UG Cables -Double circuits				
1. SITE PREP/ACCESS/TRAFFIC MANAGEMENT	\$ 96,000	\$ 616,000	\$ 172,800	\$ 884,800
2. ONSHORE CABLE CONDUITS & VAULTS INSTALLATION	\$ -	\$ -	\$ -	\$ -
3. ONSHORE CABLE PROCUREMENT AND INSTALLATION	\$ 44,460,251	\$ 18,243,138	\$ 11,801,992	\$ 74,505,381
4. MOB/DEMOB, ENGINEERING, PERMITTING, T&C, PM & INDIRECTS	\$ 4,710,497	\$ 10,698,010	\$ 3,352,069	\$ 18,760,576
SUBTOTAL (Costs):	\$ 49,266,748	\$ 29,557,148	\$ 15,326,861	\$ 94,150,757
CONTRACTOR MARK-UP (OH&P)	\$ 8,868,015	\$ 5,320,287	\$ 2,758,835	\$ 16,947,136
SUBTOTAL:	\$ 58,134,763	\$ 34,877,435	\$ 18,085,696	\$ 111,097,893
CONTINGENCY ON ENTIRE PROJECT	\$ 11,626,953	\$ 6,975,487	\$ 3,617,139	\$ 22,219,579
TOTAL:	\$ 69,761,715	\$ 41,852,922	\$ 21,702,835	\$ 133,317,472

Description of Work: Convert two existing 138kV circuits (462, 463) to 345kV with new cable; disconnect other two (465, 467). 5000 kcmil copper XLPE, single cable per phase.										
Item	Item Description	Estimated Quantity	Unit of Measure	Material Supply Rate	Labor Supply Rate	Const. Equipment Rate	Material Supply Cost	Labor Supply Cost	Const. Equipment Cost	TOTAL
Comp 8C - Rebuld: East Garden City - Newbridge 345kV Onshore UG Cables -Double circuits										
1. SITE PREP/ACCESS/TRAFFIC MANAGEMENT										
1.1	Environmental BMPs / SWPPP Installation, Maintenance & Repairs	0	LF	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
1.2	Existing Utility Conflict and Relocation	4.87	Mile				\$ -	\$ -	\$ -	\$ -
1.3	Flaggers	60	DAY	\$ 1,600	\$ 4,800	\$ 1,600	\$ 96,000	\$ 288,000	\$ 96,000	\$ 480,000
1.4	K Rail / Lane Control / Metal Plates	25,714	LF				\$ -	\$ -	\$ -	\$ -
1.5	Police Support	2,400.0	HR		\$ 120	\$ 27	\$ -	\$ 288,000	\$ 64,800	\$ 352,800
1.6	Additional Traffic Management		LS				\$ -	\$ -	\$ -	\$ -
1.7	Access / Clearing Costs		LS				\$ -	\$ -	\$ -	\$ -
1.8	Snow Removal	40.0	DAY		\$ 1,000	\$ 300	\$ -	\$ 40,000	\$ 12,000	\$ 52,000
1.9	Existing Utility Protection	-	Mile	\$ 40,000	\$ 120,000	\$ 40,000	\$ -	\$ -	\$ -	\$ -
TOTAL - SITE PREP/ACCESS/TRAFFIC MANAGEMENT/ ACCESS:							\$ 96,000	\$ 616,000	\$ 172,800	\$ 884,800
2. ONSHORE CABLE CONDUITS & VAULTS INSTALLATION										
2.1	Trench Box Shoring & Trench Box Install Crew	0.00	Miles		\$ 139,800	\$ 93,200	\$ -	\$ -	\$ -	\$ -
2.2	Formwork in Trench	0	SF	\$ 2	\$ 1.5	\$ 0.5	\$ -	\$ -	\$ -	\$ -
2.3	Trench Excavation	-	CY		\$ 17.5	\$ 7.5	\$ -	\$ -	\$ -	\$ -
2.4	Supply & Install 6" Sand Bedding for direct bury conduits	0	SF	\$ 50	\$ 25	\$ 14	\$ -	\$ -	\$ -	\$ -
2.5	Supply & Install Thermal Backfill	0	CY	\$ 350	\$ 245	\$ 105	\$ -	\$ -	\$ -	\$ -
2.6	Supply & Install Concrete Cap (6")	0	CY	\$ 200	\$ 125	\$ 50	\$ -	\$ -	\$ -	\$ -
2.7	Native Backfill -direct bury conduits sys Trench	0	CY		\$ 14.0	\$ 6.0	\$ -	\$ -	\$ -	\$ -
2.8	Supply & Install Ductbank Concrete	0	CY	\$ 200	\$ 125	\$ 50	\$ -	\$ -	\$ -	\$ -
2.9	Conduit 8" SCH 40PVC	0	LF	\$ 28.6	\$ 5.7	\$ 2.4	\$ -	\$ -	\$ -	\$ -
2.10	Conduit 4" SCH 40PVC	0	LF	\$ 9.8	\$ 4.20	\$ 1.8	\$ -	\$ -	\$ -	\$ -
2.11	Conduit 2" SCH 40PVC	0	LF	\$ 3.5	\$ 3.15	\$ 1.4	\$ -	\$ -	\$ -	\$ -
2.12	Warning Tape	0	LF	\$ 0.15	\$ 0.25	\$ 0.10	\$ -	\$ -	\$ -	\$ -
2.13	Trench Box Shoring (Vault)	0	EA	\$ -	\$ 18,079	\$ 27,119	\$ -	\$ -	\$ -	\$ -
2.14	Splice Vault Excavation	0	CY		\$ 17.5	\$ 7.5	\$ -	\$ -	\$ -	\$ -
2.15	Splice Vault Supply & Installation	0	EA	\$ 35,000	\$ 16,500	\$ 38,500	\$ -	\$ -	\$ -	\$ -
2.16	Splice Vault Backfill	0	CY		\$ 14.0	\$ 6.0	\$ -	\$ -	\$ -	\$ -
2.17	Jack and Bore along Route	0	LF	\$ 2,400	\$ 4,800	\$ 4,800	\$ -	\$ -	\$ -	\$ -
2.18	HDD along Route	0	LF	\$ 800	\$ 1,600	\$ 1,600	\$ -	\$ -	\$ -	\$ -

Item	Item Description	Estimated Quantity	Unit of Measure	Material Supply Rate	Labor Supply Rate	Const. Equipment Rate	Material Supply Cost	Labor Supply Cost	Const. Equipment Cost	TOTAL
2.19	Air Test Ducts	0	LF			\$ 0.25	\$ -	\$ -	\$ -	\$ -
2.20	PVMT, ASPHALT, 2" SURFACE COURSE	0	SY	\$ 14.00	\$ 14.00	\$ 7.00	\$ -	\$ -	\$ -	\$ -
2.21	PVMT, AGGREGATE, 10", BASE COURSE	0	CY	\$ 22.38	\$ 23.50	\$ 10.07	\$ -	\$ -	\$ -	\$ -
2.22	Concrete Ductbank Thermal Resistivity Testing (every 100CY of concrete poured)	0	EA		\$ 400	\$ 1,200	\$ -	\$ -	\$ -	\$ -
2.23	Concrete Ductbank Compressive Strength Testing (every 100CY of concrete poured)	0	EA		\$ 10	\$ 15	\$ -	\$ -	\$ -	\$ -
2.24	Backfill Thermal Resistivity Testing (every 100CY of backfill placed)	0	EA		\$ 400	\$ 1,200	\$ -	\$ -	\$ -	\$ -
2.25	Additional misc. testing allowance (Native Backfill, Asphalt Density, Concrete Curb etc.)	0	LS		\$ 448,266	\$ 298,844	\$ -	\$ -	\$ -	\$ -
2.26	Excess Materials Disposal to Certified Backfill	0	CY		\$ 24.5	\$ 10.5	\$ -	\$ -	\$ -	\$ -
2.27	Rock Excavation and Removal	0	LS				\$ -	\$ -	\$ -	\$ -
2.28	Dewatering	0	EA			\$ 4,000	\$ -	\$ -	\$ -	\$ -
2.29	Contaminated Water Treatment and Disposal	0	LS				\$ -	\$ -	\$ -	\$ -
2.30	Contaminated Spoils Disposal	0	LS				\$ -	\$ -	\$ -	\$ -
2.31	Excavated material - stockpile management	0	CF		\$ 1.0	\$ 0.5	\$ -	\$ -	\$ -	\$ -
TOTAL - ONSHORE CABLE CONDUITS & VAULTS INSTALLATION:							\$ -	\$ -	\$ -	\$ -
3. ONSHORE CABLE PROCUREMENT AND INSTALLATION										
3.1	Circuit #1- Procurement & Installation- 345kV 5000 kcmil copper XLPE	80,998	FT	\$ 167	\$ 100	\$ 67	\$ 13,526,639	\$ 8,115,984	\$ 5,410,656	\$ 27,053,279
3.2	Circuit #1- Cable Splicing- 345kV 5000 kcmil copper XLPE	42	EA	\$ 11,722	\$ 9,846	\$ 2,813	\$ 492,324	\$ 413,552	\$ 118,158	\$ 1,024,034
3.3	Circuit #1- Cable Termination- 345kV 5000 kcmil copper XLPE	6	EA	\$ 27,805	\$ 9,846	\$ 2,813	\$ 166,830	\$ 59,079	\$ 16,880	\$ 242,789
3.4	Circuit #2- Procurement & Installation- 345kV 5000 kcmil copper XLPE	80,998	FT	\$ 167	\$ 100	\$ 67	\$ 13,526,639	\$ 8,115,984	\$ 5,410,656	\$ 27,053,279
3.5	Circuit #2- Cable Splicing- 345kV 5000 kcmil copper XLPE	42	EA	\$ 11,722	\$ 9,846	\$ 2,813	\$ 492,324	\$ 413,552	\$ 118,158	\$ 1,024,034
3.6	Circuit #2- Cable Termination- 345kV 5000 kcmil copper XLPE	6	EA	\$ 27,805	\$ 9,846	\$ 2,813	\$ 166,830	\$ 59,079	\$ 16,880	\$ 242,789
3.7	Circuit #3- Procurement & Installation- 345kV 5000 kcmil copper XLPE		FT	\$ 167	\$ 100	\$ 67	\$ 13,526,639	\$ -	\$ -	\$ 13,526,639
3.8	Circuit #3- Cable Splicing- 345kV 5000 kcmil copper XLPE		EA	\$ 11,722	\$ 9,846	\$ 2,813	\$ 492,324	\$ -	\$ -	\$ 492,324
3.9	Circuit #3- Cable Termination- 345kV 5000 kcmil copper XLPE		EA	\$ 27,805	\$ 9,846	\$ 2,813	\$ 166,830	\$ -	\$ -	\$ 166,830
3.10	Link Box & MH racking	28	EA	\$ 28,548	\$ 17,129	\$ 11,419	\$ 799,357	\$ 479,614	\$ 319,743	\$ 1,598,713
3.11	Fiber Optic Cable	53,999	FT	\$ 7	\$ 3	\$ 2	\$ 399,427	\$ 179,848	\$ 119,898	\$ 699,173
3.12	Ground Continuity Conductor	53,999	FT	\$ 13	\$ 8	\$ 5	\$ 704,087	\$ 406,447	\$ 270,965	\$ 1,381,499
TOTAL - ONSHORE CABLE PROCUREMENT AND INSTALLATION							\$ 44,460,251	\$ 18,243,138	\$ 11,801,992	\$ 74,505,381
Comp 4 - Dunwoodie To New Rochelle Landing 345kV Onshore UG Cables -single circuit(EGC To Dunwoodie 345 kV)							\$ 44,556,251	\$ 18,859,138	\$ 11,974,792	\$ 75,390,181
4. MOB/DEMOB, ENGINEERING, PERMITTING, T&C, PM & INDIRECTS										
	Contractor Mobilization / Demobilization									
4.1	Mob / Demob	1	LS		\$ 925,018	\$ 616,679	\$ -	\$ 925,018	\$ 616,679	\$ 1,541,697
	Project Management, Material Handling & Amenities									
4.2	Preconstruction Supervision (Engineering, Permitting, Procurement)	1	LS		753,901.81		\$ -	\$ 753,902	\$ -	\$ 753,902
4.3	Construction Project Management / Supervision	1	LS		3,015,607.24		\$ -	\$ 3,015,607	\$ -	\$ 3,015,607
4.4	Utility PM and Project Oversight	1	LS		753,901.81		\$ -	\$ 753,902	\$ -	\$ 753,902
4.5	Site Accommodation, Facilities, Storage	1	LS	753,901.81			\$ 753,902	\$ -	\$ -	\$ 753,902
	Engineering									
4.6	Design Engineering	1.0	LS		\$ 3,769,509	\$ -	\$ -	\$ 3,769,509	\$ -	\$ 3,769,509
4.7	LiDAR /GPR	-	LS		\$ 135,702	\$ 90,468	\$ -	\$ -	\$ -	\$ -
4.8	Geotech	-	EA		2,730.00	1,820.00	\$ -	\$ -	\$ -	\$ -
4.9	Surveying/Staking	-	LS		\$ 316,639	\$ 211,093	\$ -	\$ -	\$ -	\$ -
	Testing & Commissioning									
4.10	Testing & Commissioning of T-Line and Equipment	1	EA		\$ -		\$ -	\$ -	\$ -	\$ -
	Permitting, Indirects and Additional Costs									
4.11	Environmental Licensing & Permitting Costs & related legal cost	1	LS		\$ 753,902		\$ -	\$ 753,902	\$ -	\$ 753,902
4.12	Environmental-special studies/investigation		LS		\$ -		\$ -	\$ -	\$ -	\$ -
4.13	Warranties / LOC's	1	LS		\$ 226,171		\$ -	\$ 226,171	\$ -	\$ 226,171
4.14	Laydown Lease & temporary easement	1	LS		\$ 500,000		\$ -	\$ 500,000	\$ -	\$ 500,000
4.15	Real Estate ( Acquisition)		LS				\$ -	\$ -	\$ -	\$ -
4.16	Legal Fees (Real estate)	-	LS		-	-	\$ -	\$ -	\$ -	\$ -
4.17	Insurance	-	LS		-	-	\$ -	\$ -	\$ -	\$ -
4.18	Insurance (specialty, e.g. railroad)		Crossing			\$ 1,000	\$ -	\$ -	\$ -	\$ -
4.19	Bonds	1	LS			\$ 2,660,000	\$ -	\$ -	\$ 2,660,000	\$ 2,660,000
4.20	Sales Tax on Materials	8.88%	% of material cost	\$ 44,556,251.01			\$ 3,956,595	\$ -	\$ -	\$ 3,956,595
4.21	Fees for permits, including roadway, railroad, building or other local permits	1	LS			\$ 75,390	\$ -	\$ -	\$ 75,390	\$ 75,390
TOTAL - MOB/DEMOB, ENGINEERING, PERMITTING, T&C, PM & INDIRECTS:							\$ 4,710,497	\$ 10,698,010	\$ 3,352,069	\$ 18,760,576

NEXtera Energy- TO36 Core 1

Comp 10A - East Graden City To Valley Stream 345kV Onshore UG Cables -Triple circuits

Total:   \$   394,231,294

NEXtera Energy- TO36 Core 1				
	Material Supply	Labor Supply	Equip Supply	Total
Comp 10A - East Graden City To Valley Stream 345kV Onshore UG Cables -Triple circuits				
1. SITE PREP/ACCESS/TRAFFIC MANAGEMENT	\$ 2,116,608	\$ 10,859,085	\$ 4,087,123	\$ 17,062,816
2. ONSHORE CABLE CONDUITS & VAULTS INSTALLATION	\$ 27,896,453	\$ 19,480,913	\$ 14,097,858	\$ 61,475,224
3. ONSHORE CABLE PROCUREMENT AND INSTALLATION	\$ 71,900,202	\$ 44,673,808	\$ 27,284,346	\$ 143,858,356
4. MOB/DEMOB, ENGINEERING, PERMITTING, T&C, PM & INDIRECTS	\$ 11,273,862	\$ 33,325,469	\$ 11,416,205	\$ 56,015,535
SUBTOTAL (Costs):	\$ 113,187,125	\$ 108,339,275	\$ 56,885,531	\$ 278,411,931
CONTRACTOR MARK-UP (OH&P)	\$ 20,373,682	\$ 19,501,069	\$ 10,239,396	\$ 50,114,148
SUBTOTAL:	\$ 133,560,807	\$ 127,840,344	\$ 67,124,927	\$ 328,526,078
CONTINGENCY ON ENTIRE PROJECT	\$ 26,712,161	\$ 25,568,069	\$ 13,424,985	\$ 65,705,216
TOTAL:	\$ 160,272,969	\$ 153,408,413	\$ 80,549,913	\$ 394,231,294

Description of Work: Replace two existing 138kv UG cable with three 345kv 5000 kcmil copper XLPE, single cable per phase.										
Item	Item Description	Estimated Quantity	Unit of Measure	Material Supply Rate	Labor Supply Rate	Const. Equipment Rate	Material Supply Cost	Labor Supply Cost	Const. Equipment Cost	TOTAL
Comp 10A - East Graden City To Valley Stream 345kV Onshore UG Cables -Triple circuits										
1. SITE PREP/ACCESS/TRAFFIC MANAGEMENT										
1.1	Environmental BMPs / SWPPP Installation, Maintenance & Repairs	0	LF	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
1.2	Existing Utility Conflict and Relocation	7.12	Mile		\$ 700,000	\$ 300,000	\$ -	\$ 4,984,000	\$ 2,136,000	\$ 7,120,000
1.3	Flaggers	440	DAY	\$ 1,600	\$ 4,800	\$ 1,600	\$ 704,000	\$ 2,112,000	\$ 704,000	\$ 3,520,000
1.4	K Rail / Lane Control / Metal Plates	37,594	LF	\$ 30	\$ 18	\$ 12	\$ 1,127,808	\$ 676,685	\$ 451,123	\$ 2,255,616
1.5	Police Support	17,600.0	HR		\$ 120	\$ 27	\$ -	\$ 2,112,000	\$ 475,200	\$ 2,587,200
1.6	Additional Traffic Management		LS				\$ -	\$ -	\$ -	\$ -
1.7	Access / Clearing Costs		LS				\$ -	\$ -	\$ -	\$ -
1.8	Snow Removal	120.0	DAY		\$ 1,000	\$ 300	\$ -	\$ 120,000	\$ 36,000	\$ 156,000
1.9	Existing Utility Protection	7.12	Mile	\$ 40,000	\$ 120,000	\$ 40,000	\$ 284,800	\$ 854,400	\$ 284,800	\$ 1,424,000
TOTAL - SITE PREP/ACCESS/TRAFFIC MANAGEMENT/ ACCESS:							\$ 2,116,608	\$ 10,859,085	\$ 4,087,123	\$ 17,062,816
2. ONSHORE CABLE CONDUITS & VAULTS INSTALLATION										
2.1	Trench Box Shoring & Trench Box Install Crew	7.12	Miles		\$ 139,800	\$ 93,200	\$ -	\$ 995,376	\$ 663,584	\$ 1,658,960
2.2	Formwork in Trench	292,109	SF	\$ 2	\$ 1.5	\$ 0.5	\$ 584,218	\$ 438,163	\$ 146,054	\$ 1,168,435
2.3	Trench Excavation	45,980	CY		\$ 17.5	\$ 7.5	\$ -	\$ 804,652	\$ 344,851	\$ 1,149,502
2.4	Supply & Install 6" Sand Bedding for direct bury conduits	2,874	SF	\$ 50	\$ 25	\$ 14	\$ 143,688	\$ 70,407	\$ 40,233	\$ 254,327
2.5	Supply & Install Thermal Backfill	18,105	CY	\$ 350	\$ 245	\$ 105	\$ 6,336,631	\$ 4,435,642	\$ 1,900,989	\$ 12,673,262
2.6	Supply & Install Concrete Cap (6")	0	CY	\$ 200	\$ 125	\$ 50	\$ -	\$ -	\$ -	\$ -
2.7	Native Backfill -direct bury conduits sys Trench	0	CY		\$ 14.0	\$ 6.0	\$ -	\$ -	\$ -	\$ -
2.8	Supply & Install Ductbank Concrete	14,924	CY	\$ 200	\$ 125	\$ 50	\$ 2,984,784	\$ 1,865,490	\$ 746,196	\$ 5,596,470
2.9	Conduit 8" SCH 40PVC	451,123	LF	\$ 28.6	\$ 5.7	\$ 2.4	\$ 12,902,124	\$ 2,557,869	\$ 1,096,229	\$ 16,556,221
2.10	Conduit 4" SCH 40PVC	0	LF	\$ 9.8	\$ 4.20	\$ 1.8	\$ -	\$ -	\$ -	\$ -
2.11	Conduit 2" SCH 40PVC	300,749	LF	\$ 3.5	\$ 3.15	\$ 1.4	\$ 1,058,636	\$ 947,359	\$ 406,011	\$ 2,412,005
2.12	Warning Tape	75,187	LF	\$ 0.15	\$ 0.25	\$ 0.10	\$ 11,278	\$ 18,797	\$ 7,519	\$ 37,594
2.13	Trench Box Shoring (Vault)	72	EA	\$ -	\$ 18,079	\$ 27,119	\$ -	\$ 1,301,695	\$ 1,952,542	\$ 3,254,237
2.14	Splice Vault Excavation	11,968	CY		\$ 17.5	\$ 7.5	\$ -	\$ 209,440	\$ 89,760	\$ 299,200
2.15	Splice Vault Supply & Installation	72	EA	\$ 35,000	\$ 16,500	\$ 38,500	\$ 2,520,000	\$ 1,188,000	\$ 2,772,000	\$ 6,480,000
2.16	Splice Vault Backfill	3,590	CY		\$ 14.0	\$ 6.0	\$ -	\$ 50,266	\$ 21,542	\$ 71,808
2.17	Jack and Bore along Route	360	LF	\$ 2,400	\$ 4,800	\$ 4,800	\$ 864,000	\$ 1,728,000	\$ 1,728,000	\$ 4,320,000
2.18	HDD along Route	0	LF	\$ 800	\$ 1,600	\$ 1,600	\$ -	\$ -	\$ -	\$ -



Item	Item Description	Estimated Quantity	Unit of Measure	Material Supply Rate	Labor Supply Rate	Const. Equipment Rate	Material Supply Cost	Labor Supply Cost	Const. Equipment Cost	TOTAL
2.19	Air Test Ducts	751,872	LF			\$ 0.25	\$ -	\$ -	\$ 187,968	\$ 187,968
2.20	PVMT, ASPHALT, 2" SURFACE COURSE	24,292	SY	\$ 14.00	\$ 14.00	\$ 7.00	\$ 340,082	\$ 340,082	\$ 170,041	\$ 850,206
2.21	PVMT, AGGREGATE, 10" , BASE COURSE	6,748	CY	\$ 22.38	\$ 23.50	\$ 10.07	\$ 151,013	\$ 158,563	\$ 67,956	\$ 377,532
2.22	Concrete Ductbank Thermal Resistivity Testing (every 100CY of concrete poured)	149	EA		\$ 400	\$ 1,200	\$ -	\$ 59,696	\$ 179,087	\$ 238,783
2.23	Concrete Ductbank Compressive Strength Testing (every 100CY of concrete poured)	149	EA		\$ 10	\$ 15	\$ -	\$ 1,492	\$ 2,239	\$ 3,731
2.24	Backfill Thermal Resistivity Testing (every 100CY of backfill placed)	181	EA		\$ 400	\$ 1,200	\$ -	\$ 72,419	\$ 217,256	\$ 289,675
2.25	Additional misc. testing allowance (Native Backfill, Asphalt Density, Concrete Curb etc.)	1	LS		\$ 448,266	\$ 298,844	\$ -	\$ 448,266	\$ 298,844	\$ 747,110
2.26	Excess Materials Disposal to Certified Backfill	70,665	CY		\$ 24.5	\$ 10.5	\$ -	\$ 1,731,292	\$ 741,982	\$ 2,473,275
2.27	Rock Excavation and Removal	1	LS				\$ -	\$ -	\$ -	\$ -
2.28	Dewatering	72	EA			\$ 4,000	\$ -	\$ -	\$ 288,000	\$ 288,000
2.29	Contaminated Water Treatment and Disposal	1	LS				\$ -	\$ -	\$ -	\$ -
2.30	Contaminated Spoils Disposal	1	LS				\$ -	\$ -	\$ -	\$ -
2.31	Excavated material - stockpile management	57,948	CF		\$ 1.0	\$ 0.5	\$ -	\$ 57,948	\$ 28,974	\$ 86,922
<b>TOTAL - ONSHORE CABLE CONDUITS &amp; VAULTS INSTALLATION:</b>							\$ 27,896,453	\$ 19,480,913	\$ 14,097,858	\$ 61,475,224
<b>3. ONSHORE CABLE PROCUREMENT AND INSTALLATION</b>										
3.1	Circuit #1- Procurement & Installation- 345kV 5000 kcmil copper XLPE	118,420	FT	\$ 167	\$ 100	\$ 67	\$ 19,776,113	\$ 11,865,668	\$ 7,910,445	\$ 39,552,227
3.2	Circuit #1- Cable Splicing- 345kV 5000 kcmil copper XLPE	216	EA	\$ 11,722	\$ 9,846	\$ 2,813	\$ 2,531,952	\$ 2,126,840	\$ 607,668	\$ 5,266,460
3.3	Circuit #1- Cable Termination- 345kV 5000 kcmil copper XLPE	6	EA	\$ 27,805	\$ 9,846	\$ 2,813	\$ 166,830	\$ 59,079	\$ 16,880	\$ 242,789
3.4	Circuit #2- Procurement & Installation- 345kV 5000 kcmil copper XLPE	118,420	FT	\$ 167	\$ 100	\$ 67	\$ 19,776,113	\$ 11,865,668	\$ 7,910,445	\$ 39,552,227
3.5	Circuit #2- Cable Splicing- 345kV 5000 kcmil copper XLPE	216	EA	\$ 11,722	\$ 9,846	\$ 2,813	\$ 2,531,952	\$ 2,126,840	\$ 607,668	\$ 5,266,460
3.6	Circuit #2- Cable Termination- 345kV 5000 kcmil copper XLPE	6	EA	\$ 27,805	\$ 9,846	\$ 2,813	\$ 166,830	\$ 59,079	\$ 16,880	\$ 242,789
3.7	Circuit #3- Procurement & Installation- 345kV 5000 kcmil copper XLPE	118,420	FT	\$ 167	\$ 100	\$ 67	\$ 19,776,113	\$ 11,865,668	\$ 7,910,445	\$ 39,552,227
3.8	Circuit #3- Cable Splicing- 345kV 5000 kcmil copper XLPE	216	EA	\$ 11,722	\$ 9,846	\$ 2,813	\$ 2,531,952	\$ 2,126,840	\$ 607,668	\$ 5,266,460
3.9	Circuit #3- Cable Termination- 345kV 5000 kcmil copper XLPE	6	EA	\$ 27,805	\$ 9,846	\$ 2,813	\$ 166,830	\$ 59,079	\$ 16,880	\$ 242,789
3.10	Link Box & MH racking	72	EA	\$ 28,548	\$ 17,129	\$ 11,419	\$ 2,055,488	\$ 1,233,293	\$ 822,195	\$ 4,110,977
3.11	Fiber Optic Cable	118,420	FT	\$ 7	\$ 3	\$ 2	\$ 875,952	\$ 394,409	\$ 262,939	\$ 1,533,300
3.12	Ground Continuity Conductor	118,420	FT	\$ 13	\$ 8	\$ 5	\$ 1,544,076	\$ 891,346	\$ 594,231	\$ 3,029,653
<b>TOTAL - ONSHORE CABLE PROCUREMENT AND INSTALLATION</b>							\$ 71,900,202	\$ 44,673,808	\$ 27,284,346	\$ 143,858,356
<b>Comp 4 - Dunwoodie To New Rochelle Landing 345kV Onshore UG Cables -single circuit(EGC To Dunwoodie 345 kV)</b>							\$ 101,913,263	\$ 75,013,806	\$ 45,469,327	\$ 222,396,395
<b>4. MOB/DEMOB, ENGINEERING, PERMITTING, T&amp;C, PM &amp; INDIRECTS</b>										
	<b>Contractor Mobilization / Demobilization</b>									
4.1	Mob / Demob	1	LS		\$ 3,614,494	\$ 2,409,663	\$ -	\$ 3,614,494	\$ 2,409,663	\$ 6,024,157
	<b>Project Management, Material Handling &amp; Amenities</b>									
4.2	Preconstruction Supervision (Engineering, Permitting, Procurement)	1	LS		2,223,963.95		\$ -	\$ 2,223,964	\$ -	\$ 2,223,964
4.3	Construction Project Management / Supervision	1	LS		8,895,855.82		\$ -	\$ 8,895,856	\$ -	\$ 8,895,856
4.4	Utility PM and Project Oversight	1	LS		2,223,963.95		\$ -	\$ 2,223,964	\$ -	\$ 2,223,964
4.5	Site Accommodation, Facilities, Storage	1	LS	2,223,963.95			\$ 2,223,964	\$ -	\$ -	\$ 2,223,964
	<b>Engineering</b>									
4.6	Design Engineering	1.0	LS		\$ 11,119,820	\$ -	\$ -	\$ 11,119,820	\$ -	\$ 11,119,820
4.7	LiDAR /GPR	1.0	LS		\$ 400,314	\$ 266,876	\$ -	\$ 400,314	\$ 266,876	\$ 667,189
4.8	Geotech	8.00	EA		2,730.00	1,820.00	\$ -	\$ 21,840	\$ 14,560	\$ 36,400
4.9	Surveying/Staking	1	LS		\$ 934,065	\$ 622,710	\$ -	\$ 934,065	\$ 622,710	\$ 1,556,775
	<b>Testing &amp; Commissioning</b>									
4.10	Testing & Commissioning of T-Line and Equipment	1	EA		\$ -		\$ -	\$ -	\$ -	\$ -
	<b>Permitting, Indirects and Additional Costs</b>									
4.11	Environmental Licensing & Permitting Costs & related legal cost	1	LS		\$ 2,223,964		\$ -	\$ 2,223,964	\$ -	\$ 2,223,964
4.12	Environmental-special studies/investigation		LS		\$ -		\$ -	\$ -	\$ -	\$ -
4.13	Warranties / LOC's	1	LS		\$ 667,189		\$ -	\$ 667,189	\$ -	\$ 667,189
4.14	Laydown Lease & temporary easement	1	LS		\$ 1,000,000		\$ -	\$ 1,000,000	\$ -	\$ 1,000,000
4.15	Real Estate ( Acquisition)		LS				\$ -	\$ -	\$ -	\$ -
4.16	Legal Fees (Real estate)	-	LS		-	-	\$ -	\$ -	\$ -	\$ -
4.17	Insurance	-	LS		-	-	\$ -	\$ -	\$ -	\$ -
4.18	Insurance (specialty, e.g. railroad)		Crossing			\$ 1,000	\$ -	\$ -	\$ -	\$ -
4.19	Bonds	1	LS			\$ 7,880,000	\$ -	\$ -	\$ 7,880,000	\$ 7,880,000
4.20	Sales Tax on Materials	8.88%	% of material cost	\$ 101,913,262.97			\$ 9,049,898	\$ -	\$ -	\$ 9,049,898
4.21	Fees for permits, including roadway, railroad, building or other local permits	1	LS			\$ 222,396	\$ -	\$ -	\$ 222,396	\$ 222,396
<b>TOTAL - MOB/DEMOB, ENGINEERING, PERMITTING, T&amp;C, PM &amp; INDIRECTS:</b>							\$ 11,273,862	\$ 33,325,469	\$ 11,416,205	\$ 56,015,535

**Comp 13A - Syosset - Oakwood 138 kV Onshore UG Cables -Single circuit**

NEXtera Energy- T036 Core 1				
	Material Supply	Labor Supply	Equip Supply	Total
Comp 13A - Syosset - Oakwood 138 kV Onshore UG Cables -Single circuit				
1. SITE PREP/ACCESS/TRAFFIC MANAGEMENT	\$ 64,000	\$ 424,000	\$ 119,200	\$ 607,200
2. ONSHORE CABLE CONDUITS & VAULTS INSTALLATION	\$ -	\$ -	\$ -	\$ -
3. ONSHORE CABLE PROCUREMENT AND INSTALLATION	\$ 6,641,033	\$ 4,155,419	\$ 2,657,748	\$ 13,454,200
4. MOB/DEMOB, ENGINEERING, PERMITTING, T&C, PM & INDIRECTS	\$ 736,021	\$ 2,509,301	\$ 700,561	\$ 3,945,883
SUBTOTAL (Costs):	\$ 7,441,054	\$ 7,088,720	\$ 3,477,509	\$ 18,007,283
CONTRACTOR MARK-UP (OH&P)	\$ 1,339,390	\$ 1,275,970	\$ 625,952	\$ 3,241,311
SUBTOTAL:	\$ 8,780,444	\$ 8,364,689	\$ 4,103,460	\$ 21,248,594
CONTINGENCY ON ENTIRE PROJECT	\$ 1,756,089	\$ 1,672,938	\$ 820,692	\$ 4,249,719
TOTAL:	\$ 10,536,533	\$ 10,037,627	\$ 4,924,152	\$ 25,498,312

Description of Work: Replace existing 2.6 miles of UG cable, single cable per phase.										
Item	Item Description	Estimated Quantity	Unit of Measure	Material Supply Rate	Labor Supply Rate	Const. Equipment Rate	Material Supply Cost	Labor Supply Cost	Const. Equipment Cost	TOTAL
Comp 13A - Syosset - Oakwood 138 kV Onshore UG Cables -Single circuit										
1. SITE PREP/ACCESS/TRAFFIC MANAGEMENT										
1.1	Environmental BMPs / SWPPP Installation, Maintenance & Repairs	0	LF	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
1.2	Existing Utility Conflict and Relocation	2.60	Mile				\$ -	\$ -	\$ -	\$ -
1.3	Flaggers	40	DAY	\$ 1,600	\$ 4,800	\$ 1,600	\$ 64,000	\$ 192,000	\$ 64,000	\$ 320,000
1.4	K Rail / Lane Control / Metal Plates	0	LF	\$ 30	\$ 18	\$ 12	\$ -	\$ -	\$ -	\$ -
1.5	Police Support	1,600.0	HR		\$ 120	\$ 27	\$ -	\$ 192,000	\$ 43,200	\$ 235,200
1.6	Additional Traffic Management		LS				\$ -	\$ -	\$ -	\$ -
1.7	Access / Clearing Costs		LS				\$ -	\$ -	\$ -	\$ -
1.8	Snow Removal	40.0	DAY		\$ 1,000	\$ 300	\$ -	\$ 40,000	\$ 12,000	\$ 52,000
1.9	Existing Utility Protection	-	Mile	\$ 40,000	\$ 120,000	\$ 40,000	\$ -	\$ -	\$ -	\$ -
TOTAL - SITE PREP/ACCESS/TRAFFIC MANAGEMENT/ ACCESS:							\$ 64,000	\$ 424,000	\$ 119,200	\$ 607,200
2. ONSHORE CABLE CONDUITS & VAULTS INSTALLATION										
2.1	Trench Box Shoring & Trench Box Install Crew		Miles		\$ 139,800	\$ 93,200	\$ -	\$ -	\$ -	\$ -
2.2	Formwork in Trench		SF	\$ 2	\$ 1.5	\$ 0.5	\$ -	\$ -	\$ -	\$ -
2.3	Trench Excavation		CY		\$ 17.5	\$ 7.5	\$ -	\$ -	\$ -	\$ -
2.4	Supply & Install 6" Sand Bedding for direct bury conduits		SF	\$ 50	\$ 25	\$ 14	\$ -	\$ -	\$ -	\$ -
2.5	Supply & Install Thermal Backfill		CY	\$ 350	\$ 245	\$ 105	\$ -	\$ -	\$ -	\$ -
2.6	Supply & Install Concrete Cap (6")		CY	\$ 200	\$ 125	\$ 50	\$ -	\$ -	\$ -	\$ -
2.7	Native Backfill -direct bury conduits sys Trench		CY		\$ 14.0	\$ 6.0	\$ -	\$ -	\$ -	\$ -
2.8	Supply & Install Ductbank Concrete		CY	\$ 200	\$ 125	\$ 50	\$ -	\$ -	\$ -	\$ -
2.9	Conduit 8" SCH 40PVC		LF	\$ 28.6	\$ 5.7	\$ 2.4	\$ -	\$ -	\$ -	\$ -
2.10	Conduit 4" SCH 40PVC		LF	\$ 9.8	\$ 4.20	\$ 1.8	\$ -	\$ -	\$ -	\$ -
2.11	Conduit 2" SCH 40PVC		LF	\$ 3.5	\$ 3.15	\$ 1.4	\$ -	\$ -	\$ -	\$ -
2.12	Warning Tape		LF	\$ 0.15	\$ 0.25	\$ 0.10	\$ -	\$ -	\$ -	\$ -
2.13	Trench Box Shoring (Vault)		EA	\$ -	\$ 18,079	\$ 27,119	\$ -	\$ -	\$ -	\$ -
2.14	Splice Vault Excavation	0	CY		\$ 17.5	\$ 7.5	\$ -	\$ -	\$ -	\$ -
2.15	Splice Vault Supply & Installation	0	EA	\$ 35,000	\$ 16,500	\$ 38,500	\$ -	\$ -	\$ -	\$ -
2.16	Splice Vault Backfill	0	CY		\$ 14.0	\$ 6.0	\$ -	\$ -	\$ -	\$ -
2.17	Jack and Bore along Route		LF	\$ 800	\$ 1,600	\$ 1,600	\$ -	\$ -	\$ -	\$ -
2.18	HDD along Route	0	LF	\$ 800	\$ 1,600	\$ 1,600	\$ -	\$ -	\$ -	\$ -

Item	Item Description	Estimated Quantity	Unit of Measure	Material Supply Rate	Labor Supply Rate	Const. Equipment Rate	Material Supply Cost	Labor Supply Cost	Const. Equipment Cost	TOTAL
2.19	Air Test Ducts	0	LF			\$ 0.25	\$ -	\$ -	\$ -	\$ -
2.20	PVMT, ASPHALT, 2" SURFACE COURSE	0	SY	\$ 14.00	\$ 14.00	\$ 7.00	\$ -	\$ -	\$ -	\$ -
2.21	PVMT, AGGREGATE, 10", BASE COURSE	0	CY	\$ 22.38	\$ 23.50	\$ 10.07	\$ -	\$ -	\$ -	\$ -
2.22	Concrete Ductbank Thermal Resistivity Testing (every 100CY of concrete poured)	0	EA		\$ 400	\$ 1,200	\$ -	\$ -	\$ -	\$ -
2.23	Concrete Ductbank Compressive Strength Testing (every 100CY of concrete poured)	0	EA		\$ 10	\$ 15	\$ -	\$ -	\$ -	\$ -
2.24	Backfill Thermal Resistivity Testing (every 100CY of backfill placed)	0	EA		\$ 400	\$ 1,200	\$ -	\$ -	\$ -	\$ -
2.25	Additional misc. testing allowance (Native Backfill, Asphalt Density, Concrete Curb etc.)		LS		\$ 448,266	\$ 298,844	\$ -	\$ -	\$ -	\$ -
2.26	Excess Materials Disposal to Certified Backfill	0	CY		\$ 24.5	\$ 10.5	\$ -	\$ -	\$ -	\$ -
2.27	Rock Excavation and Removal		LS				\$ -	\$ -	\$ -	\$ -
2.28	Dewatering		EA			\$ 4,000	\$ -	\$ -	\$ -	\$ -
2.29	Contaminated Water Treatment and Disposal		LS				\$ -	\$ -	\$ -	\$ -
2.30	Contaminated Spoils Disposal		LS				\$ -	\$ -	\$ -	\$ -
2.31	Excavated material - stockpile management		CF		\$ 1.0	\$ 0.5	\$ -	\$ -	\$ -	\$ -
TOTAL - ONSHORE CABLE CONDUITS & VAULTS INSTALLATION:							\$ -	\$ -	\$ -	\$ -
3. ONSHORE CABLE PROCUREMENT AND INSTALLATION										
3.1	Circuit #1- Procurement & Installation- 138kV 5000 kcmil copper XLPE	41,184	FT	\$ 145	\$ 87	\$ 58	\$ 5,971,680	\$ 3,583,008	\$ 2,388,672	\$ 11,943,360
3.2	Circuit #1- Cable Splicing- 138kV 5000 kcmil copper XLPE	24	EA	\$ 5,898	\$ 9,846	\$ 2,813	\$ 141,552	\$ 236,316	\$ 67,519	\$ 445,386
3.3	Circuit #1- Cable Termination- 138kV 5000 kcmil copper XLPE	6	EA	\$ 5,664	\$ 9,846	\$ 2,813	\$ 33,984	\$ 59,079	\$ 16,880	\$ 109,943
3.4	Circuit #2- Procurement & Installation- 138kV 5000 kcmil copper XLPE		FT	\$ 145	\$ 87	\$ 58	\$ -	\$ -	\$ -	\$ -
3.5	Circuit #2- Cable Splicing- 138kV 5000 kcmil copper XLPE		EA	\$ 5,898	\$ 9,846	\$ 2,813	\$ -	\$ -	\$ -	\$ -
3.6	Circuit #2- Cable Termination- 138kV 5000 kcmil copper XLPE		EA	\$ 5,664	\$ 9,846	\$ 2,813	\$ -	\$ -	\$ -	\$ -
3.7	Circuit #3- Procurement & Installation- 138kV 5000 kcmil copper XLPE		FT	\$ 145	\$ 87	\$ 58	\$ -	\$ -	\$ -	\$ -
3.8	Circuit #3- Cable Splicing- 138kV 5000 kcmil copper XLPE		EA	\$ 5,898	\$ 9,846	\$ 2,813	\$ -	\$ -	\$ -	\$ -
3.9	Circuit #3- Cable Termination- 138kV 5000 kcmil copper XLPE		EA	\$ 5,664	\$ 9,846	\$ 2,813	\$ -	\$ -	\$ -	\$ -
3.10	Link Box & MH racking	8	EA	\$ 26,659	\$ 15,995	\$ 10,664	\$ 213,272	\$ 127,963	\$ 85,309	\$ 426,544
3.11	Fiber Optic Cable	13,728	FT	\$ 7	\$ 3	\$ 2	\$ 101,546	\$ 45,722	\$ 30,482	\$ 177,750
3.12	Ground Continuity Conductor	13,728	FT	\$ 13	\$ 8	\$ 5	\$ 178,999	\$ 103,331	\$ 68,887	\$ 351,217
TOTAL - INSULATORS, FITTINGS, HARDWARE:							\$ 6,641,033	\$ 4,155,419	\$ 2,657,748	\$ 13,454,200
Comp 4 - Dunwoodie To New Rochelle Landing 345kV Onshore UG Cables -single circuit(EGC To Dunwoodie 345 kV)							\$ 6,705,033	\$ 4,579,419	\$ 2,776,948	\$ 14,061,400
4. MOB/DEMOB, ENGINEERING, PERMITTING, T&C, PM & INDIRECTS										
	Contractor Mobilization / Demobilization									
4.1	Mob / Demob	1	LS		\$ 220,691	\$ 147,127	\$ -	\$ 220,691	\$ 147,127	\$ 367,818
	Project Management, Material Handling & Amenities									
4.2	Preconstruction Supervision (Engineering, Permitting, Procurement)	1	LS		140,614.00		\$ -	\$ 140,614	\$ -	\$ 140,614
4.3	Construction Project Management / Supervision	1	LS		562,456.00		\$ -	\$ 562,456	\$ -	\$ 562,456
4.4	Utility PM and Project Oversight	1	LS		140,614.00		\$ -	\$ 140,614	\$ -	\$ 140,614
4.5	Site Accommodation, Facilities, Storage	1	LS	140,614.00			\$ 140,614	\$ -	\$ -	\$ 140,614
	Engineering									
4.6	Design Engineering	1.0	LS		\$ 703,070	\$ -	\$ -	\$ 703,070	\$ -	\$ 703,070
4.7	LIDAR /GPR	-	LS		\$ 25,311	\$ 16,874	\$ -	\$ -	\$ -	\$ -
4.8	Geotech	-	EA		2,730.00	1,820.00	\$ -	\$ -	\$ -	\$ -
4.9	Surveying/Staking	1	LS		\$ 59,058	\$ 39,372	\$ -	\$ 59,058	\$ 39,372	\$ 98,430
	Testing & Commissioning									
4.10	Testing & Commissioning of T-Line and Equipment	1	EA		\$ -		\$ -	\$ -	\$ -	\$ -
	Permitting, Indirects and Additional Costs									
4.11	Environmental Licensing & Permitting Costs & related legal cost	1	LS		\$ 140,614		\$ -	\$ 140,614	\$ -	\$ 140,614
4.12	Environmental-special studies/investigation		LS		\$ -		\$ -	\$ -	\$ -	\$ -
4.13	Warranties / LOC's	1	LS		\$ 42,184		\$ -	\$ 42,184	\$ -	\$ 42,184
4.14	Laydown Lease & temporary easement	1	LS		\$ 500,000		\$ -	\$ 500,000	\$ -	\$ 500,000
4.15	Real Estate ( Acquisition)		LS				\$ -	\$ -	\$ -	\$ -
4.16	Legal Fees (Real estate)	-	LS		-	-	\$ -	\$ -	\$ -	\$ -
4.17	Insurance	-	LS		-	-	\$ -	\$ -	\$ -	\$ -
4.18	Insurance (specialty, e.g. railroad)		Crossing			\$ 1,000	\$ -	\$ -	\$ -	\$ -
4.19	Bonds	1	LS			\$ 500,000	\$ -	\$ -	\$ 500,000	\$ 500,000
4.20	Sales Tax on Materials	8.88%	% of material cost	\$ 6,705,033.41			\$ 595,407	\$ -	\$ -	\$ 595,407
4.21	Fees for permits, including roadway, railroad, building or other local permits	1	LS			\$ 14,061	\$ -	\$ -	\$ 14,061	\$ 14,061
TOTAL - MOB/DEMOB, ENGINEERING, PERMITTING, T&C, PM & INDIRECTS:							\$ 736,021	\$ 2,509,301	\$ 700,561	\$ 3,945,883

## Comp 13B - Syosset - Greenlawn 138 kV Onshore UG Cables -Single circuit

NEXtera Energy- TO36 Core 1				
	Material Supply	Labor Supply	Equip Supply	Total
Comp 13B - Syosset - Greenlawn 138 kV Onshore UG Cables -Single circuit				
1. SITE PREP/ACCESS/TRAFFIC MANAGEMENT	\$ 64,000	\$ 424,000	\$ 119,200	\$ 607,200
2. ONSHORE CABLE CONDUITS & VAULTS INSTALLATION	\$ -	\$ -	\$ -	\$ -
3. ONSHORE CABLE PROCUREMENT AND INSTALLATION	\$ 6,641,033	\$ 4,155,419	\$ 2,657,748	\$ 13,454,200
4. MOB/DEMOB, ENGINEERING, PERMITTING, T&C, PM & INDIRECTS	\$ 736,021	\$ 2,509,301	\$ 700,561	\$ 3,945,883
SUBTOTAL (Costs):	\$ 7,441,054	\$ 7,088,720	\$ 3,477,509	\$ 18,007,283
CONTRACTOR MARK-UP (OH&P)	\$ 1,339,390	\$ 1,275,970	\$ 625,952	\$ 3,241,311
SUBTOTAL:	\$ 8,780,444	\$ 8,364,689	\$ 4,103,460	\$ 21,248,594
CONTINGENCY ON ENTIRE PROJECT	\$ 1,756,089	\$ 1,672,938	\$ 820,692	\$ 4,249,719
TOTAL:	\$ 10,536,533	\$ 10,037,627	\$ 4,924,152	\$ 25,498,312

Description of Work: Replace existing 2.6 miles of UG cable, single cable per phase.										
Item	Item Description	Estimated Quantity	Unit of Measure	Material Supply Rate	Labor Supply Rate	Const. Equipment Rate	Material Supply Cost	Labor Supply Cost	Const. Equipment Cost	TOTAL
Comp 13B - Syosset - Greenlawn 138 kV Onshore UG Cables -Single circuit										
1. SITE PREP/ACCESS/TRAFFIC MANAGEMENT										
1.1	Environmental BMPs / SWPPP Installation, Maintenance & Repairs	0	LF	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
1.2	Existing Utility Conflict and Relocation	2.60	Mile				\$ -	\$ -	\$ -	\$ -
1.3	Flaggers	40	DAY	\$ 1,600	\$ 4,800	\$ 1,600	\$ 64,000	\$ 192,000	\$ 64,000	\$ 320,000
1.4	K Rail / Lane Control / Metal Plates	0	LF	\$ 30	\$ 18	\$ 12	\$ -	\$ -	\$ -	\$ -
1.5	Police Support	1,600.0	HR		\$ 120	\$ 27	\$ -	\$ 192,000	\$ 43,200	\$ 235,200
1.6	Additional Traffic Management		LS				\$ -	\$ -	\$ -	\$ -
1.7	Access / Clearing Costs		LS				\$ -	\$ -	\$ -	\$ -
1.8	Snow Removal	40.0	DAY		\$ 1,000	\$ 300	\$ -	\$ 40,000	\$ 12,000	\$ 52,000
1.9	Existing Utility Protection	-	Mile	\$ 40,000	\$ 120,000	\$ 40,000	\$ -	\$ -	\$ -	\$ -
TOTAL - SITE PREP/ACCESS/TRAFFIC MANAGEMENT/ ACCESS:							\$ 64,000	\$ 424,000	\$ 119,200	\$ 607,200
2. ONSHORE CABLE CONDUITS & VAULTS INSTALLATION										
2.1	Trench Box Shoring & Trench Box Install Crew		Miles		\$ 139,800	\$ 93,200	\$ -	\$ -	\$ -	\$ -
2.2	Formwork in Trench		SF	\$ 2	\$ 1.5	\$ 0.5	\$ -	\$ -	\$ -	\$ -
2.3	Trench Excavation		CY		\$ 17.5	\$ 7.5	\$ -	\$ -	\$ -	\$ -
2.4	Supply & Install 6" Sand Bedding for direct bury conduits		SF	\$ 50	\$ 25	\$ 14	\$ -	\$ -	\$ -	\$ -
2.5	Supply & Install Thermal Backfill		CY	\$ 350	\$ 245	\$ 105	\$ -	\$ -	\$ -	\$ -
2.6	Supply & Install Concrete Cap (6")		CY	\$ 200	\$ 125	\$ 50	\$ -	\$ -	\$ -	\$ -
2.7	Native Backfill -direct bury conduits sys Trench		CY		\$ 14.0	\$ 6.0	\$ -	\$ -	\$ -	\$ -
2.8	Supply & Install Ductbank Concrete		CY	\$ 200	\$ 125	\$ 50	\$ -	\$ -	\$ -	\$ -
2.9	Conduit 8" SCH 40PVC		LF	\$ 28.6	\$ 5.7	\$ 2.4	\$ -	\$ -	\$ -	\$ -
2.10	Conduit 4" SCH 40PVC		LF	\$ 9.8	\$ 4.20	\$ 1.8	\$ -	\$ -	\$ -	\$ -
2.11	Conduit 2" SCH 40PVC		LF	\$ 3.5	\$ 3.15	\$ 1.4	\$ -	\$ -	\$ -	\$ -
2.12	Warning Tape		LF	\$ 0.15	\$ 0.25	\$ 0.10	\$ -	\$ -	\$ -	\$ -
2.13	Trench Box Shoring (Vault)		EA	\$ -	\$ 18,079	\$ 27,119	\$ -	\$ -	\$ -	\$ -
2.14	Splice Vault Excavation	0	CY		\$ 17.5	\$ 7.5	\$ -	\$ -	\$ -	\$ -
2.15	Splice Vault Supply & Installation	0	EA	\$ 35,000	\$ 16,500	\$ 38,500	\$ -	\$ -	\$ -	\$ -
2.16	Splice Vault Backfill	0	CY		\$ 14.0	\$ 6.0	\$ -	\$ -	\$ -	\$ -

Item	Item Description	Estimated Quantity	Unit of Measure	Material Supply Rate	Labor Supply Rate	Const. Equipment Rate	Material Supply Cost	Labor Supply Cost	Const. Equipment Cost	TOTAL
2.17	Jack and Bore along Route		LF	\$ 800	\$ 1,600	\$ 1,600	\$ -	\$ -	\$ -	\$ -
2.18	HDD along Route	0	LF	\$ 800	\$ 1,600	\$ 1,600	\$ -	\$ -	\$ -	\$ -
2.19	Air Test Ducts	0	LF			\$ 0.25	\$ -	\$ -	\$ -	\$ -
2.20	PVMT, ASPHALT, 2" SURFACE COURSE	0	SY	\$ 14.00	\$ 14.00	\$ 7.00	\$ -	\$ -	\$ -	\$ -
2.21	PVMT, AGGREGATE, 10", BASE COURSE	0	CY	\$ 22.38	\$ 23.50	\$ 10.07	\$ -	\$ -	\$ -	\$ -
2.22	Concrete Ductbank Thermal Resistivity Testing (every 100CY of concrete poured)	0	EA		\$ 400	\$ 1,200	\$ -	\$ -	\$ -	\$ -
2.23	Concrete Ductbank Compressive Strength Testing (every 100CY of concrete poured)	0	EA		\$ 10	\$ 15	\$ -	\$ -	\$ -	\$ -
2.24	Backfill Thermal Resistivity Testing (every 100CY of backfill placed)	0	EA		\$ 400	\$ 1,200	\$ -	\$ -	\$ -	\$ -
2.25	Additional misc. testing allowance (Native Backfill, Asphalt Density, Concrete Curb etc.)		LS		\$ 448,266	\$ 298,844	\$ -	\$ -	\$ -	\$ -
2.26	Excess Materials Disposal to Certified Backfill	0	CY		\$ 24.5	\$ 10.5	\$ -	\$ -	\$ -	\$ -
2.27	Rock Excavation and Removal		LS				\$ -	\$ -	\$ -	\$ -
2.28	Dewatering		EA			\$ 4,000	\$ -	\$ -	\$ -	\$ -
2.29	Contaminated Water Treatment and Disposal		LS				\$ -	\$ -	\$ -	\$ -
2.30	Contaminated Spoils Disposal		LS				\$ -	\$ -	\$ -	\$ -
2.31	Excavated material - stockpile management		CF		\$ 1.0	\$ 0.5	\$ -	\$ -	\$ -	\$ -
TOTAL - ONSHORE CABLE CONDUITS & VAULTS INSTALLATION:							\$ -	\$ -	\$ -	\$ -
3. ONSHORE CABLE PROCUREMENT AND INSTALLATION										
3.1	Circuit #1- Procurement & Installation- 138kV 5000 kcmil copper XLPE	41,184	FT	\$ 145	\$ 87	\$ 58	\$ 5,971,680	\$ 3,583,008	\$ 2,388,672	\$ 11,943,360
3.2	Circuit #1- Cable Splicing- 138kV 5000 kcmil copper XLPE	24	EA	\$ 5,898	\$ 9,846	\$ 2,813	\$ 141,552	\$ 236,316	\$ 67,519	\$ 445,386
3.3	Circuit #1- Cable Termination- 138kV 5000 kcmil copper XLPE	6	EA	\$ 5,664	\$ 9,846	\$ 2,813	\$ 33,984	\$ 59,079	\$ 16,880	\$ 109,943
3.4	Circuit #2- Procurement & Installation- 138kV 5000 kcmil copper XLPE		FT	\$ 145	\$ 87	\$ 58	\$ -	\$ -	\$ -	\$ -
3.5	Circuit #2- Cable Splicing- 138kV 5000 kcmil copper XLPE		EA	\$ 5,898	\$ 9,846	\$ 2,813	\$ -	\$ -	\$ -	\$ -
3.6	Circuit #2- Cable Termination- 138kV 5000 kcmil copper XLPE		EA	\$ 5,664	\$ 9,846	\$ 2,813	\$ -	\$ -	\$ -	\$ -
3.7	Circuit #3- Procurement & Installation- 138kV 5000 kcmil copper XLPE		FT	\$ 145	\$ 87	\$ 58	\$ -	\$ -	\$ -	\$ -
3.8	Circuit #3- Cable Splicing- 138kV 5000 kcmil copper XLPE		EA	\$ 5,898	\$ 9,846	\$ 2,813	\$ -	\$ -	\$ -	\$ -
3.9	Circuit #3- Cable Termination- 138kV 5000 kcmil copper XLPE		EA	\$ 5,664	\$ 9,846	\$ 2,813	\$ -	\$ -	\$ -	\$ -
3.10	Link Box & MH racking	8	EA	\$ 26,659	\$ 15,995	\$ 10,664	\$ 213,272	\$ 127,963	\$ 85,309	\$ 426,544
3.11	Fiber Optic Cable	13,728	FT	\$ 7	\$ 3	\$ 2	\$ 101,546	\$ 45,722	\$ 30,482	\$ 177,750
3.12	Ground Continuity Conductor	13,728	FT	\$ 13	\$ 8	\$ 5	\$ 178,999	\$ 103,331	\$ 68,887	\$ 351,217
TOTAL - ONSHORE CABLE PROCUREMENT AND INSTALLATION							\$ 6,641,033	\$ 4,155,419	\$ 2,657,748	\$ 13,454,200
Comp 4 - Dunwoodie To New Rochelle Landing 345kV Onshore UG Cables -single circuit(EGC To Dunwoodie 345 kV)							\$ 6,705,033	\$ 4,579,419	\$ 2,776,948	\$ 14,061,400
4. MOB/DEMOB, ENGINEERING, PERMITTING, T&C, PM & INDIRECTS										
	Contractor Mobilization / Demobilization									
4.1	Mob / Demob	1	LS		\$ 220,691	\$ 147,127	\$ -	\$ 220,691	\$ 147,127	\$ 367,818
	Project Management, Material Handling & Amenities									
4.2	Preconstruction Supervision (Engineering, Permitting, Procurement)	1	LS		140,614.00		\$ -	\$ 140,614	\$ -	\$ 140,614
4.3	Construction Project Management / Supervision	1	LS		562,456.00		\$ -	\$ 562,456	\$ -	\$ 562,456
4.4	Utility PM and Project Oversight	1	LS		140,614.00		\$ -	\$ 140,614	\$ -	\$ 140,614
4.5	Site Accommodation, Facilities, Storage	1	LS	140,614.00			\$ 140,614	\$ -	\$ -	\$ 140,614
	Engineering									
4.6	Design Engineering	1.0	LS		\$ 703,070	\$ -	\$ -	\$ 703,070	\$ -	\$ 703,070
4.7	LiDAR /GPR	-	LS		\$ 25,311	\$ 16,874	\$ -	\$ -	\$ -	\$ -
4.8	Geotech	-	EA		2,730.00	1,820.00	\$ -	\$ -	\$ -	\$ -
4.9	Surveying/Staking	1	LS		\$ 59,058	\$ 39,372	\$ -	\$ 59,058	\$ 39,372	\$ 98,430
	Testing & Commissioning									
4.10	Testing & Commissioning of T-Line and Equipment	1	EA		\$ -		\$ -	\$ -	\$ -	\$ -
	Permitting, Indirects and Additional Costs									
4.11	Environmental Licensing & Permitting Costs & related legal cost	1	LS		\$ 140,614		\$ -	\$ 140,614	\$ -	\$ 140,614
4.12	Environmental-special studies/investigation		LS		\$ -		\$ -	\$ -	\$ -	\$ -
4.13	Warranties / LOC's	1	LS		\$ 42,184		\$ -	\$ 42,184	\$ -	\$ 42,184
4.14	Laydown Lease & temporary easement	1	LS		\$ 500,000		\$ -	\$ 500,000	\$ -	\$ 500,000
4.15	Real Estate ( Acquisition)		LS				\$ -	\$ -	\$ -	\$ -
4.16	Legal Fees (Real estate)	-	LS		-	-	\$ -	\$ -	\$ -	\$ -
4.17	Insurance	-	LS		-	-	\$ -	\$ -	\$ -	\$ -
4.18	Insurance (specialty, e.g. railroad)		Crossing			\$ 1,000	\$ -	\$ -	\$ -	\$ -
4.19	Bonds	1	LS			\$ 500,000	\$ -	\$ -	\$ 500,000	\$ 500,000
4.20	Sales Tax on Materials	8.88%	% of material cost	\$ 6,705,033.41			\$ 595,407	\$ -	\$ -	\$ 595,407
4.21	Fees for permits, including roadway, railroad, building or other local permits	1	LS			\$ 14,061	\$ -	\$ -	\$ 14,061	\$ 14,061
TOTAL - MOB/DEMOB, ENGINEERING, PERMITTING, T&C, PM & INDIRECTS:							\$ 736,021	\$ 2,509,301	\$ 700,561	\$ 3,945,883



NEXtera Energy- TO36 Core 1

Comp 113 - Jamaica to East Garden City 138kV Onshore UG Cables -Single circuit

Total:     \$        232,454,478

NEXtera Energy- TO36 Core 1				
	Material Supply	Labor Supply	Equip Supply	Total
Comp 113 - Jamaica to East Garden City 138kV Onshore UG Cables -Single circuit				
1. SITE PREP/ACCESS/TRAFFIC MANAGEMENT	\$ 2,875,456	\$ 14,141,314	\$ 5,663,742	\$ 22,680,512
2. ONSHORE CABLE CONDUITS & VAULTS INSTALLATION	\$ 19,840,547	\$ 15,583,902	\$ 9,822,382	\$ 45,246,831
3. ONSHORE CABLE PROCUREMENT AND INSTALLATION	\$ 30,983,420	\$ 19,257,602	\$ 12,388,277	\$ 62,629,299
4. MOB/DEMOB, ENGINEERING, PERMITTING, T&C, PM & INDIRECTS	\$ 6,074,075	\$ 20,680,283	\$ 6,851,768	\$ 33,606,126
SUBTOTAL (Costs):	\$ 59,773,498	\$ 69,663,101	\$ 34,726,168	\$ 164,162,767
CONTRACTOR MARK-UP (OH&P)	\$ 10,759,230	\$ 12,539,358	\$ 6,250,710	\$ 29,549,298
SUBTOTAL:	\$ 70,532,728	\$ 82,202,459	\$ 40,976,879	\$ 193,712,065
CONTINGENCY ON ENTIRE PROJECT	\$ 14,106,546	\$ 16,440,492	\$ 8,195,376	\$ 38,742,413
TOTAL:	\$ 84,639,274	\$ 98,642,950	\$ 49,172,254	\$ 232,454,478

Description of Work: Jamaica to East Garden City. 5000 kcmil copper XLPE (300/400/500 MVA), single cable per phase. (Double circuit for 138 and 345kv -11.08 miles and Single circuit for 138kv -0.51 miles)										
Item	Item Description	Estimated Quantity	Unit of Measure	Material Supply Rate	Labor Supply Rate	Const. Equipment Rate	Material Supply Cost	Labor Supply Cost	Const. Equipment Cost	TOTAL
Comp 113 - Jamaica to East Garden City 138kV Onshore UG Cables -Single circuit										
1. SITE PREP/ACCESS/TRAFFIC MANAGEMENT										
1.1	Environmental BMPs / SWPPP Installation, Maintenance & Repairs	0	LF	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
1.2	Existing Utility Conflict and Relocation	11.59	Mile		\$ 700,000	\$ 300,000	\$ -	\$ 8,113,000	\$ 3,477,000	\$ 11,590,000
1.3	Flaggers	360	DAY	\$ 1,600	\$ 4,800	\$ 1,600	\$ 576,000	\$ 1,728,000	\$ 576,000	\$ 2,880,000
1.4	K Rail / Lane Control / Metal Plates	61,195	LF	\$ 30	\$ 18	\$ 12	\$ 1,835,856	\$ 1,101,514	\$ 734,342	\$ 3,671,712
1.5	Police Support	14,400.0	HR		\$ 120	\$ 27	\$ -	\$ 1,728,000	\$ 388,800	\$ 2,116,800
1.6	Additional Traffic Management		LS				\$ -	\$ -	\$ -	\$ -
1.7	Access / Clearing Costs		LS				\$ -	\$ -	\$ -	\$ -
1.8	Snow Removal	80.0	DAY		\$ 1,000	\$ 300	\$ -	\$ 80,000	\$ 24,000	\$ 104,000
1.9	Existing Utility Protection	11.59	Mile	\$ 40,000	\$ 120,000	\$ 40,000	\$ 463,600	\$ 1,390,800	\$ 463,600	\$ 2,318,000
TOTAL - SITE PREP/ACCESS/TRAFFIC MANAGEMENT/ ACCESS:							\$ 2,875,456	\$ 14,141,314	\$ 5,663,742	\$ 22,680,512
2. ONSHORE CABLE CONDUITS & VAULTS INSTALLATION										
2.1	Trench Box Shoring & Trench Box Install Crew	11.59	Miles		\$ 139,800	\$ 93,200	\$ -	\$ 1,620,282	\$ 1,080,188	\$ 2,700,470
2.2	Formwork in Trench	480,266	SF	\$ 2	\$ 1.5	\$ 0.5	\$ 960,531	\$ 720,398	\$ 240,133	\$ 1,921,062
2.3	Trench Excavation	40,022	CY		\$ 17.5	\$ 7.5	\$ -	\$ 700,387	\$ 300,166	\$ 1,000,553
2.4	Supply & Install 6" Sand Bedding for direct bury conduits	2,501	SF	\$ 50	\$ 25	\$ 14	\$ 125,069	\$ 61,284	\$ 35,019	\$ 221,372
2.5	Supply & Install Thermal Backfill	21,012	CY	\$ 350	\$ 245	\$ 105	\$ 7,354,067	\$ 5,147,847	\$ 2,206,220	\$ 14,708,134
2.6	Supply & Install Concrete Cap (6")	0	CY	\$ 200	\$ 125	\$ 50	\$ -	\$ -	\$ -	\$ -
2.7	Native Backfill -direct bury conduits sys Trench	0	CY		\$ 14.0	\$ 6.0	\$ -	\$ -	\$ -	\$ -
2.8	Supply & Install Ductbank Concrete	9,782	CY	\$ 200	\$ 125	\$ 50	\$ 1,956,415	\$ 1,222,760	\$ 489,104	\$ 3,668,279
2.9	Conduit 8" SCH 40PVC	244,781	LF	\$ 28.6	\$ 5.7	\$ 2.4	\$ 7,000,731	\$ 1,387,907	\$ 594,817	\$ 8,983,455
2.10	Conduit 4" SCH 40PVC	0	LF	\$ 9.8	\$ 4.20	\$ 1.8	\$ -	\$ -	\$ -	\$ -
2.11	Conduit 2" SCH 40PVC	122,390	LF	\$ 3.5	\$ 3.15	\$ 1.4	\$ 430,814	\$ 385,530	\$ 165,227	\$ 981,571
2.12	Warning Tape	122,390	LF	\$ 0.15	\$ 0.25	\$ 0.10	\$ 18,359	\$ 12,239	\$ 6,195	\$ 31,195
2.13	Trench Box Shoring (Vault)	38	EA	\$ -	\$ 18,079	\$ 27,119	\$ -	\$ 687,006	\$ 1,030,508	\$ 1,717,514
2.14	Splice Vault Excavation	5,202	CY		\$ 17.5	\$ 7.5	\$ -	\$ 91,031	\$ 39,013	\$ 130,044
2.15	Splice Vault Supply & Installation	38	EA	\$ 35,000	\$ 16,500	\$ 38,500	\$ 1,330,000	\$ 627,000	\$ 1,463,000	\$ 3,420,000
2.16	Splice Vault Backfill	1,561	CY		\$ 14.0	\$ 6.0	\$ -	\$ 21,847	\$ 9,363	\$ 31,211
2.17	Jack and Bore along Route	250	LF	\$ 800	\$ 1,600	\$ 1,600	\$ 200,000	\$ 400,000	\$ 400,000	\$ 1,000,000
2.18	HDD along Route	0	LF	\$ 800	\$ 1,600	\$ 1,600	\$ -	\$ -	\$ -	\$ -

Item	Item Description	Estimated Quantity	Unit of Measure	Material Supply Rate	Labor Supply Rate	Const. Equipment Rate	Material Supply Cost	Labor Supply Cost	Const. Equipment Cost	TOTAL
2.19	Air Test Ducts	367,171	LF			\$ 0.25	\$ -	\$ -	\$ 91,793	\$ 91,793
2.20	PVMT, ASPHALT, 2" SURFACE COURSE	22,979	SY	\$ 14.00	\$ 14.00	\$ 7.00	\$ 321,707	\$ 321,707	\$ 160,854	\$ 804,269
2.21	PVMT, AGGREGATE, 10" , BASE COURSE	6,383	CY	\$ 22.38	\$ 23.50	\$ 10.07	\$ 142,853	\$ 149,996	\$ 64,284	\$ 357,134
2.22	Concrete Ductbank Thermal Resistivity Testing (every 100CY of concrete poured)	98	EA		\$ 400	\$ 1,200	\$ -	\$ 39,128	\$ 117,385	\$ 156,513
2.23	Concrete Ductbank Compressive Strength Testing (every 100CY of concrete poured)	98	EA		\$ 10	\$ 15	\$ -	\$ 978	\$ 1,467	\$ 2,446
2.24	Backfill Thermal Resistivity Testing (every 100CY of backfill placed)	210	EA		\$ 400	\$ 1,200	\$ -	\$ 84,046	\$ 252,139	\$ 336,186
2.25	Additional misc. testing allowance (Native Backfill, Asphalt Density, Concrete Curb etc.)	1	LS		\$ 448,266	\$ 298,844	\$ -	\$ 448,266	\$ 298,844	\$ 747,110
2.26	Excess Materials Disposal to Certified Backfill	56,762	CY		\$ 24.5	\$ 10.5	\$ -	\$ 1,390,679	\$ 596,005	\$ 1,986,684
2.27	Rock Excavation and Removal	1	LS				\$ -	\$ -	\$ -	\$ -
2.28	Dewatering	38	EA			\$ 4,000	\$ -	\$ -	\$ 152,000	\$ 152,000
2.29	Contaminated Water Treatment and Disposal	1	LS				\$ -	\$ -	\$ -	\$ -
2.30	Contaminated Spoils Disposal	1	LS				\$ -	\$ -	\$ -	\$ -
2.31	Excavated material - stockpile management	45,224	CF		\$ 1.0	\$ 0.5	\$ -	\$ 45,224	\$ 22,612	\$ 67,836
TOTAL - ONSHORE CABLE CONDUITS & VAULTS INSTALLATION:							\$ 19,840,547	\$ 15,583,902	\$ 9,822,382	\$ 45,246,831
3. ONSHORE CABLE PROCUREMENT AND INSTALLATION										
3.1	Circuit #1- Procurement & Installation- 138kV 5000 kcmil copper XLPE	192,765	FT	\$ 145	\$ 87	\$ 58	\$ 27,950,908	\$ 16,770,545	\$ 11,180,363	\$ 55,901,815
3.2	Circuit #1- Cable Splicing- 138kV 5000 kcmil copper XLPE	114	EA	\$ 5,898	\$ 9,846	\$ 2,813	\$ 672,372	\$ 1,122,499	\$ 320,714	\$ 2,115,585
3.3	Circuit #1- Cable Termination- 138kV 5000 kcmil copper XLPE	6	EA	\$ 5,664	\$ 9,846	\$ 2,813	\$ 33,984	\$ 59,079	\$ 16,880	\$ 109,943
3.4	Circuit #2- Procurement & Installation- 138kV 5000 kcmil copper XLPE		FT	\$ 145	\$ 87	\$ 58	\$ -	\$ -	\$ -	\$ -
3.5	Circuit #2- Cable Splicing- 138kV 5000 kcmil copper XLPE		EA	\$ 5,898	\$ 9,846	\$ 2,813	\$ -	\$ -	\$ -	\$ -
3.6	Circuit #2- Cable Termination- 138kV 5000 kcmil copper XLPE		EA	\$ 5,664	\$ 9,846	\$ 2,813	\$ -	\$ -	\$ -	\$ -
3.7	Circuit #3- Procurement & Installation- 138kV 5000 kcmil copper XLPE		FT	\$ 145	\$ 87	\$ 58	\$ -	\$ -	\$ -	\$ -
3.8	Circuit #3- Cable Splicing- 138kV 5000 kcmil copper XLPE		EA	\$ 5,898	\$ 9,846	\$ 2,813	\$ -	\$ -	\$ -	\$ -
3.9	Circuit #3- Cable Termination- 138kV 5000 kcmil copper XLPE		EA	\$ 5,664	\$ 9,846	\$ 2,813	\$ -	\$ -	\$ -	\$ -
3.10	Link Box & MH racking	38	EA	\$ 26,659	\$ 15,995	\$ 10,664	\$ 1,013,042	\$ 607,825	\$ 405,217	\$ 2,026,084
3.11	Fiber Optic Cable	64,255	FT	\$ 7	\$ 3	\$ 2	\$ 475,294	\$ 214,008	\$ 142,672	\$ 831,973
3.12	Ground Continuity Conductor	64,255	FT	\$ 13	\$ 8	\$ 5	\$ 837,820	\$ 483,647	\$ 322,431	\$ 1,643,899
TOTAL - ONSHORE CABLE PROCUREMENT AND INSTALLATION							\$ 30,983,420	\$ 19,257,602	\$ 12,388,277	\$ 62,629,299
Comp 4 - Dunwoodie To New Rochelle Landing 345kV Onshore UG Cables -single circuit(EGC To Dunwoodie 345 kV)							\$ 53,699,423	\$ 48,982,817	\$ 27,874,401	\$ 130,556,641
4. MOB/DEMOB, ENGINEERING, PERMITTING, T&C, PM & INDIRECTS										
	Contractor Mobilization / Demobilization									
4.1	Mob / Demob	1	LS		\$ 2,305,717	\$ 1,537,144	\$ -	\$ 2,305,717	\$ 1,537,144	\$ 3,842,861
	Project Management, Material Handling & Amenities									
4.2	Preconstruction Supervision (Engineering, Permitting, Procurement)	1	LS		1,305,566.41		\$ -	\$ 1,305,566	\$ -	\$ 1,305,566
4.3	Construction Project Management / Supervision	1	LS		5,222,265.65		\$ -	\$ 5,222,266	\$ -	\$ 5,222,266
4.4	Utility PM and Project Oversight	1	LS		1,305,566.41		\$ -	\$ 1,305,566	\$ -	\$ 1,305,566
4.5	Site Accommodation, Facilities, Storage	1	LS	1,305,566.41			\$ 1,305,566	\$ -	\$ -	\$ 1,305,566
	Engineering									
4.6	Design Engineering	1.0	LS		\$ 6,527,832	\$ -	\$ -	\$ 6,527,832	\$ -	\$ 6,527,832
4.7	LiDAR /GPR	1.0	LS		\$ 235,002	\$ 156,668	\$ -	\$ 235,002	\$ 156,668	\$ 391,670
4.8	Geotech	12.00	EA		2,730.00	1,820.00	\$ -	\$ 32,760	\$ 21,840	\$ 54,600
4.9	Surveying/Staking	1	LS		\$ 548,338	\$ 365,559	\$ -	\$ 548,338	\$ 365,559	\$ 913,896
	Testing & Commissioning									
4.10	Testing & Commissioning of T-Line and Equipment	1	EA		\$ -		\$ -	\$ -	\$ -	\$ -
	Permitting, Indirects and Additional Costs									
4.11	Environmental Licensing & Permitting Costs & related legal cost	1	LS		\$ 1,305,566		\$ -	\$ 1,305,566	\$ -	\$ 1,305,566
4.12	Environmental-special studies/investigation		LS		\$ -		\$ -	\$ -	\$ -	\$ -
4.13	Warranties / LOC's	1	LS		\$ 391,670		\$ -	\$ 391,670	\$ -	\$ 391,670
4.14	Laydown Lease & temporary easement	1	LS		\$ 1,500,000		\$ -	\$ 1,500,000	\$ -	\$ 1,500,000
4.15	Real Estate ( Acquisition)		LS				\$ -	\$ -	\$ -	\$ -
4.16	Legal Fees (Real estate)	-	LS		-	-	\$ -	\$ -	\$ -	\$ -
4.17	Insurance	-	LS		-	-	\$ -	\$ -	\$ -	\$ -
4.18	Insurance (specialty, e.g. railroad)		Crossing			\$ 1,000	\$ -	\$ -	\$ -	\$ -
4.19	Bonds	1	LS			\$ 4,640,000	\$ -	\$ -	\$ 4,640,000	\$ 4,640,000
4.20	Sales Tax on Materials	8.88%	% of material cost	\$ 53,699,423.07			\$ 4,768,509	\$ -	\$ -	\$ 4,768,509
4.21	Fees for permits, including roadway, railroad, building or other local permits	1	LS			\$ 130,557	\$ -	\$ -	\$ 130,557	\$ 130,557
TOTAL - MOB/DEMOB, ENGINEERING, PERMITTING, T&C, PM & INDIRECTS:							\$ 6,074,075	\$ 20,680,283	\$ 6,851,768	\$ 33,606,126

NEXtera Energy- TO36 Core 1

Comp XX - Ruland Road - Newbridge138 kV #3 (567 Line) Onshore UG Cables -Single circuit

Total:     \$        5,354,910

NEXtera Energy- TO36 Core 1				
	Material Supply	Labor Supply	Equip Supply	Total
Comp XX - Ruland Road - Newbridge138 kV #3 (567 Line) Onshore UG Cables -Single circuit				
1. SITE PREP/ACCESS/TRAFFIC MANAGEMENT	\$ 103,680	\$ 467,008	\$ 139,872	\$ 710,560
2. ONSHORE CABLE CONDUITS & VAULTS INSTALLATION	\$ 350,497	\$ 277,908	\$ 192,142	\$ 820,547
3. ONSHORE CABLE PROCUREMENT AND INSTALLATION	\$ 516,796	\$ 366,133	\$ 210,329	\$ 1,093,258
4. MOB/DEMOB, ENGINEERING, PERMITTING, T&C, PM & INDIRECTS	\$ 112,466	\$ 890,875	\$ 154,010	\$ 1,157,351
SUBTOTAL (Costs):	\$ 1,083,440	\$ 2,001,924	\$ 696,353	\$ 3,781,716
CONTRACTOR MARK-UP (OH&P)	\$ 195,019	\$ 360,346	\$ 125,343	\$ 680,709
SUBTOTAL:	\$ 1,278,459	\$ 2,362,270	\$ 821,696	\$ 4,462,425
CONTINGENCY ON ENTIRE PROJECT	\$ 255,692	\$ 472,454	\$ 164,339	\$ 892,485
TOTAL:	\$ 1,534,151	\$ 2,834,724	\$ 986,035	\$ 5,354,910

Description of Work: Rebuild 0.2 mile of UG line (trench, conduits and cable), single cable per phase.										
Item	Item Description	Estimated Quantity	Unit of Measure	Material Supply Rate	Labor Supply Rate	Const. Equipment Rate	Material Supply Cost	Labor Supply Cost	Const. Equipment Cost	TOTAL
Comp XX - Ruland Road - Newbridge138 kV #3 (567 Line) Onshore UG Cables -Single circuit										
1. SITE PREP/ACCESS/TRAFFIC MANAGEMENT										
1.1	Environmental BMPs / SWPPP Installation, Maintenance & Repairs	0	LF	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
1.2	Existing Utility Conflict and Relocation	0.20	Mile				\$ -	\$ -	\$ -	\$ -
1.3	Flaggers	40	DAY	\$ 1,600	\$ 4,800	\$ 1,600	\$ 64,000	\$ 192,000	\$ 64,000	\$ 320,000
1.4	K Rail / Lane Control / Metal Plates	1,056	LF	\$ 30	\$ 18	\$ 12	\$ 31,680	\$ 19,008	\$ 12,672	\$ 63,360
1.5	Police Support	1,600.0	HR		\$ 120	\$ 27	\$ -	\$ 192,000	\$ 43,200	\$ 235,200
1.6	Additional Traffic Management		LS				\$ -	\$ -	\$ -	\$ -
1.7	Access / Clearing Costs		LS				\$ -	\$ -	\$ -	\$ -
1.8	Snow Removal	40.0	DAY		\$ 1,000	\$ 300	\$ -	\$ 40,000	\$ 12,000	\$ 52,000
1.9	Existing Utility Protection	0.20	Mile	\$ 40,000	\$ 120,000	\$ 40,000	\$ 8,000	\$ 24,000	\$ 8,000	\$ 40,000
TOTAL - SITE PREP/ACCESS/TRAFFIC MANAGEMENT/ ACCESS:							\$ 103,680	\$ 467,008	\$ 139,872	\$ 710,560
2. ONSHORE CABLE CONDUITS & VAULTS INSTALLATION										
2.1	Trench Box Shoring & Trench Box Install Crew	0.20	Miles		\$ 139,800	\$ 93,200	\$ -	\$ 27,960	\$ 18,640	\$ 46,600
2.2	Formwork in Trench	8,256	SF	\$ 2	\$ 1.5	\$ 0.5	\$ 16,512	\$ 12,384	\$ 4,128	\$ 33,024
2.3	Trench Excavation	688	CY		\$ 17.5	\$ 7.5	\$ -	\$ 12,040	\$ 5,160	\$ 17,200
2.4	Supply & Install 6" Sand Bedding for direct bury conduits	43	SF	\$ 50	\$ 25	\$ 14	\$ 2,150	\$ 1,054	\$ 602	\$ 3,806
2.5	Supply & Install Thermal Backfill	361	CY	\$ 350	\$ 245	\$ 105	\$ 126,420	\$ 88,494	\$ 37,926	\$ 252,840
2.6	Supply & Install Concrete Cap (6")	0	CY	\$ 200	\$ 125	\$ 50	\$ -	\$ -	\$ -	\$ -
2.7	Native Backfill -direct bury conduits sys Trench	0	CY		\$ 14.0	\$ 6.0	\$ -	\$ -	\$ -	\$ -
2.8	Supply & Install Ductbank Concrete	168	CY	\$ 200	\$ 125	\$ 50	\$ 33,632	\$ 21,020	\$ 8,408	\$ 63,060
2.9	Conduit 8" SCH 40PVC	4,224	LF	\$ 28.6	\$ 5.7	\$ 2.4	\$ 120,806	\$ 23,950	\$ 10,264	\$ 155,021
2.10	Conduit 4" SCH 40PVC	0	LF	\$ 9.8	\$ 4.20	\$ 1.8	\$ -	\$ -	\$ -	\$ -
2.11	Conduit 2" SCH 40PVC	2,112	LF	\$ 3.5	\$ 3.15	\$ 1.4	\$ 7,434	\$ 6,653	\$ 2,851	\$ 16,938
2.12	Warning Tape	2,112	LF	\$ 0.15	\$ 0.25	\$ 0.10	\$ 317	\$ 528	\$ 211	\$ 1,056
2.13	Trench Box Shoring (Vault)	1	EA	\$ -	\$ 18,079	\$ 27,119	\$ -	\$ 18,079	\$ 27,119	\$ 45,198
2.14	Splice Vault Excavation	137	CY		\$ 17.5	\$ 7.5	\$ -	\$ 2,396	\$ 1,027	\$ 3,422
2.15	Splice Vault Supply & Installation	1	EA	\$ 35,000	\$ 16,500	\$ 38,500	\$ 35,000	\$ 16,500	\$ 38,500	\$ 90,000
2.16	Splice Vault Backfill	41	CY		\$ 14.0	\$ 6.0	\$ -	\$ 575	\$ 246	\$ 821
2.17	Jack and Bore along Route	0	LF	\$ 800	\$ 1,600	\$ 1,600	\$ -	\$ -	\$ -	\$ -
2.18	HDD along Route	0	LF	\$ 800	\$ 1,600	\$ 1,600	\$ -	\$ -	\$ -	\$ -

Item	Item Description	Estimated Quantity	Unit of Measure	Material Supply Rate	Labor Supply Rate	Const. Equipment Rate	Material Supply Cost	Labor Supply Cost	Const. Equipment Cost	TOTAL
2.19	Air Test Ducts	6,336	LF			\$ 0.25	\$ -	\$ -	\$ 1,584	\$ 1,584
2.20	PVMT, ASPHALT, 2" SURFACE COURSE	407	SY	\$ 14.00	\$ 14.00	\$ 7.00	\$ 5,696	\$ 5,696	\$ 2,848	\$ 14,241
2.21	PVMT, AGGREGATE, 10", BASE COURSE	113	CY	\$ 22.38	\$ 23.50	\$ 10.07	\$ 2,529	\$ 2,656	\$ 1,138	\$ 6,324
2.22	Concrete Ductbank Thermal Resistivity Testing (every 100CY of concrete poured)	2	EA		\$ 400	\$ 1,200	\$ -	\$ 673	\$ 2,018	\$ 2,691
2.23	Concrete Ductbank Compressive Strength Testing (every 100CY of concrete poured)	2	EA		\$ 10	\$ 15	\$ -	\$ 17	\$ 25	\$ 42
2.24	Backfill Thermal Resistivity Testing (every 100CY of backfill placed)	4	EA		\$ 400	\$ 1,200	\$ -	\$ 1,445	\$ 4,334	\$ 5,779
2.25	Additional misc. testing allowance (Native Backfill, Asphalt Density, Concrete Curb etc.)	1	LS		\$ 10,000	\$ 10,000	\$ -	\$ 10,000	\$ 10,000	\$ 20,000
2.26	Excess Materials Disposal to Certified Backfill	1,019	CY		\$ 24.5	\$ 10.5	\$ -	\$ 24,965	\$ 10,699	\$ 35,664
2.27	Rock Excavation and Removal	1	LS				\$ -	\$ -	\$ -	\$ -
2.28	Dewatering	1	EA			\$ 4,000	\$ -	\$ -	\$ 4,000	\$ 4,000
2.29	Contaminated Water Treatment and Disposal	1	LS				\$ -	\$ -	\$ -	\$ -
2.30	Contaminated Spoils Disposal	1	LS				\$ -	\$ -	\$ -	\$ -
2.31	Excavated material - stockpile management	825	CF		\$ 1.0	\$ 0.5	\$ -	\$ 825	\$ 412	\$ 1,237
TOTAL - ONSHORE CABLE CONDUITS & VAULTS INSTALLATION:							\$ 350,497	\$ 277,908	\$ 192,142	\$ 820,547
3. ONSHORE CABLE PROCUREMENT AND INSTALLATION										
3.1	Circuit #1- Procurement & Installation- 138kV 5000 kcmil copper XLPE	3,326	FT	\$ 125	\$ 75	\$ 50	\$ 415,800	\$ 249,480	\$ 166,320	\$ 831,600
3.2	Circuit #1- Cable Splicing- 138kV 5000 kcmil copper XLPE	3	EA	\$ 5,898	\$ 9,846	\$ 2,813	\$ 17,694	\$ 29,539	\$ 8,440	\$ 55,673
3.3	Circuit #1- Cable Termination- 138kV 5000 kcmil copper XLPE	6	EA	\$ 5,664	\$ 9,846	\$ 2,813	\$ 33,984	\$ 59,079	\$ 16,880	\$ 109,943
3.4	Circuit #2- Procurement & Installation- 138kV 5000 kcmil copper XLPE		FT	\$ 125	\$ 75	\$ 50	\$ -	\$ -	\$ -	\$ -
3.5	Circuit #2- Cable Splicing- 138kV 5000 kcmil copper XLPE		EA	\$ 5,898	\$ 9,846	\$ 2,813	\$ -	\$ -	\$ -	\$ -
3.6	Circuit #2- Cable Termination- 138kV 5000 kcmil copper XLPE		EA	\$ 5,664	\$ 9,846	\$ 2,813	\$ -	\$ -	\$ -	\$ -
3.7	Circuit #3- Procurement & Installation- 138kV 5000 kcmil copper XLPE		FT	\$ 125	\$ 75	\$ 50	\$ -	\$ -	\$ -	\$ -
3.8	Circuit #3- Cable Splicing- 138kV 5000 kcmil copper XLPE		EA	\$ 5,898	\$ 9,846	\$ 2,813	\$ -	\$ -	\$ -	\$ -
3.9	Circuit #3- Cable Termination- 138kV 5000 kcmil copper XLPE		EA	\$ 5,664	\$ 9,846	\$ 2,813	\$ -	\$ -	\$ -	\$ -
3.10	Link Box & MH racking	1	EA	\$ 26,659	\$ 15,995	\$ 10,664	\$ 26,659	\$ 15,995	\$ 10,664	\$ 53,318
3.11	Fiber Optic Cable	1,109	FT	\$ 7	\$ 3	\$ 2	\$ 8,202	\$ 3,693	\$ 2,462	\$ 14,357
3.12	Ground Continuity Conductor	1,109	FT	\$ 13	\$ 8	\$ 5	\$ 14,458	\$ 8,346	\$ 5,564	\$ 28,368
TOTAL - INSULATORS, FITTINGS, HARDWARE:							\$ 516,796	\$ 366,133	\$ 210,329	\$ 1,093,258
Comp 4 - Dunwoodie To New Rochelle Landing 345kV Onshore UG Cables -single circuit(EGC To Dunwoodie 345 kV)							\$ 970,974	\$ 1,111,049	\$ 542,343	\$ 2,624,365
4. MOB/DEMOB, ENGINEERING, PERMITTING, T&C, PM & INDIRECTS										
	Contractor Mobilization / Demobilization									
4.1	Mob / Demob	1	LS		\$ 49,602	\$ 33,068	\$ -	\$ 49,602	\$ 33,068	\$ 82,670
	Project Management, Material Handling & Amenities									
4.2	Preconstruction Supervision (Engineering, Permitting, Procurement)	1	LS		26,243.65		\$ -	\$ 26,244	\$ -	\$ 26,244
4.3	Construction Project Management / Supervision	1	LS		104,974.61		\$ -	\$ 104,975	\$ -	\$ 104,975
4.4	Utility PM and Project Oversight	1	LS		26,243.65		\$ -	\$ 26,244	\$ -	\$ 26,244
4.5	Site Accommodation, Facilities, Storage	1	LS	26,243.65			\$ 26,244	\$ -	\$ -	\$ 26,244
	Engineering									
4.6	Design Engineering	1.0	LS		\$ 131,218	\$ -	\$ -	\$ 131,218	\$ -	\$ 131,218
4.7	LIDAR /GPR	1.0	LS		\$ 4,724	\$ 3,149	\$ -	\$ 4,724	\$ 3,149	\$ 7,873
4.8	Geotech	1.00	EA		2,730	1,820	\$ -	\$ 2,730	\$ 1,820	\$ 4,550
4.9	Surveying/Staking	1	LS		\$ 11,022	\$ 7,348	\$ -	\$ 11,022	\$ 7,348	\$ 18,371
	Testing & Commissioning									
4.10	Testing & Commissioning of T-Line and Equipment	1	EA		\$ -		\$ -	\$ -	\$ -	\$ -
	Permitting, Indirects and Additional Costs									
4.11	Environmental Licensing & Permitting Costs & related legal cost	1	LS		\$ 26,244		\$ -	\$ 26,244	\$ -	\$ 26,244
4.12	Environmental-special studies/investigation		LS		\$ -		\$ -	\$ -	\$ -	\$ -
4.13	Warranties / LOC's	1	LS		\$ 7,873		\$ -	\$ 7,873	\$ -	\$ 7,873
4.14	Laydown Lease & temporary easement	1	LS		\$ 500,000		\$ -	\$ 500,000	\$ -	\$ 500,000
4.15	Real Estate ( Acquisition)		LS				\$ -	\$ -	\$ -	\$ -
4.16	Legal Fees (Real estate)	-	LS		-	-	\$ -	\$ -	\$ -	\$ -
4.17	Insurance	-	LS		-	-	\$ -	\$ -	\$ -	\$ -
4.18	Insurance (specialty, e.g. railroad)		Crossing			\$ 1,000	\$ -	\$ -	\$ -	\$ -
4.19	Bonds	1	LS			\$ 106,000	\$ -	\$ -	\$ 106,000	\$ 106,000
4.20	Sales Tax on Materials	8.88%	% of material cost	\$ 970,973.55			\$ 86,222	\$ -	\$ -	\$ 86,222
4.21	Fees for permits, including roadway, railroad, building or other local permits	1	LS			\$ 2,624	\$ -	\$ -	\$ 2,624	\$ 2,624
TOTAL - MOB/DEMOB, ENGINEERING, PERMITTING, T&C, PM & INDIRECTS:							\$ 112,466	\$ 890,875	\$ 154,010	\$ 1,157,351

NEXtera Energy- TO36 Core 1

Other Comp. 138kV Upgrades

Total: \$ 16,870,335

Other Comp. 138kV Upgrades					
	Material Supply	Labor Supply	Equip Supply	Total	
Other Comp. 138kV Upgrades					
1. West Bus-Kings CT Upgrade	\$ 278,435	\$ 158,049	\$ 77,216	\$ 513,700	
2. Newbridge to Ruland 138kV (561Line OH reconductor)- Comp 97	\$ 1,900,000	\$ 950,000	\$ 950,000	\$ 3,800,000	
3. Newbridge to Ruland 138kV (562Line OH reconductor)-Comp 98	\$ 1,977,500	\$ 988,750	\$ 988,750	\$ 3,955,000	
	\$ -	\$ -	\$ -	\$ -	
	\$ -	\$ -	\$ -	\$ -	
	\$ -	\$ -	\$ -	\$ -	
4. MOB/DEMOB, ENGINEERING, PERMITTING, T&C, PM & INDIRECTS:	\$ 451,734	\$ 2,750,045	\$ 443,599	\$ 3,645,378	
CONTRACTOR MARK-UP (OH&P)	\$ 829,380	\$ 872,432	\$ 442,722	\$ 2,144,534	
SUBTOTAL:	\$ 5,437,050	\$ 5,719,276	\$ 2,902,287	\$ 14,058,612	
CONTINGENCY ON ENTIRE PROJECT	\$ 1,087,410	\$ 1,143,855	\$ 580,457	\$ 2,811,722	
TOTAL:	\$ 6,524,459	\$ 6,863,131	\$ 3,482,744	\$ 16,870,335	

Description of Work: 5000KCMIL (Conductor size) (XLPE )armored cable buried below the Long Island Sound (buried 6' or protected by concrete mattresses or rock)										
Item	Item Description	Estimated Quantity	Unit of Measure	Material Supply Rate	Labor Supply Rate	Const. Equipment Rate	Material Supply Cost	Labor Supply Cost	Const. Equipment Cost	TOTAL
Other Comp. 138kV Upgrades										
1. West Bus-Kings CT Upgrade										
1.1	CT Replacement	12	EA	\$ 18,000	\$ 7,970	\$ 3,416	\$ 216,000	\$ 95,641	\$ 40,989	\$ 352,630
1.2	CT Replacement-foundation	60	CY	\$ 704	\$ 804	\$ 503	\$ 42,233	\$ 48,266	\$ 30,167	\$ 120,666
1.3	CT Replacement-structure	12	EA	\$ 1,684	\$ 1,178	\$ 505	\$ 20,202	\$ 14,141	\$ 6,061	\$ 40,404
							\$ -	from	\$ -	\$ -
TOTAL - West Bus-Kings-Pligrim CT Upgrade :							\$ 278,435	\$ 158,049	\$ 77,216	\$ 513,700
2. Newbridge to Ruland 138kV (561Line OH reconductor)- Comp 97										
2.1	138kV Line Upgrade	7.600	MI	\$ 250,000	\$ 125,000	\$ 125,000	\$ 1,900,000	\$ 950,000	\$ 950,000	\$ 3,800,000
							\$ -	\$ -	\$ -	\$ -
TOTAL - Newbridge to Ruland 138kV (561Line OH reconductor) :							\$ 1,900,000	\$ 950,000	\$ 950,000	\$ 3,800,000
3. Newbridge to Ruland 138kV (562Line OH reconductor)-Comp 98										
3.1	138kV Line Upgrade	7.910	MI	\$ 250,000	\$ 125,000	\$ 125,000	\$ 1,977,500	\$ 988,750	\$ 988,750	\$ 3,955,000
							\$ -	\$ -	\$ -	\$ -
TOTAL - Newbridge to Ruland 138kV (562Line OH reconductor) :							\$ 1,977,500	\$ 988,750	\$ 988,750	\$ 3,955,000
							\$ -	\$ -	\$ -	\$ -
							\$ -	\$ -	\$ -	\$ -
							\$ -	\$ -	\$ -	\$ -
							\$ -	\$ -	\$ -	\$ -
							\$ -	\$ -	\$ -	\$ -
							\$ -	\$ -	\$ -	\$ -
							\$ -	\$ -	\$ -	\$ -
Other Comp. 138kV Upgrades							\$ 4,155,935.10	\$ 2,096,798.80	\$ 2,015,966.10	\$ 8,268,700.00
4. MOB/DEMOB, ENGINEERING, PERMITTING, T&C, PM & INDIRECTS:										
	Contractor Mobilization / Demobilization									



Item	Item Description	Estimated Quantity	Unit of Measure	Material Supply Rate	Labor Supply Rate	Const. Equipment Rate	Material Supply Cost	Labor Supply Cost	Const. Equipment Cost	TOTAL
4.1	Mob / Demob	1.0	LS		\$ 123,383	\$ 82,255	\$ -	\$ 123,383	\$ 82,255	\$ 205,638
	Project Management, Material Handling & Amenities									
4.2	Preconstruction Supervision (Engineering, Permitting, Procurement)	1	LS		82,687.00		\$ -	\$ 82,687	\$ -	\$ 82,687
4.3	Construction Project Management / Supervision	1	LS		330,748.00		\$ -	\$ 330,748	\$ -	\$ 330,748
4.4	Utility PM and Project Oversight	1	LS		82,687.00		\$ -	\$ 82,687	\$ -	\$ 82,687
4.5	Site Accommodation, Facilities, Storage	1	LS	82,687.00			\$ 82,687	\$ -	\$ -	\$ 82,687
	Engineering									
4.6	Design Engineering	1.00	LS		\$ 413,435	\$ -	\$ -	\$ 413,435	\$ -	\$ 413,435
4.7	LiDAR	1.00	LS		\$ 14,884	\$ 9,922	\$ -	\$ 14,884	\$ 9,922	\$ 24,806
4.8	Geotech	-	EA		\$ 2,730	\$ 1,820	\$ -	\$ -	\$ -	\$ -
4.9	Surveying/Staking	1.00	Site		\$ 34,729	\$ 23,152	\$ -	\$ 34,729	\$ 23,152	\$ 57,881
	Testing & Commissioning									
4.10	Testing & Commissioning of SS and Equipment	1.00	LS		\$ 60,000		\$ -	\$ 60,000	\$ -	\$ 60,000
	Permitting and Additional Costs									
4.11	Physical Security	-	LS				\$ -	\$ -	\$ -	\$ -
4.12	Environmental Licensing & Permitting Costs & related legal cost	1.00	LS		\$ 82,687		\$ -	\$ 82,687	\$ -	\$ 82,687
4.13	Environmental-special studies/investigation	-	LS		\$ -		\$ -	\$ -	\$ -	\$ -
4.14	Warranties / LOC's	1.00	LS		\$ 24,806		\$ -	\$ 24,806	\$ -	\$ 24,806
4.15	Laydown Lease & temporary easement	1	LS		\$ 1,500,000		\$ -	\$ 1,500,000	\$ -	\$ 1,500,000
4.16	Real Estate ( Acquisition)	1.00	LS				\$ -	\$ -	\$ -	\$ -
4.17	Legal Fees (Real estate)	1.00	LS		-	-	\$ -	\$ -	\$ -	\$ -
4.18	Insurance	-	LS		-	-	\$ -	\$ -	\$ -	\$ -
4.19	Insurance (specialty, e.g. railroad)		Crossing			\$ 1,000	\$ -	\$ -	\$ -	\$ -
4.20	Bonds	1	LS			\$ 320,000	\$ -	\$ -	\$ 320,000	\$ 320,000
4.21	Sales Tax on Materials	8.88%	LS	\$ 4,155,935.10			\$ 369,047	\$ -	\$ -	\$ 369,047
4.22	Fees for permits, including roadway, railroad, building or other local permits	1.00	LS			\$ 8,269	\$ -	\$ -	\$ 8,269	\$ 8,269
TOTAL - MOB/DEMOB, ENGINEERING, PERMITTING, T&C, PM & INDIRECTS:							\$ 451,734	\$ 2,750,045	\$ 443,599	\$ 3,645,378

NEXtera Energy- TO36 Core 1	
ESTIMATE ASSUMPTIONS & CLARIFICATIONS	
General assumptions/clarifications	
1	This TO36 estimating workbook includes the substation and transmission line components listed to the right.
2	Based on 2022 pricing
3	The estimate contains 20% contingency amount. To cover unknow risk allowance. Costs include contractor mark-up (6%-trunkey cost (i.e. HVDC, GIS), 18%-others) for OH and profit
4	Costs have been developed based on historical data from Projects of a similar nature (AACE Class 5 and 4 Estimating Practices). Major equipment pricing is based on budgetary quotes from equipment suppliers. However, we have not engaged any subcontractors or material venders for formal quotes for minor materials.
5	Cost for dust control is excluded, we assume that water trucks for construction are not required.
6	Excavation currently excludes rock. More detail required to quantify rock, as well as construction means and methods allowed. Rock adder is approximately \$405/CY for standard rock excavation.
7	Work schedule assumes working 5 days per week, 10 hours per day. The construction durations for each segment are based on Attachment B.04.1 _Addendum Construction Schedule Revision 0.
8	Pricing assumes union labor will be required.
9	In indirect section, we assume that these construction contracts will be let on an EPC type basis (perhaps progressive design-build or similar contracting model) and that the construction contractor would have significant input into the pre-con planning stage. The project management staffing make up is based on the project scope and duration, for the substation interconnection/upgrade project only assume one construction manager and one environmental coordinator to meet EMCP requirement.
10	Cost s will vary for handling and disposal of contaminated spoils, depending on type of contaminants and availability / location of the appropriate tippy facility. Since there is not enough information to provide a quantified estimate for this item, allowance is included in the contingency monies.
11	An allowance of 5% for transmission design and engineering is included in indirect section, cost of turnkey GIS and HVDC excluded
12	An allowance of 8% for substation design and engineering is included in indirect section, cost of turnkey GIS and HVDC excluded
13	An allowance of 0.3% for GPR of the transmission line is included in indirect section
14	An allowance of 0.7% for survey and staking of the tline and substation layout is included in indirect section, cost of turnkey GIS and HVDC excluded for substations.
15	An allowance of 3.75% for substation testing and commissioning is included in indirect section, cost of turnkey GIS and HVDC excluded
16	An allowance of \$20,000 per circuit for transmission line testing and commissioning is included in indirect section
17	An allowance of 1% for environmental Licensing & Permitting Costs & related legal cost is included in indirect section; and cost for environmental-special studies/investigation is quantified and included for required segment. Cost of turnkey GIS and HVDC excluded for substations.
18	The estimate does not include cost for insurance, assume it will be provided by he owner (i.e. OCIP) . The estimate includes cost for bond (2% of the total contracct value)
19	New York State sales tax of 8.8% is included for all material pricing
20	A mob of 3% and demob of 2% has been included per segment (percentage is based on construction labor and equipment costs), except submarine segment.
21	An allowance of 1% for Preconstruction Supervision (Engineering, Permitting, Procurement) is included in indirect section.
22	An allowance of 4% for Project Management & Staffing (includes PM, Field Engineers / Supervision, Scheduler and Cost Manager, SHEQ Staff, and Admin Staff) is included in indirect section.
23	An allowance of 1% for Utility PM and Project Oversight is included in indirect section.
24	An allowance of 1% for Site Accommodation, Facilities, Storage is included in indirect section.
25	An allowance of 3% of the real estate acquisition cost is included for real estate legal fees.
Tline assumptions/clarifications	
26	Assumed all UG conduits are installed with concrete encasement and no splicing point included inside substations. The conduit trench details please refer to each tab.
27	Not enough detail to quantify existing utility relocation. A plug of \$1M per mile has been included for relocation of existing utilities and \$200K / mile for protection of existing utilities.
28	Traffic control allows for k-rail, metal sheet plates and lane control for underground sections. We have not included for construction of new roads or any permanent traffic measures.
29	The trench excavation width and depth assumed details are shown in each tab.
30	The MH counts are based on our field and desktop review
31	Assumes that 30% of native spoils from vault excavation will be used as backfill.
32	Off haul / disposal spoils quantity includes a 1.3X multiplier for truck load.
33	Assumed asphalt paving repair includes a 2" surfacing course pavement
34	Additional 5% of route length is added to UG cable length, 10% of route length added to submarine cable length
35	All Tline segments construction period is based on milestone schedule provided
36	Spare conduit has been added to all UG conduit system
37	The HDD, jack&bore quantity is based on information provided
38	Existing 138/345kv UG upgrade, assumed no work is required for existing conduit systems, the splice quantity is pending on when the existing splice vault quantity is provided. The 138KV UG conductor cost is based on 4000 kcmil XLPE cable,
39	Assume the cable trench in between transition manholes and transition station will be covered by submarine cable supplier/contractor
40	Please also refer to each tab for component specific assumptions and clarifications
41	Assume the cable trench in between transition manholes and transition station will be covered by submarine cable supplier/contractor
42	The submarine cable quantity and cost are calculated based on # of passes and the total cable length. We assume i.e 3 circuits, 2 cable per circuit, so there are 6 passes.
43	For transmission lines that are routed on the west side of the LI Sound (Bronx and Westchester County) assume 40% rock excavation.
Substation assumptions/clarifications -	
44	Site grading: Excavation quantity in substations is based on 3', fill quantity is based on 60% site borrow and 40% import.
45	Substation new access road access road quantity is based on interior access road only, no new exterior access roads are required based on the plot drawings provided.
46	Substation pad is based on 8" base and 6" surfacing rock.
47	If required, the firewalls for transformers/PAR/Reactors are assumed 30' tall.
48	All of the enclosure buildings are based on dimensions shown on the site plot plan, cost includes pre-engineered building structure, HVAC, mechanical, fire protection.
49	Substation quantity takeoff is based on the plot and one line drawings provided, takeoff assumptions details please see each tab
50	All substation segments construction period is based on milestone schedule provided